

Orosco Concrete And Construction Llc

Angel Orosco
Angelorosco3690@gmail.com
116 N Louisiana Ave, Mangum, Ok
P: 5805637202

Estimate: EST-61

Bill To

City Of Mangum

Estimate Date: 03/09/25

Total: \$7,000.00

Billed Items

Item	Unit Cost	Quantity	Cost
Labor bid for concrete colvert. Approximately 5ftx 3ft x32ft long. Demo existing culvert and road way. Install new steam walls with footer 32ft x3ftx 10in. With a #4 rebar mat 1ft o.c. 4000psi concrete mix. Concrete Culvert floor will 5ftx32ftx4in with #4rebar mat 2ft o.c 4000psi concrete mix. Top of culvert will be 10ftx32ftx10in deep double mat #4 rebar 1ft o.c.Header walls will be approximately 7ftx5ftx12in with #4 rebar mat and 3500psi concrete mix. City of mangum will provide all materials. Demo and haul off City materials cost will be approximately 7500 dollars	\$7,000.00	1	\$7,000.00

Bill To

City Of Mangum
mangumlibrary@gmail.com

Subtotal \$7,000.00

Total: \$7,000.00 (USD)