PROPOSAL

LONE STAR PAVING

11675 JOLLYVILLE RD, SUITE 150
AUSTIN, TX 78759

Phone #
(512)-428-5778

Date	Estimate No.
2/12/2024	JMW-54036-001

Project

CAP METRO BCT FUNDED PAVING IMPROVEMENTS

CHANGE ORDER

PRICING VALID FOR CONSTRUCTION THROUGH 9/1/2024 (IF CONSTRUCTION EXTENDS PAST 9/1/2024, ADDITIONAL COSTS WILL BE ADDED TO UNIT PRICES)

ADDITIONAL TIME NEEDED: 10 DAY

Item No.	Description	Qty	U/M	UNIT PRICE	Total
1	LEXINGTON ST: REMOVE MEDIAN, EXCAVATE 10", REPLACE WITH 8" TY B PG64-22 HMA, REPLACE CURB	1.00	LS	$60,652.15	$60,652.15
2	ADDED PAVEMENT MARKINGS TO LEXINGTON ST	1.00	LS	$6,727.50	$6,727.50
3	2" HMAC TYPE D, PG64-22 PAVEMENT OVERLAY	115.00	SY	$17.00	$1,955.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					$0.00
					Total
					$69,334.65

Estimator
Jon Wickes
jwickes@lspaving.com
512-269-2195

We acknowledge receipt of the following Addendum----> ADDENDUM NO. N/A

PRICING FOR THIS WORK EXPIRES IN 30-DAYS FROM BID DATE UNLESS THIS PROPOSAL/ESTIMATE IS ACCEPTED AND RETURNED SIGNED.

Terms & Conditions

EXCLUDES - PERMITS, UTILITY ADJUSTMENTS, LAYOUT OR SURVEYING, SAFETY SLOPE INSTALL/REMOVAL; Material Sales Tax; TESTING (OTHER THAND FOR OUR ASPHALT ITEMS); POLICE OFFICERS; MESSAGE BOARDS; TMAS

MIX DESIGN: JOB MIX FORMULA IS CERTIFIED IN ACCORDANCE WITH TXDOT CONSTRUCTION BULLETIN C-14, AS MODIFIED BY TEST METHOD TEX-204-F AND TEXDOT ITEM 340; ASPHALT CONTENT (PG76-22) FOR TYPE C MIXES; ASPHALT CONTENT (PG76-22) FOR TOM MIXES. ALL MATERIALS ARE GUARANTEED TO BE AS SPECIFIED. ALL MATERIALS QUOTED WITH SAC B AGGREGATES WITH RAP UNLESS NOTED OTHERWISE.

LONE STAR PAVING WILL EXECUTE ONLY THOSE ITEMS OF WORK LISTED IN THE "SCOPE OF WORK" ABOVE. ANY ADDITIONAL ITEMS OF WORK WILL REQUIRE A WRITTEN CHANGE ORDER IN ADVANCE. LONE STAR PAVING IS NOT RESPONSIBLE FOR DRAINAGE ISSUES ON SLOPES LESS THAN 2%. ALL QUANTITY OVERRUNS WILL BE VERIFIED IN PLACE UPON COMPLETION AND BILLED AT UNIT PRICES SHOWN ABOVE.

Terms & Conditions

All agreements must be made in writing. Asphalt paving standards for newly constructed areas are proposed to comply with the Texas Department of Transportation hot mix standards. Other paving specifications must be specifically outlined. All permits and fees are excluded unless otherwise noted. Lone Star Paving is not responsible for utility lines less than 12 inches deep. Lone Star Paving will carry Workers Compensation, General Liability and Auto Insurance for labor provided in the performance of this contract. The amounts included in this estimate are based on information provided and are subject to change if new information is provided or differing site conditions are encountered. The contractor is responsible for the paving surface. From time to time, the paving surface may have areas whereby additional hot mix must be applied to achieve desired results, the fees for these additional amounts of materials will be discussed and agreed to prior to commencement of work. All changes in the scope of the work must be agreed prior to the commencement of work. Fees for our services are due 30 days from the date of the invoice. Payments should be remitted to Asphalt Inc., LLC d/b/a Lone Star Paving , PO Box 200608, Austin, Tx 78720. Interest shall accrue for all amounts past due at the rate of eighteen percent (18%) compound interest per annum or highest legal limit. The Contractor agrees to pay reasonable attorney fees, expert fees, all costs of court, and any other expenses incurred by Asphalt Inc in the collection of any sums due under the performance of this contract. The venue for any legal action under this contract shall be Bexar County, Texas. The parties expressly agree to waive the right to a jury trial. Pricing based on a mutually agreeable contract.

The above prices, specifications, and conditions are satisfactory and are hereby accepted. Payment will be made as outlined above.

Accepted by: _____ Date: _____

Title: _____

Company Name: _____