



# Proposal

Think Safety!

12000 West Parmer Lane  
 Phone: 512-250-2910 Fax: 512-250-1960

Date 12/18/2023  
 Proposal #: Timmermann Park

**Project Name:** Lighting for Walking Trail/Sidewalk with Receptacles  
 Timmermann Park  
 Manor, Texas

**Estimator:** Steven Shepherd  
 830-832-4117

Type of Field:	Walking Trail/Sidewalk
Photometrics	LSI Lighting
Type of Fixture:	LSI Lighting

Quantity:	Description:
1	Unload and Store New Lighting System
1	Installation of 26 Duplex Receptacles Along the Walking Trail.
1	Installation of 26 New 20A Single Pole Circuit Breakers. Each Receptacles will be on a Dedicated Circuit.
1	Installation of One 20A 240V Circuit to all Poles
1	Installation of New Luminaires and 15' Poles
1	Connection to Wiring at Base of Poles
1	Photocell Will be Installed on Each Light Fixture for Controls

Walking Trail/Sidewalk with LSI Lighting Turnkey Installed \$326,460.00  
 Buy Board was Applied to the Price Listed

Project Notes:
* Customer shall pay all taxes, duties, levies or fees.
* Based on normal soil conditions.
* Based on having full access to the walking trail/sidewalk.
* Based on 240V available being available on the exterior of the small building by the Skimmer Road parking lot.
* Based on existing 240V panel having enough spaces available for all the new circuit breakers.



**SPORTS LIGHTING DIVISION**  
 BUILDING FOR SPORTS FROM START TO FINISH