



January 5, 2024

Bid Proposal- City of Manor Ring Road Sidewalk

We are pleased to quote all labor, materials, equipment, insurance, and incidentals necessary to complete the above reference project:

Alternate 740' X 8' Sidewalk:

- Excavate 12" below finish grade
- Spread spoils beside sidewalk
- Compact subgrade
- Place geotextile fabric
- Place 8" sand
- Place #3 Rebar 12" O/C
- Place redwood expansion joints every 40'
- Place 4" class A 3,000 psi concrete
- Saw control joints every 5'

Total: \$77,000.00

Respectfully,
Smith Paving Inc.
Casey Smith
512-917-1142 – Mobile
512-233-4444 – Office
512-280-5545 – Fax
Smithpaving99@yahoo.com