

STATE OF TEXAS       §  
                                  §  
COUNTY OF TRAVIS   §

**PETITION FOR VOLUNTARY ANNEXATION  
OF PROPERTY INTO THE CITY LIMITS  
OF THE CITY OF MANOR, TEXAS**

**To the Mayor and City Council of the City of Manor, Texas:**

The undersigned owner or agent of a tract of land being a portion of the right-of-way of Old Kimbro Road in Travis County do hereby request and petition the City of Manor (“City”), pursuant to the Texas Local Government Code, to extend the present corporate limits of the City and annex the right-of-way more fully described in Exhibit A, which description is attached and incorporated herein for all purposes.

I/We certify and swear that:

1. Travis County is the owner or agent of the road right-of-way described in Exhibit A; and
2. This request for annexation of the tract by Manor is made voluntarily.

Travis County

By:


DocuSigned by:  
  
C21317DB291D47D...  
Name       County Judge  
Address:   700 Lavaca St, 2nd Floor  
              Austin, TX 78701  
Date :     2/3/2023 | 1:52 PM PST

EXHIBIT A  
Right of Way Legal Description



10090 W Highway 29 | Liberty Hill, Texas 78642  
TBPELS Firm No. 10001800 | 512-238-7901 office

EXHIBIT "A"

METES AND BOUNDS DESCRIPTION

BEING 2.855 ACRES OF LAND SURVEYED BY LANDESIGN SERVICES, INC., SITUATED IN THE A.C. CALDWELL SURVEY NO. 52, ABSTRACT NO. 154, IN TRAVIS COUNTY, TEXAS AND BEING A PORTION OF THE EXISTING RIGHT-OF-WAY OF OLD KIMBRO ROAD (OLD STATE HWY 20 - 80' R.O.W.), DESCRIBED IN A DEED TO THE STATE OF TEXAS, RECORDED IN VOL. 482, PG. 419, OF THE DEED RECORDS OF TRAVIS COUNTY, TEXAS (D.R.T.C.T.), AND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

**BEGINNING** at a 1/2-inch iron rebar with cap stamped "4WARD BOUNDARY" found at the intersection of the existing Southerly right-of-way line of U.S. 290 (R.O.W. Varies) and the existing Easterly right-of-way line of said Old Kimbro Road, for the Westerly common corner of a called 62.8431 acre tract of land described in a General Warranty Deed to Jefferson Triangle Marine, L.P., recorded in Document No. 2008096315 of the Official Public Records of Travis County, Texas (O.P.R.T.C.T.) and of a called 4.382 acre tract of land described in a Warranty Deed with Vendor's Lien to Auspro Enterprises, L.P., recorded in Document No. 2019013915 of said O.P.R.T.C.T.;

THENCE **South 26°27'38" West** with the existing Easterly right-of-way line of said Old Kimbro Road and the common Westerly line of said 62.8431 acre tract, a distance of **1,403.61** feet to a 1/2-inch iron rebar found for the Westerly common corner of said 62.8431 acre tract and of a called 56.652 acre tract of land described in a General Warranty Deed to Horsefeathers Farms, Inc., recorded in Document No. 2002187747 of said O.P.R.T.C.T.;

THENCE **North 64°02'06" West** over and across the existing right-of-way of said Old Kimbro Road a distance of **79.52** feet to a Calculated Point in the existing Westerly right-of-way line of said Old Kimbro Road and the common Easterly line of Lot 7, KIMBRO BUSINESS PARK, a subdivision of record in Volume 86, Page 187D, of the Plat Records of Travis County, Texas (P.R.T.C.T.);

THENCE **North 25°57'54" East** with the existing Westerly right-of-way line of said Old Kimbro Road and the common Easterly line of said Lot 7, a distance of **126.53** feet to a 1/2-inch iron rebar found for the Northeast corner of said Lot 7;

THENCE **North 72°12'08" West** with the existing Westerly right-of-way line of said Old Kimbro Road and the common Northerly line of said Lot 7, a distance of **4.94** feet to a Calculated Point for the Southeast corner of Lot 6, REPLAT OF LOTS 3,4,5 AND 6 KIMBRO BUSINESS PARK, a subdivision of record in Volume 93, Page 17 of said P.R.T.C.T.





THENCE with the existing Westerly right-of-way line of said Old Kimbro Road and the common Easterly line of said REPLAT OF LOTS 3,4,5 AND 6 KIMBRO BUSINESS PARK, the following five (5) courses and distances:

1. **North 26°35'54" East** a distance of **248.92** feet to a Calculated Point for the Easterly common corner of said Lot 6 and of Lot 5, REPLAT OF LOTS 3,4,5 AND 6 KIMBRO BUSINESS PARK;
2. **North 26°03'55" East** a distance of **26.15** feet to a Calculated Point;
3. **North 26°26'49" East** a distance of **284.11** feet to a Calculated Point for the Easterly common corner of said Lot 5 and of Lot 4, REPLAT OF LOTS 3,4,5 AND 6 KIMBRO BUSINESS PARK;
4. **North 26°28'40" East** a distance of **497.03** feet to a Calculated Point; and
5. **North 09°25'54" West** a distance of **150.32** feet to a Calculated Point at the intersection of the existing Westerly right-of-way line of said Old Kimbro Road and the existing Southerly right-of-way line of said U.S. 290, for the Northeast corner of said Lot 4;

THENCE **North 86°19'03" East** with the existing Southerly right-of-way line of said U.S. 290, over and across the existing right-of-way of said Old Kimbro Road, a distance of **200.20** feet to the **POINT OF BEGINNING** and containing 2.855 acres of land, more or less;

This project is referenced for all bearing and coordinate basis to the Texas State Plane Coordinate System, North American Datum of 1983 (NAD83 - 2011 adjustment), Central Zone (4203). Distances and Areas shown hereon are Grid values represented in U.S. survey feet.

This property description accompanies a separate plat of even date and was prepared by an on the ground survey made under my supervision during the month of September, 2022.

*Frank W. Funk* 09/20/2022


Frank W. Funk  
Registered Professional Land Surveyor  
State of Texas No. 6803



Job Number: 21-021

Attachments: K:\21021 - JTM OLD KIMBRO RD\CAID\DWG\OLD KIMBRO ROAD ROW.DWG







LINE TABLE		
LINE #	BEARING	DISTANCE
L1	N64°02'06"W	79.52'
L2	N25°57'54"E	126.53'
L3	N72°12'08"W	4.94'
L4	N26°03'55"E	26.15'
L5	N09°25'54"W	150.32'
L6	N86°19'03"E	200.20'

GENERAL NOTES:

THIS PROJECT IS REFERENCED FOR ALL BEARING AND COORDINATE BASIS TO THE TEXAS COORDINATE SYSTEM, NORTH AMERICAN DATUM OF 1983 (NAD83 - 2011 ADJUSTMENT), CENTRAL ZONE (4203).

DISTANCES AND AREAS SHOWN HEREON ARE SURFACE VALUES REPRESENTED IN U.S. SURVEY FEET BASED ON A GRID-TO-SURFACE COMBINED ADJUSTMENT FACTOR OF 1.00005359.

SOME FEATURES SHOWN HEREON MAY BE OUT OF SCALE FOR CLARITY.

JOB NUMBER: 21-021		DATE: 09/19/2022	
PROJECT NAME: JTM OLD KIMBRO RD			
DRAWING NAME: OLD KIMBRO ROAD ROW			
DRAWING FILE PATH:			
K:\21021 - JTM OLD KIMBRO RD\CAD\DWGS			
METES AND BOUNDS FILE PATH:			
K:\21021 - JTM OLD KIMBRO RD\DESCRIPTIONS			
RPLS: FWF	TECH: JRM	PARTY CHIEF: N/A	CHK BY: HAS
SHEET 04 of 04	FIELDBOOKS N/A	SCALE: 1" = 200'	



10090 W HIGHWAY 29, LIBERTY HILL, TEXAS 78642  
 TBPELS FIRM NO. 10001800  
 512-238-7901