



Hydro-Klean, LLC
333 NW 49th Place
Des Moines, IA, 50313
Phone: 515-283-0500

Quote

Quote Nbr.: PQ004397
Order Date: 02/14/2025
Valid Until: 05/15/2025
Sales Person: Jake Nanti
Customer ID: 100474
Payment Terms: Net 30 Days

Job Site:

City of Marshall, MN
344 W. Main Street
Marshall MN 56258
United States of America

Bill to:

City of Marshall, MN
344 W. Main Street
Marshall MN 56258
United States of America

Job Description

Projected probable project cost to perform the following tasks on a unit cost basis: Variations in the work scope will require execution of a change order.

Manholes #38 & #37

HK Solutions Group will provide all equipment, labor, and material to remove existing castings, demo existing chimney sections, rebuild existing bench and inverts as needed providing smooth flow lines from inlet piping to outlet piping, internally bypass and block-out any inside mainline or lateral drop pipe connections, Monoform new wall sections with formed concentric cone to elevation, set new Neenah R1550 castings at grade, and provide concrete hi-early strength concrete pavement patch surface restorations as required.

Manholes #20 & #45

HK Solutions Group will provide all labor, equipment, and material to prepare and install HDPE linings at a (2) severely corroded manholes. The manholes will be reconstructed via installation of a new 3" thick monolithic concrete wall and finish top section as an concentric flat-top with an integrated 3mm Agru Sure-Grip lining. Manhole bench and inverts will be repaired to provide smooth flowlines from inlet to outlet piping w/ embedded 5mm HDPE Agru base. A new cast iron casting (provided by HK) will be set at grade and provide a high-early DOT 9"t concrete surface restoration. Truck and trailer access to the manhole structure is required.

Our only request is that the city of Marshall, MN pick up and dispose of the construction debris (pavement, chimney demo rubble, etc.) and provide traffic control (if needed). Pricing per manhole unit is complete including a charge for crew & equipment mobilization covering travel time, fuel, crew lodging and per-diems.

RESC. QTY.	ITEM	QTY.	UOM	PRICE	Amount
	Monoform Plus MH 9SE #45	1.0000	EACH	39,700.0000	39,700.00
	Monoform Plus MH 10SW #20	1.0000	EACH	37,450.0000	37,450.00
	Monoform (Traditional) MH 9SW #37	1.0000	EACH	22,950.0000	22,950.00
	Monoform (Traditional) MH 9SE #38	1.0000	EACH	22,950.0000	22,950.00

***NOTE: Quote does not include any applicable taxes**

Prepared By: Jake Nanti
Approved By: Wade Anderson

Accepted By: _____
Date: _____
PO#: _____

***Quote Total:** 123,050.00