



CITY OF MARSHALL AGENDA ITEM REPORT

Meeting Date:	Tuesday, April 13, 2021
Category:	AWARD OF BIDS
Type:	ACTION
Subject:	Project Z78: Storm Structure Outfall Improvements Project - Consider Resolution Accepting Bid (Awarding Contract).
Background Information:	<p>The purpose of this project is to add stormwater manholes at two different locations to aid City staff with flood fighting operations when we have high water events in County Ditch 70 (CD 70) and the Redwood River Diversion Channel. This project spawned from City staff experience with the high-water events of 2018 and 2019.</p> <p><u>S. Saratoga Street:</u> The proposal at this location includes the installation of a storm water manhole on the west side of S. Saratoga Street near the bend of CD 70. The City has a 30" storm water outfall at this location that drains the Carr Estates neighborhood. Staff is also proposing to install an in-line backflow preventer in the stormwater pipe to help prevent CD 70 from backing into the City storm sewer system during high water events. The new manhole will provide City staff with a suitable location to install pumps in the event of high-water levels in CD 70 preventing free discharge of the industrial park drainage system.</p> <p><u>Redwood River Diversion Channel:</u> The proposal at this location includes the installation of a storm water manhole just upstream of a 54" storm water outfall into the Diversion Channel. The location of this installation is approximately 775-FT east of US 59, near 800 N US 59. The new manhole will provide City staff with a suitable location to install pumps in the event of high-water levels in the Diversion Channel.</p> <p>Bids were received on April 2, 2021 for the above-referenced project. Five bids were received as shown on the attached resolution awarding contract. The apparent low bid was received from R&G Construction Co. of Marshall, Minnesota, in the amount of \$49,358.10.</p>
Fiscal Impact:	The engineer's estimate for the construction is approximately \$56,165. The total project cost estimate is \$60,118, including 5% contingency and 16% engineering. The project was originally included in the 2020 CIP. We did not complete the project in 2020 due to US Army Corps of Engineers permitting concerns. The project was carried over into the 2021 CIP and will be funded by the Surface Water Management Utility.
Alternative/ Variations:	No alternative actions recommended.
Recommendation:	that the Council adopt RESOLUTION NUMBER 21-027, which provides for the Resolution Accepting Bid (Awarding Contract) and authorizing entering into an agreement with R&G Construction Co. of Marshall, Minnesota, in the amount of \$49,358.10, for Project Z78.

RESOLUTION NUMBER 21-027

RESOLUTION ACCEPTING BID (AWARD CONTRACT)

WHEREAS, pursuant to an advertisement for bids for the following project:

PROJECT Z78: STORM STRUCTURE OUTFALL IMPROVEMENTS PROJECT -- This project consists of the following: Installation of stormwater manholes on South Saratoga Street south of Continental Street and adjacent to the north bank of the Redwood River Diversion Channel approximately 800 feet east of US 59. This project will also include installation of a check valve and turf restoration.

bids were received, opened and tabulated according to law, and the following bids were received complying with the advertisement:

Bidder	Bid Amount
R&G Construction Co. Marshall, MN	\$49,358.10
D&G Excavating, Inc. Marshall, MN	\$52,980.00
Duininck, Inc. Prinsburg, Minnesota	\$54,578.00
Towne & Country Excavating LLC Garvin, MN	\$65,707.50
Kuechle Underground, Inc. Kimball, MN	\$66,838.00

AND WHEREAS, it appears that R&G Construction Co. of Marshall, Minnesota, is the lowest responsible bidder.

NOW THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF MARSHALL, MINNESOTA:

1. The Mayor and City Clerk are hereby authorized and directed to enter into a contract with R&G Construction Co. of Marshall, Minnesota, in the amount of \$49,358.10, in the name of the City of Marshall for the above-referenced project, according to the plans and specifications therefore approved by the City Council and on file in the office of the City Clerk.

Passed and adopted by the City Council this 13th day of April, 2021.

ATTEST:

City Clerk

Mayor

This Instrument Drafted by:
Jason R. Anderson, P.E.
Director of Public Works/City Engineer