



**CITY OF MARSHALL  
AGENDA ITEM REPORT  
PI/T – 11/25/2025**

<b>Presenter:</b>	Jason Anderson
<b>Meeting Date:</b>	Tuesday, November 25, 2025
<b>Category:</b>	NEW BUSINESS
<b>Type:</b>	ACTION
<b>Subject:</b>	Project ST-020: S 5th Street (Saratoga to Main) Reconstruction Project
<b>Background Information:</b>	<p>This project consists of the following work: complete street reconstruction of S. 5<sup>th</sup> Street from approximately 300-FT west of W. Main Street to W. Saratoga Street. Reconstruction includes the intersection of W. Saratoga Street and S. 5<sup>th</sup> Street, and work items include: curb and gutter, driveway approaches, and sidewalks. Underground utility work includes sanitary sewer main and services, water main and services, and storm sewer replacement.</p> <p>The street section will be a typical Marshall residential street design with 4" of bituminous surfacing over 12" Class 5 aggregate base, with geotextile fabric separation between the gravel base and the subgrade, and drain tile behind both sides of the curb to ensure a well-drained street section. Sidewalk is located on both sides of the existing street, and the project proposes to replace on both sides with 5-FT wide sidewalk.</p> <p>The existing street width is 43.5-FT as measured from back of curb to back of curb. The proposed street width is 38-FT as measured from back of curb to back of curb. Because we are starting "mid-block" with this reconstruction project, the narrowing of the street will begin just west of the alley and will occur along the south curbline to ensure that snowplows are able to follow the curb taper with their direction of travel. At the end of the curb taper (heading west toward Saratoga), the street alignment will shift slightly to the south to align S. 5<sup>th</sup> Street to the center of the right of way by the time the street reaches its intersection with W. Saratoga Street.</p>
<b>Fiscal Impact:</b>	This project is identified in our CIP at \$1,235,219. Estimated total cost and cost splits will be further refined as staff works further into project design.
<b>Alternative/ Variations:</b>	No alternative actions recommended.
<b>Recommendations:</b>	PI/T Committee concurrence with the project considerations identified above.