



HIPERLINE
HIGH PERFORMANCE LINING

Manhole Quote

Sold To Roger Cauwels
Marshall, MN
Roger.Cauwels@ci.marshall.mn.us
[1 \(507\) 530-8002](tel:15075308002)

Date 5/17/2023

PO No.

Manhole	Location	Depth (ft)	Description of Repair	Mobilization:	Cost
1	10 SW 8	21.20	SpectraShield, Old Precast, Grout High leaks	\$1,800.00	12,826.00
2	10NW26	8.20	Grout Only, Grout Medium leaks		1,180.80
3	10SW4A	8.60	Grout Only, Grout Medium leaks		1,238.40
4	10SW4	9.00	Grout Only, Grout High leaks		1,674.00
5	9SW32	16.80	SpectraShield, Old Precast 5' Diameter, Grout High leaks, Remove Old Liner		14,733.60
6	9SW30	16.90	SpectraShield, Old Precast 5' Diameter, Grout High leaks, Remove Old Liner, Bypass		15,489.30
7	8NE23	13.90	Grout Only, Grout Low leaks		1,459.50
8	5NE4	17.11	Grout Only, Grout High leaks		3,182.46
9	5NE3	17.70	Grout Only, Grout Medium leaks		2,548.80
Total					\$56,132.86

*Clarice
Nawakama
Floyd wild
Drive
Hwy 23d
Saratoga
Southview
N 11th
St*

Notes:

- A site visit is agreed upon prior to mobilization if deemed necessary by HIPERLINE.
- Owner shall be responsible for providing a disposal site for all debris during the installation of the SpectraShield Liner System. This debris shall include, but not be limited to sand, chipped concrete, old linings, effluents, etc.
- Invoice(s) will be based upon field measurements and may increase or decrease the actual invoice/contract/purchase order amount accordingly.
- Our invoices are NET 30 DAYS, no retainage. A 1.5% interest charge per month for invoices over 30 days will apply.
- Sanitary sewer manholes include our industry leading 10 year warranty; storm sewer structures come with a standard 1 year warranty
- Removing manhole steps is part of the standard process unless noted otherwise
- If excessive grouting/leak-stopping is required (more than 1 workday), we will notify customer before proceeding. Additional grouting rates are \$300 per hour for the truck and crew, \$100 per gallon of grout, and \$25 per tube of grout

Customer Name

Customer Signature

Send Invoice To

10SW4 is currently figured for only grouting but should be SpectraShield Lined if budget allows. To line this structure it would be an additional cost of \$3,771.00.

Additional Notes:

Throughout the surface preparation process if Hiperline determines a particular structure is too corroded to successfully rehabilitate the structure, Hiperline will notify the owner and the owner will only be invoiced a crew rate of \$350 per hour for the time the crew spent at that particular structure. If the owner would like Hiperline to install the SpectraShield Liner regardless, then for that particular structure our standard 10 year warranty will not apply and the specific structure will not come with a warranty.

Thanks for the Opportunity to Serve You!

HIPERLINE 15725 US HWY 12 SW Cokato, MN 55321 320.286.2471