

SCOTT

CONSTRUCTION, INC.

ASPHALT SURFACING SINCE 1926

ROADS • STREETS • HIGHWAYS • DRIVEWAYS • PARKING LOTS

www.scottconstruct.com

Ph. 608-254-2555

In WI: 800-843-1556

Fax: 608-254-2249

560 MUNROE AVE., P.O. BOX 340 LAKE DELTON, WI 53940

"An Equal Opportunity Employer."

Submitted To:	Contact:	Proposal/Date:
CITY OF MAUSTON	C/O ROB NELSON	
JUNEAU COUNTY	PUBLIC WORKS DIRECTOR	S0290507
1260 NORTH ROAD	- -	3/18/2025
MAUSTON, WI 53948	prevailing wage determination number:	None Provided

Asphaltic Chip Seal Surfacing for Pavement Maintenance and Preservation

Includes men and equipment to sign work zone and thoroughly clean existing pavement with a combination self-propelled power broom/mechanical blower, furnish cold mix patch material and pot hole hand patch prior to chip seal surfacing.

Polymer-Modified Liquid Asphalt blended at a State of Wisconsin and AASHTO certified liquid asphalt production facility; furnished, heated to 180 degrees F and applied in a single pass up to 24 feet wide.

Scott Construction Inc. to furnish, load, haul and place cover aggregate, in a single pass up to 24 feet wide, using a self-propelled chip spreader and compact using a rubber tire and/or combination rubber tire/steel wheel self-propelled roller.

ALL WORK INCLUDES CRACK FILL PRIOR TO DOUBLE CHIP SEALING USING DARK GRANITE CHIP AND ALL PAINT MARKINGS TO BE REPLACED AFTER CHIP SEALING.

HIGHVIEW ST. - MARTIN ST. TO PEARL ST. (1,284' X 29') TOTAL = \$47,622.81

LOOMIS DR. - GROVE ST. TO ARLINGTON AVE. (895' X 36') TOTAL = \$23,311.00

COLFAX ST. - MONROE ST. TO SHERMAN ST. (1,175' X 33') TOTAL = \$24,381.50

ELM ST. - WEST AVE. TO GRAYSIDE AVE. (2,239' X 32') TOTAL = \$20,684.48

GRAND TOTAL = \$115,999.79

ONE YEAR WARRANTY ON ALL MATERIAL AND LABOR FROM DATE COMPLETED.

ALL WORK TO MEET OR EXCEED THE CITY OF MAUSTON'S SPECIFICATIONS

If SCI determines the scope and/or quantity of work to be performed under contract differs from this proposal, SCI retains the right to price adjust prior to commencement of the work.

Payment Terms: Net 30

NOTE: This proposal may be withdrawn by us if not accepted within 30 days from issue date.

Acceptance of Proposal -- The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance: _____

Customer Signature(s): _____

SCI Representative Signature:  _____ Steve Bezemek

SCOTT

CONSTRUCTION, INC.

ASPHALT SURFACING SINCE 1926

ROADS • STREETS • HIGHWAYS • DRIVEWAYS • PARKING LOTS

When Scott Construction, Inc. does your **SEAL COAT** surfacing, we will use the finest equipment and the best trained personal in the industry.

The equipment, numbers of pieces of each, and the number of employees involved, are as follows:

EQUIPMENT # of PIECES

- 1 – Chip spreader (Full width)
- 2 - Distributor (s) (Full width)
- 5 - Dump trucks
- 1 – Patch/Sweeper Truck
- 2 - Rubber or Steel Roller
- 1 - End Loader
- 1- Supervisor- Regional Mgr.
- 1 – Foreman Pick - up
- 1 - Maintenance Pick - up
- 1 - 20,000 gallon asphalt heating tank
- 1 - Laborer (s)
- 1 – Grader (If Necessary)
- 1 – Water Truck (If Necessary)

Other

EMPLOYEES

- 1- Operator & Front-end
- 2 - Operators
- 5 - CDL Truck Drivers
- 2 - Truck Driver & Labor
- 1 – Operator
- 0 - Used to load aggregate
- 1 - Supervisor
- 1 - Foreman
- 1 - Mechanic
- 0 - Used to heat Hot Asphalt
- 1 - All around worker
- 1 - Operator
- 1 - Operator

Respectfully submitted by Steve Bezemek

2025 SEASON

ASPHALT MAINTENANCE AND CONSTRUCTION