

# SCOTT

CONSTRUCTION, INC.

ASPHALT SURFACING SINCE 1926

ROADS • STREETS • HIGHWAYS • DRIVEWAYS • PARKING LOTS

www.scottconstruct.com

Ph. 608-254-2555

In WI: 800-843-1556

Fax: 608-254-2249

560 MUNROE AVE., P.O. BOX 340 LAKE DELTON, WI 53940

Submitted To:	"An Equal Opportunity Employer."	Proposal/Date:
CITY OF MAUSTON	C/O ROB NELSON	
JUNEAU COUNTY	PUBLIC WORKS DIRECTOR	S0290507
1260 NORTH ROAD	- -	3/4/2024
MAUSTON, WI 53948	prevailing wage determination number:	None Provided

## Asphaltic Chip Seal Surfacing for Pavement Maintenance and Preservation

Includes men and equipment to sign work zone and thoroughly clean existing pavement with a combination self-propelled power broom/mechanical blower, furnish cold mix patch material and pot hole hand patch prior to chip seal surfacing.

Polymer-Modified Liquid Asphalt blended at a State of Wisconsin and AASHTO certified liquid asphalt production facility: furnished, heated to 180 degrees F and applied in a single pass up to 24 feet wide.

Scott Construction Inc. to furnish, load, haul and place cover aggregate, in a single pass up to 24 feet wide, using a self-propelled chip spreader and compact using a rubber tire and/or combination rubber tire/steel wheel self-propelled roller.

### E. MILWAUKEE ST. - DIVISION TO TERMINAL – APPROX. (826 FT X 29 FT – 30 FT)

**DOUBLE CHIP SEAL USING DARK GRANITE CHIP INCLUDING ALL CRACK FILLING PRIOR TO CHIP SEALING AND ANY PAINT MARKINGS BEING REPLACED AFTER COMPLETION. TOTAL = \$17,629.17**

### CITY SHOP PARKING AREAS ON NORTH RD. - ALL PARKING AREAS AROUND DPW SHOP

**DOUBLE CHIP SEAL USING DARK GRANITE CHIP INCLUDING ALL CRACK FILLING PRIOR TO CHIP SEALING AND ANY PAINT MARKINGS BEING REPLACED AFTER COMPLETION. TOTAL = \$41,519.96**

### MILL ST. - LACROSSE ST. TO WATER ST. - APPROX. (713 X 30 FT – 33 FT)

**DOUBLE CHIP SEAL USING DARK GRANITE CHIP, INCLUDING ALL CRACK FILLING PRIOR TO CHIP SEALING AND ANY PAINT MARKINGS BEING REPLACED AFTER COMPLETION. TOTAL = \$14,788.20**

### MAUGHS ST. - WATER ST. TO TERMINAL – APPROX. (1,516 FT X 32 FT – 34 FT)

**DOUBLE CHIP SEAL USING DARK GRANITE CHIP, INCLUDING ALL CRACK FILLING PRIOR TO CHIP SEALING AND ANY PAINT MARKINGS BEING REPLACED AFTER COMPLETION. TOTAL = \$30,726.46**

**GRAND TOTAL FOR ALL PROJECTS = \$104,663.79**

ONE YEAR WARRANTY ON ALL MATERIAL AND LABOR FROM DATE COMPLETED.

ALL WORK TO BE COMPLETED PRIOR TO OCTOBER 1<sup>ST</sup> 2024

ALL WORK WILL BE PERFORMED TO MEET OR EXCEED THE CITY OF MAUSTON'S SPECIFICATIONS

If SCI determines the scope and/or quantity of work to be performed under contract differs from this proposal, SCI retains the right to price adjust prior to commencement of the work.

Payment Terms: Net 30

NOTE: This proposal may be withdrawn by us if not accepted within 30 days from issue date.

**Acceptance of Proposal** -- The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance: \_\_\_\_\_

Customer Signature(s): \_\_\_\_\_

SCI Representative Signature:  \_\_\_\_\_ Steve Bezemek