

May 22, 2026

Quote Number: 9408

To: City of McCleary

Project: Well No. 3 Remote-IO Upgrade

Corporate Office
2303 196th Street SW
Lynnwood, WA 98036
Tel 425.775.5696
TSIcontrols.com

Technical Systems, Inc. (TSI) is pleased to provide a quote for upgrading Well No. 3 Remote-IO system.

Bid Items

Bid Item #	Bid Item Description	Price
1	Well No. 3 Controls Upgrade This work includes replacing the existing wireless-IO system with a new Remote-IO system connected by fiber optic cable to the existing Well No. 2 PLC including: • Supply RIO hardware and associated equipment: ○ Schnieder Electric – Modicon Edge I/O system ▪ Network interface module (Ethernet) ▪ Power supply and base module ▪ Discrete input module, 16-pt, 24VDC ▪ Discrete output module, 8-pt, 24VDC ▪ Analog input module, 4-pt ○ Wiring, terminals, labels, etc. as required for Well No. 3 control panel wiring modifications. • Updated wiring diagrams and layout drawings for control panel modifications. • Programming modifications to existing PLC. • Onsite installation, configuration, and testing of the RIO hardware.	\$10,608.00
	8.9% TAX:	\$944.11
		Total Bid: \$11,552.11

Notes:

- Quote valid for 90 days from bid date.
- Bonding can be provided at an additional cost.
- Fiber optic cable, patch panels, and fiber/copper converters are currently installed in the control panels and ready to connect to new RIO system.

Please feel free to contact me to discuss any questions or comments you may have regarding this quotation.

Sincerely,

Steve DeHaan, P.E.
(425) 678-4142
steved@tsicontrols.com



Leaders in Integrated Water Solutions Since 1970