

7900 46th Avenue North • St. Petersburg, FL 33709 • Phone: (727) 322-8080

Megan Wepfer Phone: 7275438154

300 Municipal Dr. Madeira Beach, 33708

Description

Job Address: 300 Municipal Dr. Madeira Beach, FL 33708

Print Date: 1-9-2023

Megan Wepfer- Scope of Work- Parks

Walkways
Description
Machine excavate area approximately 3390 square feet as necessary to remove existing grass/dirt for 6 feet walkways and planter at (5) city parks.
Install crushed concrete paver base material and compact.
Install approximately 3,390 square feet of 60mm standard pavers. (City will have to come to our office (7900 46th Ave. N) to choose their pavers).
Wet sweep sand into joints and compact.
All un-restrained edges will have our standard concrete edge restraint.
Clean up and recycle as much as possible
Category Total: \$34,171.79
Planters

Build (5) planters out of munich block 5 layers high at 28 linear feet.	
Category Total: \$6,712	.88
Cleaning & Sealing Applies to only pavers installed with this proposal.	
Description	
Pressure wash pavers to remove existing dirt and debris.	
Apply sand to pavers joints as needed.	
Apply penetrating, water-based paver sealer.	
Category Total: \$3,898	.50
Concrete demolition is based on 4" max. thickness, additional thickness may result in an additional charge. Any work adjacent to a swimming pool may result in dirt and debris in the pool that will need to be cleaned out by others. We are not responsible for buried sprinkler lines, utilities, fixtures, etc. that may be damaged as a result of our work. Permit fees are not included in this proposal and will be added to final bill. Any de-rooting required if not listed above is not included in the proposal. Sprinkler repairs, damaged by us, up to 3 fittings and 5' of 3/4" pipe or a maximum of \$25.00 is included in this proposal. Any rem of customer's existing pavers installed over sand bed are included, however removal of pavers installed with adhesive or thinset are not included unless explicity stated above. This proposal may be withdrawn if not accepted within 30 days. Note: 50% Deposit and signed paperwork are required before materials can be ordered and work can be scheduled. The balance of paver installation is due upon completion of the work. The balance of the cleaning & sealing price is paid upon completion of sea work, which will not be scheduled until paver installation price has been paid in full. Payments are due upon substantial completion of the work, and regardless of warranty or punch list items that may remain after installation.	nis oval ded the er
installation. Any unpaid balance over 15 days will be assessed a fee of 1-1/2% per month, figured daily, from the date of completion.	
Additional Information:	
By signing below you are accepting this proposal as a contract for services and acknowledging that you have read and understand the terms conditions.	and
Signature:	
Date:	

Print Name:			
Time Nume.			