



# Trenko Glass

"Every customer treated like our only customer"

April 10, 2023

Frank Rewold & Son

303 E. Third St.

Rochester, MI 48307

**o:** 248.601.1226 **m:** 248.310.0809

## **Project Madison DPW windows**

Trenko proposes to remove existing windows and install new 2 x 4 ½ storefront windows with lower vent and one casement windows as per the following.

### Scope

Remove 8 existing windows approx. 42 x 66

Remove 1 existing slider windows approx. 72 x 48

Install new 2 x 4 ½ thermally improved storefront framing.

Install 8 new lower vents approximately 48 x 18

Install 1 new casement windows approximately 32 x 44

Caulk perimeter of newly installed windows

Finish of new windows is Clear anodized.

Window Insulated glass is 1" oa., Clear low E) Tempered per Codes)

Standard hardware

Screens

Sales tax

Shop drawings

See attached for layout

Total cost supplied and installed \$ 31,650.00.

Respectfully,

John Trenkamp

Estimator