Mercer Island City Hall

facilities conditions assessment and long range planning mercer island northwest studio architects urban designers 07.18.20

Project Team

Facilities condition assessment, Long range planning, Capital projects support

northwest studio architect urban designers

Lead consultant for facilities condition assessment and Long Range planning



Building systems design and engineering, leaders in Sustainable Design

Facilities condition assessments

DCW COST MANAGEMENT Cost estimating and management

City Hall Context and Scope Overview

City Hall Re-Occupancy - Concept level scope of work, cost estimate, and estimated timeline for removals and replacement.

Police Department areas Re-Occupancy - Concept level scope of work, cost estimate, and estimated timeline for removals and replacement.






Existing Heating and Cooling System

SYSTEM DEFICIENCIES:

- PVC piping is at risk of _ catastrophic failure.
- All the equipment is near the end of life. _

ENVIRONMENTAL DEFICIENCIES:

- Using fossil fuel (i.e., natural _ gas for heating)
- Water use for cooling






Existing Ventilation System

SYSTEM DEFICIENCIES:

- Asbestos found in ductwork. _
- All the equipment is near the _ end of life.



ENVIRONMENTAL DEFICIENCIES:

No air-to-air heat recovery, _ which is required when installing a new system under the current Washington State energy code requirement.



Replacement of the HVAC System






New HVAC Hydronic System

SYSTEM IMPROVEMENTS:

- New copper piping condenser water distribution system.
- New high-efficiency and reduced noise water-to-air heat pumps in the building.
- Low maintenance air-source heat pumps _ (ASHPs) in place of the cooling tower.
- Partial heating and cooling redundancy if _ one of the ASHPs is down for maintenance.
- Back-up electric boiler for low-cost winter _ heating redundancy if one ASHP fails.

ENVIRONMENTAL IMPROVEMENTS:

- **Operational Net Zero Carbon HVAC** system
- No water used for cooling



Long-Term Operational Cost Savings:

- Energy utility bills
- Water utility bills •
- Maintenance




New HVAC Ventilation System

SYSTEM IMPROVEMENTS:

- New heat recovery AHUs will _ provide outside air for the entire building.
- CO₂ sensors and VAV terminals will _ control the outside air to highoccupancy spaces based on occupancy.

ENVIRONMENTAL IMPROVEMENTS:

AHUs with air-to-air heat recovery _ provide significant energy savings.



Work related to removal and replacement of HVAC system


Demolish and Replace:

- Removal or relocation and storage of FF&E (furniture, fixtures & equipment)
- Ceilings
- Light fixtures and control wiring
- Data/ IT cabling, and devices
- Security cabling and devices
- Fire alarm systems
- Mechanical systems
- Attic insulation
- Partial wall removals at penetrations
- Floor finishes (+/- 75%)

Additional scopes of work:

- Patch and repair wall finishes
- Repainting
- Interior partition seismic bracing
- Fire protection systems (sprinklers)
- Interior FF&E replacement or relocation from storage
- Additional potential energy code upgrades

Hazardous materials abatement/ remediation allowance included for partial HVAC removals scope only (pending source and extents reporting and abatement plan definition)



Cost estimate overview

DCW Cost Management prepared a preliminary cost estimate for replacement of existing building-wide HVAC systems, along with related work that is required to undertake the HVAC system replacement scope and return the building to a serviceable condition.

The estimate was developed using existing documents, reports, and prior studies, and is based on building gross square footages multiplied by current regional costs per-square-foot for the scope of work involved. The cost report includes seismic upgrades to non-structural interior partitions and masonry walls, as well as select allowances for asbestos abatement.

The cost report is based on the following notes, assumptions, and inclusions:

- The cost estimate reflects information on-hand at the time of the estimate. Future information or additional findings may alter the required scope of work and preliminary cost estimate.
- The consulting team has not had access to City Hall due to the building's closure for asbestos testing. Preliminary figures should be refined once access becomes available.
- Allowances for hazardous materials abatement do not reflect the potential full scope of work required and should be updated following the development of an abatement scope-of-work.
- The project would be delivered via traditional low-bid procurement with a minimum of four (4) qualified General Contractors to assure competitive pricing.
- The majority of work would be performed during regular business hours.
- Owner's soft costs are not included.
- Escalation is included to Q3 2024.
- Sales tax is excluded.

Cost Estimator

DCW Cost Management is an independent third-party cost consultancy with offices in Seattle, WA and Portland, OR. DCW is embedded in the regional construction community, and has a proven track record of providing accurate cost planning and cost control services, with cost estimates falling within 3% to 5% of project low bid amounts.

Cost estimate (draft)

DCW COST MANAGEMENT

Renovation				
	Quantity	Unit	Rate	Total
Program Area	34,737	SF		
Level 1	8,975	SF		
Level 2	25,762	SF		
	20,102	01		
01 Foundations	34,737	SF		
No work anticipated				NIC
02 Vertical Structure	34,737	SF	15.40	535,108
Existing CFS wall bracing	1,861	LF	10.40	333,100
400S200-23	1.27	TN	18,000.00	22,946
600T300-54	2.15	TN	18,000.00	38,690
600\$300-54	2.30	TN	18,000.00	41,370
Existing masonry bracing	910	LF	10,000.00	41,070
L4x4x1/4, cont	3.00	TN	18,000.00	54,054
L4x4x1/4, angle	11.26	TN	18,000.00	202,703
Threaded rods	228	EA	18,000.00 86.00	19,608
Strapping, nails and screws (allow)	34,737	SF	0.40	13,895
Misc. plates and connections (allow)	34,737	LS	40,000.00	40,000
	-	SF	40,000.00	40,000 86,843
Rough carpentry, allow Temporary shoring	34,737	SF LS	2.50 15,000.00	00,043 15,000
Temporary shoring	1	LO	15,000.00	15,000
03 Floor and Roof Structure	34,737	SF		
See "Vertical Structure"				incl. above
04 External Cladding	34,737	SF		
No work anticipated				NIC
05 Roofing and Waterproofing	34,737	SF		
No work anticipated	e iji ei			NIC
	04 707	05	1.00	E7 004
06 Interior Partitions	34,737	SF	1.66	57,691
Patch and repair existing as required, allow	18,610	SF	3.10	57,691
07 Interior Finishes	34,737	SF	19.65	682,582
07 Interior Finishes Ceiling finish - ACT	34,737 24,316	SF SF	19.65 8.50	
				206,685
Ceiling finish - ACT	24,316	SF	8.50	206,685 109,422
Ceiling finish - ACT Ceiling finish - painted gyp.	24,316 10,421	SF SF	8.50 10.50	206,685 109,422 52,106
Ceiling finish - ACT Ceiling finish - painted gyp. Paint, touch up existing to remain (allow)	24,316 10,421 34,737	SF SF SF	8.50 10.50 1.50	682,582 206,685 109,422 52,106 62,527 138,948

Renovation
08 Equipment and Specialties
Corner guards, allow
Wayfinding signage, allow
09 Vertical Transportation
No work anticipated
10 Plumbing
No work anticipated
11 HVAC
Mechanical systems, allow
Heating/cooling system
Exhaust system
Ductwork incl. insulation
Ancillary equipment
12 Electrical
Distribution - modifications as required, allow
Light fixtures, allow
Lighting controls
Fire alarm systems
Voice/data
Equipment connections
13 Fire Sprinklers
Modifications as required, allow
14 Selective Demolition

e	
	Area of protection, allow
	Demo - ceiling finish
	Demo - attic insulation
	Demo - floor finish
	Trade demolition - plumbing, not required
	Trade demolition - mechanical, allow
	Trade demolition - electrical, allow
	Hazardous materials remediation, allow
	FF&E relocation - by Owner

Quantity	Unit	Rate	Total
, ,			
34,737	SF	0.64	22,369
1	LS	5,000.00	5,000
34,737	SF	0.50	17,369
34,737	SF		
			NIC
34,737	SF		
			NIC
 04 303	05	70.00	0 504 004
34,737	SF	72.00	2,501,064
34,737	SF	72.00	2,501,064
			incl.above
04 707	OF	40.60	1 110 200
34,737	SF	40.60	1,410,322
34,737	SF	1.60	55,579
34,737 34,737	SF SF	1.60 19.00	55,579 660,003
34,737 34,737 34,737	SF SF SF	1.60 19.00 4.50	55,579 660,003 156,317
34,737 34,737 34,737 34,737	SF SF SF SF	1.60 19.00 4.50 4.50	55,579 660,003 156,317 156,317
34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50	55,579 660,003 156,317 156,317 295,265
34,737 34,737 34,737 34,737	SF SF SF SF	1.60 19.00 4.50 4.50	55,579 660,003 156,317 156,317
34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50	55,579 660,003 156,317 156,317 295,265 86,843
34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50 3.00	55,579 660,003 156,317 156,317 295,265 86,843 104,211
34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50	55,579 660,003 156,317 156,317 295,265 86,843
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50 3.00 3.00	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211
34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50 3.00	55,579 660,003 156,317 156,317 295,265 86,843 104,211
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF SF	1.60 19.00 4.50 4.50 8.50 2.50 3.00 3.00 19.85 3.10	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10 1.75	55,579 660,003 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948 45,084
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10 1.75 2.25	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948 45,084 78,158 <i>NIC</i>
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 25,762 34,737 34,737	SF SF SF SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10 1.75 2.25 3.60	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948 45,084 78,158 <i>NIC</i> 125,053
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737	SF SF SF SF SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10 1.75 2.25 3.60 2.50	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948 45,084 78,158 <i>NIC</i> 125,053 86,843
34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 34,737 25,762 34,737 34,737	SF SF SF SF SF SF SF SF SF SF SF	1.60 19.00 4.50 8.50 2.50 3.00 3.00 19.85 3.10 2.10 1.75 2.25 3.60	55,579 660,003 156,317 156,317 295,265 86,843 104,211 104,211 689,455 107,685 72,948 45,084 78,158 <i>NIC</i> 125,053

Cost estimate (draft)

DCW COST MANAGEMENT

Renovation Summary				
The novation Summary		%	\$/SF	TOTAL
	Gro	oss Area:	34,737 SF	TOTAL
Foundations		0%	0.00	0
Vertical Structure		6%	15.40	535,108
Floor and Roof Structure		0%	0.00	0
External Cladding		0%	0.00	0
Roofing and Waterproofing		0%	0.00	0
1 Shell		6%	15.40	535,108
Interior Partitions		1%	1.66	57,691
Interior Finishes		7%	19.65	682,582
2 Interiors		8%	21.31	740,273
Equipment and Specialties		0%	0.64	22,369
Vertical Transportation		0%	0.00	0
3 Equipment & Vertical Transportation		0%	0.64	22,369
Plumbing		0%	0.00	0
HVAC		27%	72.00	2,501,064
Electrical		15%	40.60	1,410,322
Fire Protection		1%	3.00	104,211
4 Mechanical & Electrical		43%	115.60	4,015,597
Selective Demolition		7%	19.85	689,455
5 Selective Demolition		7%	19.85	689,455
BUILDING CONSTRUCTION		64%	172.81	6,002,802
General Requirements	7.50%	5%	12.96	450,210
Design Contingency	15.00%	10%	27.87	967,952
Construction Contingency	5.00%	4%	10.68	371,048
General Conditions	7.00%	6%	15.70	545,441
Liability Insurance	1.00%	1%	2.40	83,375
Payment & Performance Bonds	1.00%	1%	2.42	84,208
Overhead & Profit Fee	4.00%	4%	9.79	340,201
CONSTRUCTION COST BEFORE ESCALATION		95%	254.63	8,845,237
Escalation to Start Date (Q3 2024)	5.30%	5%	13.49	468,463
RECOMMENDED BUDGET		100%	268.12	9,313,700

Recommended hard cost budget: \$ 9,313,700 WSST + MI (10.10%): Recommended hard cost total: \$10,254,366

*NIC owner soft costs

Estimated Total:	13 - 17 mont
Move-in:	1 month
Construction:	6 - 8 months
Abatement:	TBD
Design & Permitting:	6 - 8 months
Estimated Durations:	

3 - 17 months + abatement

- 8 months

\$ 940,683

MI PD Areas HVAC System Options

800






Police Department HVAC System

We were asked to study a potential solution for the use of the Police Department areas for 5 to 7 years as an alternative to re-occupancy of all of City Hall.

As an initial option, the team looked at partitioning the existing Police Department spaces from the remainder of the building, abating those spaces, removing the existing HVAC system, and installing a contemporary system to serve this occupancy.




northwest studio architects urban designers

07.18.2023 15



Police Department HVAC System



AB 6351 | Exhibit 3 | Page 42

07.18.2023 16



Police Department HVAC System

FULL REPLACEMENT WITH VRF AND DOAS

Variable Refrigerant Flow (VRF)


Provide a VRF system with indoor wall and ceiling-mounted cassettes to provide heating and cooling for the space. There would be a new outdoor heat pump located at grade in the location where the existing cooling tower is located. This system comes with it's own control system.

Outside Air System

Provide either 1 or 2 new heat recovery ventilators (HRVs) for ventilation air with new supply and return ductwork.



Heat Recovery Ventilator (HRV)



VRF System Schematic

Police Department areas - work related to removal and replacement of HVAC system


Demolish and Replace:

- Removal or relocation and storage of FF&E (furniture, fixtures & equipment)
- Ceilings
- Light fixtures and control wiring
- Data/ IT cabling, and devices
- Security cabling and devices
- Fire alarm systems
- Mechanical systems
- Attic insulation
- Partial wall removals at penetrations
- Floor finishes (+/- 75%)

Additional select scopes:

- Patch and repair wall finishes
- Repainting
- Interior partition seismic bracing
- Fire protection systems (sprinklers)
- Interior FF&E replacement or relocation from storage
- Additional potential energy code upgrades

Hazardous materials abatement/ remediation allowance included for partial HVAC removals scope only (pending source and extents reporting and abatement plan definition)



Cost estimate

Full building estimate for reference only

			\$/SF	τοτα
	Gro	ss Area:	34,737 SF	
Foundations		0%	0.00	(
Vertical Structure		6%	15.40	535,108
Floor and Roof Structure		0%	0.00	, (
External Cladding		0%	0.00	(
Roofing and Waterproofing		0%	0.00	
1 Shell		6%	15.40	535,108
Interior Partitions		1%	1.66	57,69 ⁻
Interior Finishes		7%	19.65	682,582
2 Interiors		8%	21.31	740,273
Equipment and Specialties		0%	0.64	22,369
Vertical Transportation		0%	0.00	(
3 Equipment & Vertical Transportation		0%	0.64	22,369
Plumbing		0%	0.00	(
HVAC		27%	72.00	2,501,064
Electrical		15%	40.60	1,410,322
Fire Protection		1%	3.00	104,21
4 Mechanical & Electrical		43%	115.60	4,015,59
Selective Demolition		7%	19.85	689,45
5 Selective Demolition		7%	19.85	689,45
UILDING CONSTRUCTION		64%	172.81	6,002,802
General Requirements	7.50%	5%	12.96	450,210
Design Contingency	15.00%	10%	27.87	967,952
Construction Contingency	5.00%	4%	10.68	371,048
General Conditions	7.00%	6%	15.70	545,44
Liability Insurance	1.00%	1%	2.40	83,37
Payment & Performance Bonds	1.00%	1%	2.42	84,208
Overhead & Profit Fee	4.00%	4%	9.79	340,20
ONSTRUCTION COST BEFORE ESCALATION		95%	254.63	8,845,23 ⁻
Escalation to Start Date (Q3 2024)	5.30%	5%	13.49	468,463
ECOMMENDED BUDGET		100%	268.12	9,313,700

40.20% of \$9,311,700 equals \$3,744,107

PD approximate area: 13,971 sf Area of total facility: 40.20%

40.20% of full-facility costs:

Recommended hard cost budget: \$ 3,744,107 WSST + MI (10.10%): Recommended hard cost total: \$ 4,122,261

*NIC owner soft costs

Estimated Durations:	
Design & Permitting:	6
Abatement:	ΤE
Construction:	6
Move-in:	1
Estimated Total:	13

months ЪD - 8 months month 3 - 15 months + abatement

\$ 378,154

Mercer Island City Hall

facilities conditions assessment and long range planning mercer island northwest studio architects urban designers 07.18.2