

STAFF REPORT
COMMUNITY DEVELOPMENT DEPARTMENT



HEARING DATE: November 3, 2022
 TO: Planning & Zoning Commission
 FROM: Sonya Allen, Associate Planner
 208-884-5533
 SUBJECT: H-2022-0056
 McDermott Village – AZ, CUP, PP
 LOCATION: 3235 N. McDermott Rd. at the northwest corner of W. Ustick Rd. & N. McDermott Rd., in the SE 1/4 of Section 32, T.4N., R.1W. (Parcel #S0432429360 & #S0432429355)



I. PROJECT DESCRIPTION

Annexation of 40.05 acres of land with R-15 (17.12 acres), R-40 (15.85 acres) and C-G zoning (7.08 acres); Preliminary plat consisting of 85 building lots (81 townhome, 1 multi-family and 3 commercial) & 8 common lots on 40.05 acres of land in the R-15, R-40 & C-G zoning districts; and Conditional Use Permit for a multi-family residential development consisting of 250 dwelling units on 12.19 acres of land in the R-40 zoning district.

II. SUMMARY OF REPORT

A. Project Summary

Description	Details
Acreage	40.05-acres (AZ); 40.05-acres (PP); 12.19-acres (CUP)
Existing/Proposed Zoning	RUT in Ada County (existing); R-15, R-40 & C-G (proposed)
Future Land Use Designation	Mixed Use – Regional (MU-R)
Existing Land Use(s)	Vacant/undeveloped land used for agricultural purposes
Proposed Land Use(s)	Mix of commercial (fuel sales facility & convenience store and flex commercial/office); and residential (i.e. multi-family apartments and townhomes)
Lots (# and type; bldg./common)	85 buildable lots (81 townhome lots, 1 multi-family lot & 3 commercial lots) and 8 common lots
Phasing Plan (# of phases)	3 phases
Number of Residential Units (type of units)	250 multi-family apartment units & 81 townhome units
Physical Features (waterways, hazards, flood plain, hillside)	The Eight Mile Lateral runs across the northeast corner of this site and the Sky Pilot Drain runs across the southern portion of the site.
Neighborhood meeting date	5/25/22

Description	Details
History (previous approvals)	None


B. Community Metrics

Description	Details															
Ada County Highway District																
<ul style="list-style-type: none"> Staff report (yes/no) Requires ACHD Commission Action (yes/no) 	<p>Yes</p> <p>No</p> <p>A Traffic Impact Study (TIS) was prepared by Kittleson & Associates, Inc.</p>															
Access (Arterial/Collectors/State Hwy/Local)(Existing and Proposed)	One access is proposed via S. Rolling Hill Dr. from E. Overland Rd. to the south; and two driveways will provide access from the commercial development to the west via S. Silverstone Way from E. Overland Rd. (a signalized intersection exists at Silverstone/Overland)															
Traffic Level of Service	<table border="1"> <thead> <tr> <th>Roadway</th> <th>Frontage</th> <th>Functional Classification</th> <th>PM Peak Hour Traffic Count</th> <th>PM Peak Hour Level of Service</th> </tr> </thead> <tbody> <tr> <td>Ustick Road</td> <td>1,304-feet</td> <td>Principal Arterial</td> <td>321</td> <td>Better than "E"</td> </tr> <tr> <td>McDermott Road</td> <td>1,304-feet</td> <td>Collector*</td> <td>100</td> <td>Better than "D"</td> </tr> </tbody> </table>	Roadway	Frontage	Functional Classification	PM Peak Hour Traffic Count	PM Peak Hour Level of Service	Ustick Road	1,304-feet	Principal Arterial	321	Better than "E"	McDermott Road	1,304-feet	Collector*	100	Better than "D"
Roadway	Frontage	Functional Classification	PM Peak Hour Traffic Count	PM Peak Hour Level of Service												
Ustick Road	1,304-feet	Principal Arterial	321	Better than "E"												
McDermott Road	1,304-feet	Collector*	100	Better than "D"												
Stub Street/Interconnectivity/Cross Access	A public stub street is planned to the north boundary of this property with the Aviator Springs development (H-2021-0065). W. Endeavor St. to the west is planned to stub/connect to the west boundary of this property when the abutting Flower property (#S0432438850) re-develops.															
Existing Road Network	N. McDermott Rd., a residential collector street & entryway corridor; and W. Ustick Rd., a residential arterial street & entryway corridor, abut this site along the south and east property boundaries.															
Existing Arterial Sidewalks / Buffers	None															
Proposed Road Improvements	<p>Capital Improvements Plan (CIP)/ Integrated Five Year Work Plan (IFYWP):</p> <ul style="list-style-type: none"> The intersection of Ustick Road and McDermott Road is scheduled in the IFYWP to be widened and reconstructed with design in 2026 and construction in the future. Ustick Road is listed in the IFYWP and CIP to be widened to 5-lanes from Star Road to McDermott Road with design in 2026 and construction in the future. Star Road is listed in the CIP to be widened to 5-lanes from Ustick Road to McMillan Road between 2031 and 2035. The intersection of Ustick Road and Star Road is listed in the CIP to be widened to 4-lanes on the north leg, 4-lanes on the south, 5-lanes east, and 5-lanes on the west leg, and signalized between 2031 and 2035. <p>SH-16 is planned to extend north/south through this property and an interchange is proposed at Ustick Rd.</p>															

West Ada School District	Approved MF units					Projected Students from Approved Dev.
	Enrollment	Capacity	Approved lots per attendance area	per attendance area	per attendance area	
Pleasant View Elementary	614	650	3322	100	970	
Star Middle School	893	1000	9667	321	880	
Owyhee High School	1785	1800	6229	137	829	
School of Choice Options						
Chief Joseph Elementary – Arts	524	700	N/A	N/A		
Barbara Morgan STEM Academy	421	500	N/A	N/A		
<ul style="list-style-type: none"> Distance (elem, ms, hs) Capacity of Schools # of Students Enrolled 						

Description	Details
<ul style="list-style-type: none"> Predicted # of students generated from proposed development 	73 +/-
Police Service	
<ul style="list-style-type: none"> Distance to Police Station 	7.5 miles
<ul style="list-style-type: none"> Police Response Time 	6:59 minutes - doesn't currently meet response time goal of 3-5 minutes; however, response times will drastically decline when the MPD precinct opens in the Fall.
<ul style="list-style-type: none"> Calls for Service 	313 within a mile of the site between 6/1/20 and 5/31/22
<ul style="list-style-type: none"> Accessibility 	PD requests police access into each building's entry point using a multi-technology keypad
<ul style="list-style-type: none"> Specialty/resource needs 	None – MPD can service this development & already serves this area.
<ul style="list-style-type: none"> Crimes 	54 within a mile of the site between 6/1/20 and 5/31/22
<ul style="list-style-type: none"> Crashes 	8 within a mile of the site between 6/1/20 and 5/31/22
<ul style="list-style-type: none"> Other 	For more info, see Section VIII.D
Wastewater	
<ul style="list-style-type: none"> Distance to Sewer Services 	
<ul style="list-style-type: none"> Sewer Shed 	
<ul style="list-style-type: none"> Estimated Project Sewer ERU's 	
<ul style="list-style-type: none"> WRRF Declining Balance 	14.42 MGD
<ul style="list-style-type: none"> Project Consistent with WW Master Plan/Facility Plan 	Yes
<ul style="list-style-type: none"> Impacts/concerns 	Additional 11,691 gpd committed to model.
Water	
<ul style="list-style-type: none"> Distance to Water Services 	
<ul style="list-style-type: none"> Pressure Zone 	
<ul style="list-style-type: none"> Estimated Project Water ERU's 	
<ul style="list-style-type: none"> Water Quality Concerns 	
<ul style="list-style-type: none"> Project Consistent with Water Master Plan 	Yes
<ul style="list-style-type: none"> Impacts/Concerns 	

C. Project Area Maps



A. Applicant:

Todd Tucker, Boise Hunter Homes – 729 S. Bridgeway Pl., Eagle, ID 83616

B. Owners:

James Hunter, Woodside Avenue Investors, LLC – 923 S. Bridgeway Pl., Eagle, ID 83616

C. Representative:

Same as Applicant

III. NOTICING

	Planning & Zoning Posting Date	City Council Posting Date
Notification published in newspaper	10/19/2022	
Notification mailed to property owners within 300 feet	10/13/2022	
Applicant posted public hearing notice on site	10/24/2022	
Nextdoor posting	10/13/2022	

IV. COMPREHENSIVE PLAN ANALYSIS ([Comprehensive Plan](#))

Land Use: The Future Land Use Map (FLUM) contained in the Comprehensive Plan designates this property as Mixed Use – Regional (MU-R). *Note: The Applicant requested this designation as part of the update to the Comprehensive Plan in 2019.*

The purpose of the MU-R designation is to provide a mix of employment, retail, and residential dwellings and public uses near major arterial intersections. The intent is to integrate a variety of uses together, including residential, and to avoid predominantly single use developments such as a regional retail center with only restaurants and other commercial uses. Developments should be anchored by uses that have a regional draw with the appropriate supporting uses. The developments are encouraged to be designed consistent with the conceptual MU-R plan depicted in Figure 3D (pg. 3-17). Sample uses, appropriate in MU-R areas would include: All MU-N and MU-C categories, entertainment uses, major employment centers, clean industry, and other appropriate regional-serving most uses. Sample zoning include: R-15, R-40, TN-C, C-G, and M-E

Transportation: State Highway (SH) 16 is planned to extend through this site and an interchange is planned at Ustick Rd.

ACHD’s Master Street Map doesn’t depict any collector streets planned across this site. The segment of Ustick Rd. that this site fronts on is designated on the MSM as a residential arterial with 5-lanes and on-street bike lanes within 100-feet of right-of-way. The segment of McDermott Rd. that the townhome portion of the development fronts on is designated on the MSM as a residential collector with 3-lane roadway, a 46-foot street section within 74-feet of ROW. Due to the extension of SH-16, sidewalk is required on only the east side of the roadway.

Transit services are not available to this site.

Proposed Development: The Applicant proposes to develop the site with two (2) land use types – commercial (includes retail, restaurants, etc.) and residential (i.e. multi-family and townhome). No employment or public uses are proposed and it’s unlikely any of the proposed uses will have a regional draw. The site is designed with the commercial uses along Ustick Rd., an arterial street, with an integrated plaza area between the two northern buildings and multi-family development to the north along future SH-16. Townhomes are proposed on the east side of future SH-16 along N. McDermott Rd., a collector street. The proposed development is generally consistent with the conceptual MU-R plan in the Comprehensive Plan.

This is the only property in this area with a MU-R designation; that along with the property being bisected by SH-16 in the future, which reduces the size of the property from 40 acres to 26.5 acres, makes it difficult to develop the property entirely consistent with the MU-R designation. Additionally, because an interchange is planned in this area and access is limited, the Comprehensive

Plan states retail and auto-generated services should be minimized and transition rapidly from the interchange to residential uses near the County line, which the plan proposes. For these reasons, Staff is amenable to only two (2) land uses and the lower intensity of uses (i.e. primarily residential) proposed rather than more intense commercial uses as is typically desired in the MU-R designation. Additionally, because of the bifurcation of this property with the SH-16 extension, interconnectivity and a full integration of uses within the overall site is not possible as typically desired in mixed use designated areas.

In reviewing development applications, the following items will be considered in all Mixed-Use areas, per the Comprehensive Plan (pg. 3-13): *(Staff's analysis in italics)*

- “A mixed-use project should include at least three types of land uses. Exceptions may be granted for smaller sites on a case-by-case basis. This land use is not intended for high density residential development alone.”

The proposed 26.5-acre development (after right-of-way is taken out for SH-16) includes two types of land uses – commercial and residential. Because this is the only MU-R designated property in this area and the site is not very large and will be divided by a state highway, Staff is of the opinion the proposed number of land use types is sufficient.

- “Where appropriate, higher density and/or multi-family residential development is encouraged for projects with the potential to serve as employment destination centers and when the project is adjacent to US 20/26, SH-55, SH-16 or SH-69.”

The proposed development includes 250 multi-family units at a gross density of 20.5 units per acre. The multi-family portion of the project is located along the west side of future SH-16 and at the northwest corner of the future interchange at Ustick Rd. An employment destination center is not proposed but Owyhee High School exists directly to the west. High-density development is desired near schools so that students can walk to school, reducing bussing needs and traffic in the area.

- “Mixed Use areas are typically developed under a master or conceptual plan; during an annexation or rezone request, a development agreement will typically be required for developments with a Mixed-Use designation.”

A conceptual development plan was submitted with the annexation request, included in Section VII.B. A Development Agreement that ties future development to this plan and the general guidelines for mixed use developments and specifically the MU-R designation is recommended as a provision of annexation.

- “In developments where multiple commercial and/or office buildings are proposed, the buildings should be arranged to create some form of common, usable area, such as a plaza or green space.”

The conceptual development plan depicts a common plaza area between the northern two commercial buildings with a pedestrian walkway to the area from the southern lot (fuel facility/convenience store).

- “The site plan should depict a transitional use and/or landscaped buffering between commercial and existing low- or medium-density residential development.”

There is an existing low-density residential property along the west boundary of the site south of the Sky Pilot Drain adjacent to the proposed commercial uses. A public street (N. Glassford Ave.) is proposed between the commercial buildings and the residential property but a buffer is not proposed to the residential property. A landscaped street buffer is proposed on the east side of the street. Per UDC [Table 11-2B-3](#), a minimum 25-foot wide landscaped buffer is

required on C-G zoned properties to residential uses, unless such width is otherwise modified by City Council at a public hearing with notice to surrounding property owners.

- “Community-serving facilities such as hospitals, clinics, churches, schools, parks, daycares, civic buildings, or public safety facilities are expected in larger mixed-use developments.”

No such uses are specifically proposed in this development – the tenants of the commercial buildings are unknown at this time. Owyhee High School is located directly to the northwest of this site and an LDS seminary and Boys & Girls Club has been conceptually approved to develop on the adjacent property to the north next to the school in close proximity to this site. Although these uses are not within the MU-R designation, they are still provided nearby.

- “Supportive and proportional public and/or quasi-public spaces and places including but not limited to parks, plazas, outdoor gathering areas, open space, libraries, and schools are expected; outdoor seating areas at restaurants do not count.”

A plaza/gathering area is depicted on the conceptual development plan between the two northern commercial buildings; there are no other public and/or quasi-public spaces or places proposed. As noted above, a high school exists to the northwest and an LDS seminary and a Boys & Girls Club are planned to develop in the Aviator Springs development directly to the north.

- “Mixed use areas should be centered around spaces that are well-designed public and quasi-public centers of activity. Spaces should be activated and incorporate permanent design elements and amenities that foster a wide variety of interests ranging from leisure to play. These areas should be thoughtfully integrated into the development and further placemaking opportunities considered.”

No such spaces are proposed on the conceptual development plan. Although a “mix” of uses (i.e. commercial & residential) are proposed, Staff wouldn’t consider this a true mixed-use development due to the lack of integration and connectivity within the overall site, which isn’t possible due to the extension of SH-16 through the property. A plaza/common open space area is depicted between the two (2) northern commercial buildings, which Staff feels is appropriate given the development limitations for this site.

- “All mixed-use projects should be directly accessible to neighborhoods within the section by both vehicles and pedestrians.”

The proposed commercial portion of the development is directly accessible to the multi-family residential portion of the development to the north and the single-family development further to the north (Aviator Springs) by both vehicles and pedestrians.

Future SH-16 will separate the commercial and multi-family development from the townhome development making it impossible for these uses to be directly accessible. Pedestrian pathways are proposed throughout the commercial and multi-family development and a 10-foot wide pathway is proposed to the single-family development to the north for connectivity.

- “Alleys and roadways should be used to transition from dissimilar land uses, and between residential densities and housing types.”

A roadway, parking area and landscape buffer is proposed between the commercial and multi-family development (150’ between structures); and a 2-way drive aisle with parking on either side and a landscape buffer is proposed between the proposed multi-family and future single-family development to the north (115’ between uses) as a transition and buffer between uses.

- “Because of the parcel configuration within Old Town, development is not subject to the Mixed-Use standards listed herein.”

The subject property is not located in Old Town; therefore, this item is not applicable.

In reviewing development applications, the following items will be considered in MU-R areas, per the Comprehensive Plan (pgs. 3-16 thru 3-17):

- Development should generally comply with the general guidelines for development in all Mixed-Use areas.

Staff’s analysis on the proposed project’s compliance with these guidelines is included above.

- Residential uses should comprise a minimum of 10% of the development area at gross densities ranging from 6 to 40 units/acre. There is neither a minimum nor maximum imposed on non-retail commercial uses such as office, clean industry, or entertainment uses.

Residential uses are proposed over 86% of the development area at an overall gross density of 14.58 units/acre, consistent with the density desired in MU-R designated areas. The gross density of the multi-family portion is 20.5 units/acre and the townhome portion is 7.71 units/acre.

- Retail commercial uses should comprise a maximum of 50% of the development area.

Retail/commercial uses are only proposed to comprise of 14% of the development area in accord with this guideline.

Where the development proposes public and quasi-public uses to support the development, the developer may be eligible for additional area for retail development (beyond the allowed 50%), based on the ratios below:

- For land that is designated for a public use, such as a library or school, the developer is eligible for a 2:1 bonus. That is to say, if there is a one-acre library site planned and dedicated, the project would be eligible for two additional acres of retail development.
- For active open space or passive recreation areas, such as a park, tot-lot, or playfield, the developer is eligible for a 2:1 bonus. That is to say, if the park is 10 acres in area, the site would be eligible for 20 additional acres of retail development.
- For plazas that are integrated into a retail project, the developer would be eligible for a 6:1 bonus. Such plazas should provide a focal point (such as a fountain, statue, and water feature), seating areas, and some weather protection. That would mean that by providing a
- half-acre plaza, the developer would be eligible for three additional acres of retail development.

This guideline is not applicable as no public/quasi-public uses are proposed on this site and the retail development area is below the allowed 50%.

Comprehensive Plan Policies: The following Comprehensive Plan Policies are applicable to this development:

- “Permit new development only where it can be adequately served by critical public facilities and urban services at the time of final approval, and in accord with any adopted levels of service for public facilities and services.” (3.03.03F)

City water and sewer service is available and can be extended by the developer with development in accord with UDC 11-3A-21. Urban services are available to be provided upon development.

- “Encourage compatible uses and site design to minimize conflicts and maximize use of land.” (3.07.00)

The proposed retail/commercial uses should be compatible with the existing low-density residential use to the west if a 25-foot wide buffer is provided with dense landscaping as required by UDC Table 11-2B-3 and 11-3B-9C.1 to minimize conflicts between land uses. The proposed multi-family development should be compatible with future single-family residential uses to the north in Aviator Springs subdivision with the proposed separation in uses by drive aisles, parking and a densely landscaped buffer to minimize conflicts between higher and lower density residential uses; and to the high school to the west. The proposed townhomes should be compatible with existing low-density residential properties across McDermott Rd. to the east and any future redevelopment of that area with MU-I (Mixed Use – Interchange) uses; and also, the future research and development use to the north, which is proposed to be separated by a 75-foot wide densely landscaped buffer.

- “Encourage and support mixed-use areas that provide the benefits of being able to live, shop, dine, play, and work in close proximity, thereby reducing vehicle trips, and enhancing overall livability and sustainability.” (3.06.02B)

The proposed apartments and townhomes will provide housing in close proximity to Owyhee High School which will reduce bussing and vehicle trips in the area. The proposed retail/commercial uses should provide benefits to future residents of being able to live, shop and possibly work nearby enhancing overall livability and sustainability.

- “Require pedestrian circulation plans to ensure safety and convenient access across large commercial and mixed-use developments.” (3.07.02A)

The conceptual development plan depicts pedestrian pathways throughout the commercial and multi-family residential developments and to the adjacent single-family residential development to the north (Aviator Springs) for interconnectivity.

- “Ensure development is connected to City of Meridian water and sanitary sewer systems and the extension to and through said developments are constructed in conformance with the City of Meridian Water and Sewer System Master Plans in effect at the time of development.” (3.03.03A)

The proposed development will connect to City water and sewer systems; services are required to be provided to and through this development in accord with current City plans.

- “Permit new development only where it can be adequately served by critical public facilities and urban services at the time of final approval, and in accord with any adopted levels of service for public facilities and services.” (3.03.03F)

City water and sewer services are available to this site and can be extended by the developer with development in accord with UDC 11-3A-21. The emergency response times for Police and Fire Dept. currently fall outside of response time goals; however, when the new MPD precinct opens in Fall of 2023 and Fire Station #8 is constructed and staffed in late summer of 2023, response time goals will be met.

- “With new subdivision plats, require the design and construction of pathway connections, easy pedestrian and bicycle access to parks, safe routes to schools, and the incorporation of usable open space with quality amenities.” (2.02.01A)

Safe pathway connections should be provided from the proposed multi-family development to the abutting high school to the west. Usable open space and quality amenities are proposed with the multi-family development that exceed UDC standards.

- “Require appropriate landscaping, buffers, and noise mitigation with new development along transportation corridors (setback, vegetation, low walls, berms, etc.).” (3.07.01C)

A minimum 35-foot wide landscaped street buffer is required to be provided along future SH-16 and N. McDermott Rd., both designated entryway corridors. Noise mitigation is required within the buffer along future SH-16 per the standards listed in UDC [11-3H-4D](#) for residential uses adjoining a state highway.

- “Evaluate the feasibility of annexing existing county enclaves and discourage the creation of additional enclaves.” (3.03.03I)

This property abuts City annexed land to the north and west; a large enclave area of County land exists to the east. This area is largely sprawl with a lot of properties still in Ada County to the east and southeast. The land directly to the south is within Canyon County’s Area of City Impact boundary. Annexation of this property will not create additional enclaves and will actually decrease the existing enclave area.

- “Require urban infrastructure be provided for all new developments, including curb and gutter, sidewalks, water and sewer utilities.” (3.03.03G)

Urban infrastructure as noted is required to be provided with development in accord with UDC standards.

In summary, Staff believes the proposed development plan is generally consistent with the vision of the Comprehensive Plan for this area per the analysis above.

V. UNIFIED DEVELOPMENT CODE ANALYSIS ([UDC](#))

A. Annexation:

The proposed annexation is for 40.05 acres of land with R-15 (17.12 acres), R-40 (15.85 acres) and C-G zoning (7.08 acres). The proposed use of the property will include a mix of commercial uses, including a fuel sales facility & convenience store and flex commercial/office (tenants have not been identified at this time) on 3.8 acres in the C-G district, multi-family residential apartments on 12.19 acres in the R-40 district, and townhomes on 10.51 acres of land in the R-15 district. The right-of-way proposed to be dedicated for the future extension of SH-16 consists of 13.55 acres of land.

A conceptual development plan was submitted, included in Section VII.B below that shows how the overall property is planned to develop. Based on the analysis above in Section IV, Staff is of the opinion the proposed annexation, zoning and development plan is generally consistent with the Comprehensive Plan with the provisions noted in Section VIII as discussed herein.

A multi-family development requires approval of a Conditional Use Permit (CUP) in the R-40 zoning district, subject to the specific use standards for such listed in UDC [11-4-3-27](#), and townhouse dwellings are listed as a principal permitted use in the R-15 zoning district per UDC [Table 11-2A-2](#). Commercial/retail and fuel sales facility uses are listed as a principal permitted use in the C-G zoning district per UDC [Table 11-2B-2](#), fuel sales facilities are subject to the

specific use standards listed in UDC [11-4-3-20](#). Other uses may be allowed as noted in the Allowed Uses in the Commercial Districts [Table 11-2B-2](#).

The proposed uses and zoning districts are listed as appropriate uses and zoning in the Comprehensive Plan for the MU-R designated area.

The property is contiguous to City annexed land and is within the City's Area of City Impact boundary. A legal description and exhibit map of the overall annexation area is included in Section VII.A.

The City may require a development agreement (DA) in conjunction with an annexation pursuant to Idaho Code section 67-6511A. **To ensure future development is consistent with the Comprehensive Plan and with the development plan proposed with this application, Staff recommends a DA is required with this application, containing the provisions noted in Section VIII.A, as discussed herein.**

B. Preliminary Plat:

The proposed preliminary plat consists of 85 building lots (81 townhome, 1 multi-family and 3 commercial) & 8 common lots on 40.05 acres of land in the R-15, R-40 & C-G zoning districts.

The Applicant anticipates the development will be constructed in three (3) phases with the multi-family development first, the townhomes second and the commercial last unless they get a demand for the commercial, then it might be second.

Existing Structures/Site Improvements:

There are no existing structures or improvements on this site.

Dimensional Standards:

Development of the proposed lots is required to comply with the dimensional standards listed in UDC Tables [11-2A-7](#) for the R-15 district and [11-2A-8](#) for the R-40 district; and UDC Table [11-2B-3](#) for the C-G zoning district. **Some of the R-15 zoned lots do not comply with the minimum lot size of 2,000 square feet per dwelling units; revisions are necessary to comply. Zero (0) lot lines should be graphically depicted on the plat on the internal lot lines where the townhomes are proposed (i.e. where structures are proposed to span across lot lines).**

Subdivision Design and Improvement Standards (UDC [11-6C-3](#)):

Development of the subdivision is required to comply with the subdivision design and improvement standards listed in UDC 11-6C-3.

Road Improvements [Capital Improvements Plan (CIP)/Integrated Five Year Work Plan (IFYWP)]: The intersection of Ustick Road and McDermott Road is scheduled in the IFYWP to be widened and reconstructed with design in 2026 and construction in the future. Ustick Road is listed in the IFYWP and CIP to be widened to 5- lanes from Star Road to McDermott Road with design in 2026 and construction in the future. Star Road is listed in the CIP to be widened to 5- lanes from Ustick Road to McMillan Road between 2031 and 2035. The intersection of Ustick Road and Star Road is listed in the CIP to be widened to 4- lanes on the north leg, 4- lanes on the south, 5- lanes east, and 5- lanes on the west leg, and signalized between 2031 and 2035. See *ACHD's staff report in Section VIII.I for more information.*

Access (UDC [11-3A-3](#))

A public street access is proposed via W. Ustick Rd., an arterial street, to the portion of the site west of future SH-16. A stub street is proposed to the property to the north (Aviator Springs) to connect to a planned stub street to this property. Another stub street (W. Endeavor St.) is proposed to the school property to the west for future extension and connection to N. Owyhee Storm Ave., a collector street. Alleys/private streets are depicted on the plat in the proposed

multi-family development. Private streets should be provided for addressing purposes. **A private street application should be submitted prior to or concurrent with the final plat application.**

Two (2) accesses are proposed via N. McDermott Rd., a collector street, to the portion of the site east of future SH-16. McDermott Rd. is planned to dead-end in a cul-de-sac just north of Ustick Rd. and not connect to Ustick when the interchange is constructed. An emergency only access is proposed out to W. Ustick Rd. that has been approved by the Fire Dept.; ITD has verified that this access does not touch or abut the State Highway system. **The bollards should be located completely outside of the right-of-way.** ITD's roadway plans for the existing Ustick/McDermott Rd. intersection are included in Section VIII.I. Alleys are proposed for access to the townhome units located north of W. Aspenstone St. and south of Beechstone St. All alleys must comply with the standards listed in UDC [11-6C-3B.5](#). The proposed alleys appear to comply with these standards.

Cross-access/ingress-egress easements should be provided between all C-G zoned commercial lots in the subdivision via a note on the final plat or a separate recorded easement.

Pathways (UDC [11-3A-8](#)):

The Pathways Master Plan depicts a 10-foot wide multi-use pathway along W. Ustick Rd. on this site; a 10-foot wide pathway is depicted on the landscape plan as required.

A 10-foot wide multi-use pathway is proposed within the street buffer along the west side of N. Glassford Ave., consistent with the developments to the north, which crosses to the east at the north boundary of the site within the buffer along SH-16 which will connect to the pathway planned to the north in Aviator Springs. A 14-foot wide public use easement is required for the pathway; the easement should be submitted to the Planning division prior to submittal for City Engineer signature on the final plat.

Internal pedestrian pathways are proposed throughout the central common open space area and to the commercial development to the south.

Safe pathway connections should be provided from the proposed multi-family development to the abutting high school to the west.

Sidewalks (UDC [11-3A-17](#)):

Detached sidewalks are required along all collector and arterial streets; attached sidewalks may be provided along local streets. Sidewalks are not required along I-84; however, a pathway is proposed within the buffer. **ACHD is requiring a sidewalk to be constructed off-site along one side of S. Rolling Hill Dr. with development of this site.**

Landscaping (UDC [11-3B](#)):

Street buffers are required to be provided as follows: A minimum 35-foot wide buffer is required along future SH-16 and the interchange and along N. McDermott Rd., entryway corridors; a minimum 25-foot wide buffer is required along the western portion of W. Ustick Rd., an arterial street; and a minimum 10-foot wide buffer is required along local streets in the C-G zoning district, measured per the standards listed in UDC [11-3B-7C.1a](#). **Landscaping is required within the street buffer as set forth in UDC [11-3B-7C](#) (see updated standards).** Street buffers are required to be maintained by the property owner or business owners' association and should be depicted on the plat in a common lot or permanent dedicated buffer per UDC [11-3B-7C.2b](#).

Landscaping is required adjacent to all pathways in accord with the standards listed in UDC [11-3B-12C](#).

Depict landscaping within common open space areas as set forth in UDC 11-3G-5B.3.

The City Arborist requests a change in tree selection of the Fraxinus Pennsylvanica “Marshall’s Seedless” Green Ash is changed to another variety due to a future threat of Emerald Ash Borer.

There are no existing trees on the site to be removed or that require mitigation.

Common Open Space (UDC [11-3G-3B](#)): A minimum of 15% *qualified* open space is required to be provided within the townhome portion of the development that meets the quality standards listed in UDC 11-3G-3A.2. Based on 10.51 acres, a minimum of 1.58 acres of qualified open space is required. A total of 3.33 acres of qualified open space is proposed on the open space exhibit included in Section VII.F in excess of UDC standards (i.e red hatched areas). Open space areas consist of open grassy areas of at least 5,000 square feet and linear open space.

Site Amenities (UDC [11-3G-4](#)): A minimum of 2 points of site amenities are required based on 10.51 acres of development area from the Site Amenities and Point Value [Table 11-3G-4](#). It’s not clear to Staff what is proposed for site amenities in the townhome portion of the development. The Applicant should clarify prior to or at the Commission hearing what amenities are proposed.

Noise Abatement: Noise abatement is required for residential uses along state highways per the standards listed in UDC [11-3H-4D](#). A 10-foot solid screen wall is proposed. **Noise abatement should be provided within the street buffers along SH-16 that are adjacent to residential uses per the standards listed in UDC 11-3H-4D for residential uses adjoining a state highway. A berm or a berm and wall combination that’s a minimum of 10-feet higher than the elevation at the centerline of the state highway is required. Include a cross-section of the berm or berm/wall that complies with this standard with the final plat application(s).**

Storm Drainage (UDC [11-3A-18](#)):

An adequate storm drainage system is required in all developments in accord with the City’s adopted standards, specifications and ordinances. Design and construction is required to follow Best Management Practices as adopted by the City. The Applicant submitted a [Geotechnical Engineering Report](#) for the subdivision. Stormwater integration is required in accord with the standards listed in UDC [11-3B-11C](#).

Pressure Irrigation (UDC [11-3A-15](#)):

Underground pressurized irrigation water is required to be provided for each and every lot in the subdivision as required in UDC 11-3A-15. This property lies within the Nampa-Meridian Irrigation District boundary.

Utilities (UDC [11-3A-21](#)):

Utilities are required to be provided to the subdivision as required in UDC [11-3A-21](#).. Street lights shall be installed in accord with the City’s adopted standards, specifications and ordinances/

Waterways (UDC [11-3A-6](#)):

The Sky Pilot Drain crosses the southern portion of this site within a 100-foot wide easement; the Eight Mile Lateral crosses the northeast corner of the site within a 50-foot wide easement; and the Noble Lateral runs along the east boundary of the site within a 40-foot wide easement (20-feet from centerline each side). **The easements for all of these waterways shall be depicted on the final plat; structures shall not encroach within these easements.** All waterways on this site shall be piped as set forth in UDC [11-3A-6B.3](#), unless otherwise waived by City Council. This project is not within the flood plain.

The developer has requested ITD relocate the Eight Mile Lateral to accommodate the proposed development plan. Because the plans have already been designed and environmental approvals

obtained to pipe it in its current location, a change this late in the process may not be approved. **If the location of the lateral changes, it should be depicted on the plans submitted with the final plat application.**

Fencing (UDC [11-3A-6](#) and [11-3A-7](#)):

All fencing is required to comply with the standards listed in UDC 11-3A-7. A 6-foot tall solid screen fence is proposed along the northern & western boundaries of the multi-family development.

C. Conditional Use Permit (CUP):

A Conditional Use Permit is requested for a multi-family residential development consisting of 250 dwelling units on 12.19 acres of land in the R-40 zoning district in accord with UDC [Table 11-2B-2](#). The proposed development will have (12) 3-story multi-family structures and a 9,055 square foot amenity building centrally located within the complex. Six (6) different floor plans are proposed with a mix of units consisting of 1- (97), 2- (114) and 3- (39) bedroom units ranging from 712 to 1,278 square feet in size.

Specific Use Standards (UDC 11-4-3-27):

The proposed use is subject to the following standards: *(Staff's analysis/comments in italic text)*

[11-4-3-27](#): MULTI-FAMILY DEVELOPMENT:

Site Design:

1. Buildings shall provide a minimum setback of ten feet (10') unless a greater setback is otherwise required by this title and/or [title 10](#) of this Code. Building setbacks shall take into account windows, entrances, porches and patios, and how they impact adjacent properties. *The site plan included in Section VII.D depicts buildings at a minimum setback of 10-feet; no greater setback is required.*
2. All on-site service areas, outdoor storage areas, waste storage, disposal facilities, and transformer and utility vaults shall be located in an area not visible from a public street, or shall be fully screened from view from a public street. ***The plans submitted with the Certificate of Zoning Compliance application should demonstrate compliance with this standard.***
3. A minimum of eighty (80) square feet of private, usable open space shall be provided for each unit. This requirement can be satisfied through porches, patios, decks, and/or enclosed yards. Landscaping, entryway and other access ways shall not count toward this requirement. In circumstances where strict adherence to such standard would create inconsistency with the purpose statements of this section, the Director may consider an alternative design proposal through the alternative compliance provisions as set forth in section [11-5B-5](#) of this title. *The Applicant's narrative states each dwelling unit is provided with a minimum 80 square foot attached patio or deck, which meets this standard.*
4. For the purposes of this section, vehicular circulation areas, parking areas, and private usable open space shall not be considered common open space. *These areas were not included in the common open space calculations for the site.*
5. No recreational vehicles, snowmobiles, boats or other personal recreation vehicles shall be stored on the site unless provided for in a separate, designated and screened area. *The Applicant should comply with this requirement.*

6. The parking shall meet the requirements set forth in [chapter 3](#), "Regulations Applying to All Districts", of this title. *A minimum of 477 off-street parking spaces are required for the multi-family development with 250 of those being in a covered carport or garage; a minimum of 19 bicycle parking spaces are required. A minimum of 18 spaces are required for the amenity building with a minimum of one (1) bicycle parking space. The minimum number of spaces required overall is 495 with a minimum of 20 bicycle spaces. A total of 482+/- parking spaces are proposed overall, with 250 of those being covered, and 20 bicycle spaces, which does not meet the minimum standard. **A revised parking plan that meets the minimum standards should be submitted prior to the Commission hearing. Bike racks should be provided in central locations for each multi-family building and the amenity building.***
7. Developments with twenty (20) units or more shall provide the following:
 - a. A property management office.
 - b. A maintenance storage area.
 - c. A central mailbox location, including provisions for parcel mail, that provide safe pedestrian and/or vehicular access.
 - d. A directory and map of the development at an entrance or convenient location for those entering the development. (Ord. 18-1773, 4-24-2018)

*The site amenity plan included in Section VII.G depicts a leasing area (property management office), a maintenance storage area and mailbox location (including provisions for parcel mail), in accord with this standard. **The location of the directory and map of the development should be depicted on the site plan submitted with the Certificate of Zoning Compliance application.***

Common Open Space Design Requirements (UDC [11-4-3-27C](#)):

The total baseline land area of all qualified common open space shall equal or exceed 10% of the gross land area for multi-family developments of 5 acres or more. *A minimum of 1.22 acres of common open is required to meet this standard.*

Common open space areas are also required to comply with the standards listed in UDC 11-4-3-27C.2, which state that open space areas must be integrated into the development as a priority and not for the use of land after all other elements of the development have been designed. These areas should have direct pedestrian access, be highly visible, comply with CPTED standards and support a range of leisure and play activities and uses – irregular shaped, disconnected or isolated open spaces do not meet the standard. Open space areas should be accessible and well connected throughout the development (i.e. centrally located, accessible by pathway and visually accessible along collector streets or as a terminal view from a street). Open space areas should promote the health and well-being of its residents and support active and passive uses for recreation, social gathering and relaxation to serve the development. *The proposed common open space meets these standards.*

All multi-family projects over 20 units are required to provide at least one (1) common grassy area of at least 5,000 s.f. in area that's integrated into the site design allowing for general activities by all ages, which may be included in the minimum required open space. The area shall increase proportionately as the number of units increase and shall be commensurate to the size of the development as determined by the decision-making body. *The Applicant proposes two (2) central common open space areas of 67,632 and 29,360 s.f. that meets this requirement.*

In addition to the baseline open space requirement, a minimum area of outdoor common open space shall be provided as follows:

- a. One hundred fifty (150) square feet for each unit containing five hundred (500) or less square feet of living area. *All units contain more than 500 square feet (s.f.) of living area.*
- b. Two hundred fifty (250) square feet for each unit containing more than five hundred (500) square feet and up to one thousand two hundred (1,200) square feet of living area. *A total of 211 units contain between 500 and 1,200 s.f. of living area; therefore, a minimum of 52,750 s.f. (or 1.21 acres) of common open space is required.*
- c. Three hundred fifty (350) square feet for each unit containing more than one thousand two hundred (1,200) square feet of living area. *A total of 39 units contain more than 1,200 s.f.; therefore, a minimum of 13,650 s.f. (or 0.31 acre) of common open space is required.*

At a minimum, a total of 66,400 s.f. (or 1.52 acres) of qualified outdoor common open space is required to be provided per this standard. In order to meet the baseline requirement noted above and this standard, a total of 119,500 s.f. (or 2.74 acres) of common open space is required. A total of 146,094 s.f. (or 3.35 acres) of qualified open space is proposed in excess of the minimum standards as shown in Section VII.F (red hatch areas). Qualified areas consist of central common/amenity areas and a pedestrian corridor where a multi-use pathway is planned.

Common open space shall be not less than four hundred (400) square feet in area, and shall have a minimum length and width dimension of twenty feet (20'). *All of the red hatched areas depicted on the open space exhibit in Section VII.G meet this requirement.*

In phased developments, common open space shall be provided in each phase of the development consistent with the requirements for the size and number of dwelling units. *The Applicant anticipates the multi-family development will be constructed in one phase. If not, compliance with this standard is required.*

Unless otherwise approved through the conditional use process, common open space areas shall not be adjacent to collector or arterial streets unless separated from the street by a berm or constructed barrier at least four feet (4') in height, with breaks in the berm or barrier to allow for pedestrian access. (Ord. 09-1394, 3-3-2009, eff. retroactive to 2-4-2009) *None of the common open space areas are located adjacent to a collector or arterial street.*

Site Development Amenities:

1. All multi-family developments shall provide for quality of life, open space and recreation amenities to meet the particular needs of the residents as follows:
 - a. Quality of life:
 - (1) Clubhouse.
 - (2) Fitness facilities.
 - (3) Enclosed bike storage.
 - (4) Public art such as a statue.
 - (5) Dog park with waste station.
 - (6) Commercial outdoor kitchen.

- (7) Fitness course.
 - (8) Enclosed storage.
 - b. Open space:
 - (1) Community garden.
 - (2) Ponds or water features.
 - (3) Plaza.
 - (4) Picnic area including tables, benches, landscaping and a structure for shade.
 - c. Recreation:
 - (1) Pool.
 - (2) Walking trails.
 - (3) Children's play structures.
 - (4) Sports courts.
 - d. Multi-modal amenity standards:
 - (1) Bicycle repair station.
 - (2) Park and ride lot.
 - (3) Sheltered transit stop
 - (4) Charging stations for electric vehicles
2. The number of amenities shall depend on the size of multi-family development as follows:
- a. For multi-family developments with less than twenty (20) units, two (2) amenities shall be provided from two (2) separate categories.
 - b. For multi-family development between twenty (20) and seventy-five (75) units, three (3) amenities shall be provided, with one from each category.
 - c. For multi-family development with seventy-five (75) units or more, four (4) amenities shall be provided, with at least one from each category.
 - d. For multi-family developments with more than one hundred (100) units, the decision-making body shall require additional amenities commensurate to the size of the proposed development.
3. The decision-making body shall be authorized to consider other improvements in addition to those provided under this subsection D, provided that these improvements provide a similar level of amenity. (Ord. 05-1170, 8-30-2005, eff. 9-15-2005)

*Proposed amenities include a clubhouse with a fitness facility, a swimming pool and spa with cabanas and an outdoor lounge area, 10-foot wide multi-use pathways and internal walking trails, a plaza, a pickleball sports court, and a bike repair station. A **BBQ area is depicted on the site plan; Staff recommends this area is constructed as a commercial outdoor kitchen. An outdoor seating area is also depicted on the site plan; Staff recommends this area is constructed as a picnic area with tables, benches, landscaping and a shade structure. Staff also recommends a children's play structure is provided. Staff is of the opinion these upgrades and addition of an amenity is commensurate with the number of units proposed.***

E. Landscaping Requirements:

1. Development shall meet the minimum landscaping requirements in accord with [chapter 3](#), "Regulations Applying to All Districts", of this title.
2. All street facing elevations shall have landscaping along their foundation. The foundation landscaping shall meet the following minimum standards:
 - a. The landscaped area shall be at least three feet (3') wide.
 - b. For every three (3) linear feet of foundation, an evergreen shrub having a minimum mature height of twenty-four inches (24") shall be planted.
 - c. Ground cover plants shall be planted in the remainder of the landscaped area.

The landscape plan submitted with the Certificate of Zoning Compliance application should depict landscaping in accord with these standards.

- F. Maintenance and Ownership Responsibilities: All multi-family developments shall record legally binding documents that state the maintenance and ownership responsibilities for the management of the development, including, but not limited to, structures, parking, common areas, and other development features. ***The Applicant shall comply with this requirement.***

Landscaping (UDC [11-3B](#)):

Street buffer landscaping, including noise abatement along future SH-16, is required to be provided with the subdivision improvements as noted above in Section V.B.

Landscaping is required to be provided along all pathways per the standards listed in UDC [11-3B-12C](#). **A mix of trees, shrubs, lawn and/or other vegetative ground cover with a minimum of one (1) tree per 100 linear feet of pathway.**

Fencing: All fencing is required to comply with the standards listed in UDC 11-3A-7. A 6-foot tall solid screen fence is proposed along the northern & western boundaries of the multi-family development.

Building Elevations (UDC [11-3A-19](#) | [Architectural Standards Manual](#)):

Conceptual building elevations were submitted for the proposed structures, included in Section VII.H. The townhomes are proposed to be 2- or 3-stories in height, the multi-family structures are proposed to be 3-stories in height, and the clubhouse if proposed to be a single-story in height; building materials consist of a mix of vertical board & batten fiber cement siding and horizontal lap siding with brick veneer siding and wood ridge beam accents, metal awnings and asphalt shingle roofing.

A Certificate of Zoning Compliance and Design Review application is required to be submitted for approval of the multi-family and commercial development to ensure compliance with UDC standards and development provisions associated with this application. A Design Review application is required to be submitted for approval of the townhomes. Final design of all structures must comply with the design standards in the Architectural Standards Manual.

VI. DECISION

A. Staff:

Staff recommends approval of the requested annexation with the requirement of a development agreement, preliminary plat and conditional use permit with the provisions noted in Section VIII, per the Findings in Section IX.

VII. EXHIBITS

A. Annexation Legal Description & Exhibit Map



9955 W Emerald St
Boise, ID 83704
Phone: (208) 846-8570
Fax: (208) 884-5399

**McDermott Village Subdivision
Annexation
Boundary Description**
Project Number 21-578 June 15, 2022

The southeast quarter of the southeast quarter of Section 32, Township 4 North, Range 1 West, Boise Meridian, Ada County, Idaho, and being more particularly described as follows:

BEGINNING at the southeast corner of the southeast quarter of the southeast quarter of Section 32, Township 4 North, Range 1 West, Boise Meridian:

Thence N89°17'49"W, 1325.58 feet along the south line of the southeast quarter of the southeast quarter to the east sixteenth-section corner;


Thence N00°33'07"E, 1316.23 feet along the west line of the southeast quarter of the southeast quarter to the southeast sixteenth-section corner;

Thence S89°19'58"E, 1324.63 feet along the north line of the southeast quarter of the southeast quarter to the south sixteenth-section corner;





Thence S00°30'38"W, 1317.06 feet along the east line of the southeast quarter of the southeast quarter to the POINT OF BEGINNING.


The above-described parcel contains 40.05 acres, more or less.





Legend

-  Property Corner
-  Property Boundary Line
-  Parcel Line
-  Section Line



P:\3235 N McDermott Rd Bndry 21-578\dwg\21-578 Annexation.dwg 6/15/2022 2:17:22 PM

	IDAHO SURVEY GROUP, LLC	9955 W. EMERALD ST. BOISE, IDAHO 83704 (208) 846-8570
	Exhibit Drawing for Annexation	

Situated in the southeast quarter of the southeast quarter of Section 32, Township 4 North, Range 1 West, B.M., Ada County, Idaho.

Job No. 21-578
Sheet No. 1
Dwg. Date 6/15/2022


B. Conceptual Development Plan, Overall Development Plan in the Vicinity & Concept Data



CONCEPTUAL DEVELOPMENT PLAN

NTS





Ustick/ McDermott Residential
Meridian, ID

Pivot North Architects
05/25/2022

Zoning Summary:			
Site Area:			
Site 1: (Multifamily)	12.19 AC	Site 3: (TH)	10.4 AC
Site 2: (Retail/ C-store)	3.89 AC	Highway (N.A.P.):	13.9 AC
Current:		Proposed:	
Current Zoning:	RUT Rural, Urban Transitional	Proposed Zoning (MF):	R-40 (change)
Max. Density:	43.56 du/AC (1,000 sf/du)	Proposed Density:	20.5 du/AC
Setbacks Required:		Setbacks Proposed:	
Rear:	12'	Rear:	20' min.
Side Int:	3'	Side Int:	10' min.
Street Setback to Garage Required:		Street Setback to Garage Proposed:	
Local:	20'	Local:	20' min.
Street Setback to Living Required:		Street Setback to Living Proposed:	
Local:	10'	Local:	20' min.
Street Landscape Buffer Required:		Street Landscape Buffer Proposed:	
Local:	n/a	Local:	20' min.
Max. Height:	60'	Proposed Height:	+/-41'-9"

Gross SF Data:						
Multifamily:	Fir.-to-Fir. Height:	Bldg. GSF + deck	Bldg. GSF	Bldg. Net SF	Eff. #	# Unit per floor
Level 1:	10'-2"	116,413	112,413	47,436	42%	50
Level 2:	10'-2"	116,750	108,750	95,181	88%	100
Level 3:	11'-2"	113,638	105,638	95,181	90%	100
Foot:	10'-3"					
Total:	41'-9"	346,801	326,801	237,798	73%	250

Commercial Data:		
C-store:		5,549
Retail 1:		3,407
Retail 2:		6,117
Level 1:		15,073

Common Open Space Summary:			
Common Open Space Required:		Common Open Space Proposed:	
Baseline:	# ratio total	total	
10% of site:	452,131 10% 45,213 sf	Ground Level:	82,553
Multifamily:	# ratio total		30,710
Units <500 sf:	0 150 -		17,324
Units 500-1200 sf:	211 250 52,750		13,629
Units >1200 sf:	39 350 13,650		
Subtotal Required:	250 66,400 sf	Subtotal MF Provided:	144,730 sf
Subtotal MF Required:	111,513 sf		
TH/C-store:	# sf ratio total	Ground Level:	11,447
5% of site:	169,448 5% 8,473	Plaza:	5,050
Subtotal Required:	8,473 sf	Subtotal Provided:	16,497 sf

**Note: Data is schematic and subject to update as more information is known

Unit Summary:							
	#	NSF*	DECK	Net-deck	NSF	SUBTOTAL	%
1A	87	719	80	799			
1B	10	835	80	515			
Subtotal 1- bed	97	731			70,903		38.8%
2A	58	1,099	90	1,089			
2B	18	1,117	90	1,197			
2C	38	1,004	80	1,084			
Subtotal 2- bed	114	1,024			116,780		45.6%
3A	39	1,285	80	1,365			
Subtotal 3- bed	39	1,285			50,115		15.6%
TOTAL:	250	951 ave.			237,798	sq'	

*Notes: Data taken to inside face of exterior / corridor / unit walls

Parking Summary:			
Parking Required:		Parking Proposed:	
	#	ratio	total
1-bed	97	1.5	146
2-bed	114	2	228
3-bed	39	2	78
Guest	250	0.1	25
Amenity:	9,000	1/500	18
Subtotal Multifamily:			477
Covered:		1:1	250
	#	ratio	total
C-store:	5,549	1:500 sf	12
Retail 1:	3,407	1:500 sf	7
Retail 2:	6,117	1:500 sf	13
Subtotal C.ct:			32
Garage:			139
Carport:			81
Garport:			30
Standard:			62
Parking Pad:			112
HC:			10
Amenity:			18
Parallel Street:			25
Subtotal Multifamily:			477
Covered:			250
Retail:			51
HC:			3
Subtotal Cmcl:			54

Bike Parking Summary:			
Bike Parking Required:		Bike Parking Proposed:	
	#	ratio	total
Multifamily:	477	1:25	20
Total Required:			20
Covered/Secured:			20
Total Proposed:			20



CONCEPT DATA

05.25.2022


McDermott Multifamily

Ustick & McDermott., Meridian ID
PNa JOB # 21-0XX





MATCHLINE - SEE SHEET RIGHT



MATCHLINE - SEE SHEET LEFT

Kimley»Horn


SCALE: 1/4" = 1'-0"
 DATE: 03/27/2022
 DRAWN BY: JHM
 CHECKED BY: JHM
 DATE: 03/27/2022

MCDERMOTT VILLAGE
 PRELIMINARY PLAT
 MERIDIAN, IDAHO



PROJECT NO.
 093969000
 DRAWING NAME
 PFD1.dwg

02 of 17



PROJECT NO. 03-38-000	DATE: 03/17/2022
DRAWING NAME PPSI-003	DATE: 03/17/2022
MCDERMOTT VILLAGE PRELIMINARY PLAT MERIDIAN, IDAHO	



1 CONCEPTUAL PHASING PLAN


L-005
06/30/2022

GGLO **pivot north**
ARCHITECTURE

McDermott and Ustick, MERIDIAN, ID
2022014.01

McDermott Mixed-Use

D. CUP Site Plan for Multi-Family Development (dated: 6/30/2022)



LANDSCAPE GENERAL NOTES

1. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL.

STREET TREES

1. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL.

TREE COUNT

1. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN.

TREE MITIGATION

1. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES.

OPEN SPACE

1. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN.

WALKWAY PLANTING REQUIREMENTS

1. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS.

WALKWAY PLANTING REQUIREMENTS

1. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS.

WALKWAY PLANTING REQUIREMENTS

1. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS.

LANDSCAPE GENERAL NOTES

1. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL.

STREET TREES

1. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL. ALL STREET TREES SHALL BE PLANTED IN ACCORDANCE WITH THE CITY OF MERIDIAN LANDSCAPE DESIGN MANUAL.

TREE COUNT

1. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN. THE TOTAL NUMBER OF TREES TO BE PLANTED SHALL BE AS SHOWN ON THIS PLAN.

TREE MITIGATION

1. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES. ALL TREES TO BE REMOVED SHALL BE REPLACED WITH ONE OR MORE TREES OF EQUAL OR GREATER CALIBER AND SPECIES.

OPEN SPACE


1. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN. ALL OPEN SPACE SHALL BE MAINTAINED AND KEPT OPEN.

WALKWAY PLANTING REQUIREMENTS

1. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS.

WALKWAY PLANTING REQUIREMENTS

1. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS. ALL WALKWAYS SHALL BE PLANTED WITH TREES AND SHRUBS.



1 LANDSCAPE PLAN - OPEN SPACE DIAGRAM - R40
 PRELIMINARY PLAT OPEN SPACE, AMENITY, &
 STREET TREE CALCULATIONS - R40
 SCALE: 1" = 40'-0" @ 24536
 McDermott and Ustick, MERIDIAN, ID
 2022014.01

GGLO pivot north
 ARCHITECTURE

L-002
 06/30/2022

LANDSCAPE GENERAL NOTES

1. THE DESIGNER HAS CONDUCTED VISUAL ANALYSES AND SELECTED PLANT MATERIALS THAT ARE SUITABLE FOR THE CLIMATE AND SOILS OF THE PROJECT AREA. PLANT MATERIALS SHOULD BE SEASONALLY APPROPRIATE AND MAINTAINABLE. PLANT MATERIALS SHOULD BE SEASONALLY APPROPRIATE AND MAINTAINABLE. PLANT MATERIALS SHOULD BE SEASONALLY APPROPRIATE AND MAINTAINABLE.

STREET TREES

1. STREET TREES SHALL BE PLANTED AT THE CURB LINE OF THE STREET. STREET TREES SHALL BE PLANTED AT THE CURB LINE OF THE STREET. STREET TREES SHALL BE PLANTED AT THE CURB LINE OF THE STREET.

TREE COUNT

1. TREE COUNT SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET. TREE COUNT SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET.

TREE MITIGATION

1. TREE MITIGATION SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET. TREE MITIGATION SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET.

OPEN SPACE


1. OPEN SPACE SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET. OPEN SPACE SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET.

WALKWAY PLANTING REQUIREMENTS

1. WALKWAY PLANTING SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET. WALKWAY PLANTING SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET.

BUFFER PLANTING REQUIREMENTS

1. BUFFER PLANTING SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET. BUFFER PLANTING SHALL BE BASED ON THE NUMBER OF TREES PLANTED AT THE CURB LINE OF THE STREET.



1 LANDSCAPE PLAN - OPEN SPACE DIAGRAM - R15
 PRELIMINARY PLAT OPEN SPACE, AMENITY, &
 STREET TREE CALCULATIONS - R15
 SCALE: 1" = 40'-0" @ 24036
 L-004
 06/30/2022
GGLO pivot north
 ARCHITECTURE
 McDermott and Ustick, MERIDIAN, ID
 2022014.01

G. Site Amenity Plan for Multi-Family Development – CUP (dated: 6/29/22)



GROSS SF: +/-9,055 SF
SCALE: 1" = 20'

CONCEPT AMENITY PLAN

N
01
06.29.2022

McDermott Multifamily

Ustick & McDermott., Meridian ID
PNa JOB # 21-0XX

pivot north
ARCHITECTURE

H. Conceptual Building Elevations & Perspectives for Residential (dated: 6/30/22)

Townhomes:



Multi-Family Development – Apartment & Amenity Buildings:



VIEW 1. VIEW TO RESIDENT ENTRY, LOOKING NORTH



VIEW 2. VIEW TO AMENITY BUILDING



VIEW 3. VIEW TO POOL DECK



VIEW 4. VIEW TO FITNESS CENTER/ CLUBROOM AND POOL

CONCEPT IMAGERY

McDermott Mixed-Use McDermott and Ustick, MERIDIAN, ID
Plan JOB # 21-059

v1
06.30.2022

pivot north
ARCHITECTURE



VIEW 5. VIEW TO RESIDENT BUILDING, LOOKING NORTH WEST



VIEW 6. VIEW TO RESIDENT BUILDING, LOOKING SOUTH EAST



VIEW 7. VIEW TO RESIDENT COMMUNITY FROM FUTURE HIGHWAY



VIEW 8. AERIAL VIEW TO AMENITY BUILDING


CONCEPT IMAGERY

v2
06.30.2022

McDermott Mixed-Use McDermott and Ustick, MERIDIAN, ID
PNa JOB # 21-059




1. STREET (NORTH) ELEVATION



2. STREET (WEST) ELEVATION



3. HWY16 (EAST) ELEVATION



4. INTERIOR DRIVE (NORTH) ELEVATION

CONCEPT ELEVATION VIEWS

SCALE: 1/16" = 1'-0" @ 24x36


01
06.30.2022

McDermott Mixed-Use McDermott and Ustick, MERIDIAN, ID
PNa JOB # 21-059






1. OPEN SPACE (SOUTH) ELEVATION



2. (WEST) ELEVATION



3. (EAST) ELEVATION



4. INTERIOR DRIVE (NORTH) ELEVATION

CONCEPT ELEVATION VIEWS

SCALE: 1/16" = 1'-0" @ 24x36

McDermott Mixed-Use


McDermott and Ustick, MERIDIAN, ID
PNa JOB # 21-059

02
06.30.2022

pivot north
ARCHITECTURE




1. CLUBHOUSE ENTRY (SOUTH) ELEVATION



2. (WEST) ELEVATION



3. (EAST) ELEVATION



4. CLUBHOUSE POOL DECK (NORTH) ELEVATION

CONCEPT ELEVATION VIEWS


SCALE: 1/16" = 1'-0" @ 24x36

McDermott Mixed-Use

McDermott and Ustick, MERIDIAN, ID
PNa JOB # 21-059

03
06.30.2022

pivot north
ARCHITECTURE



NOTE: NUMBERS DENOTE MATERIALS LETTERS DENOTE COLORS

NOTE: ALL MATERIALS AS NOTED OR OWNER APPROVED EQUAL

CONCEPT DETAIL/ MATERIAL BOARD


McDermott Mixed-Use

McDermott and Ustick, MERIDIAN, ID
 PNa JOB # 21-059



06.29.2022
 XX

J. ITD's Plan for the Ustick Rd./SH-16 Interchange



REVISIONS			
NO.	DATE	BY	DESCRIPTION

DESIGNED	B. STARK
DESIGN CHECKED	D. WITTHAUS
DETAILED	J. GRAVES
DRAWING CHECKED	D. WITTHAUS

IDAHO TRANSPORTATION DEPARTMENT
 YOUR Safety • YOUR Mobility • YOUR Economic Opportunity
DAVID EVANS ASSOCIATES INC.

PROJECT NO.	A023(408)
ROADWAY PLAN SHEET	SH-16, USTICK RD TO US-20/26 ADA AND CANYON COUNTY USTICK ROAD
STA.	2025+60 TO STA. 2030+40

ENGLISH
 COUNTY ADA & CANYON
 KEY NUMBER 23408
 SHEET 191 OF 762

VIII. CITY/AGENCY COMMENTS & CONDITIONS

A. PLANNING DIVISION

1. A Development Agreement (DA) is required as a provision of annexation of this property. Prior to approval of the annexation ordinance, a DA shall be entered into between the City of Meridian, the property owner(s) at the time of annexation ordinance adoption, and the developer.

Currently, a fee of \$303.00 shall be paid by the Applicant to the Planning Division prior to commencement of the DA. The DA shall be signed by the property owner and returned to the Planning Division within six (6) months of the City Council granting the annexation. The DA shall, at minimum, incorporate the following provisions:

- a. Development of the subject property shall be generally consistent with the conceptual development plan, site plan, preliminary plat, conceptual phasing plan, landscape plan, open space and site amenity exhibits, and conceptual building elevations submitted with the application contained herein.
- b. The two (2) commercial buildings proposed on the northern portion of the site shall be arranged to create some form of common, usable gathering area, such as a plaza or green space as depicted on the conceptual development plan in accord with the mixed-use guidelines in the [Comprehensive Plan](#) (see pg. 3-13).
- c. A minimum 25-foot wide buffer shall be provided on the C-G zoned property to the adjacent residential use to the west (Flower #S0432438850) and to the future multi-family residential uses in this development as set forth in UDC [Table 11-2B-3](#), unless such width is otherwise modified by City Council at a public hearing with notice to surrounding property owners as set forth in UDC [11-3B-9C.2](#). The buffer shall be landscaped in accord with the standards listed in UDC [11-3B-9C](#). *Note: If the land use on the Flower property changes to non-residential prior to development of the subject property, a buffer to residential uses is not required.*
- d. Noise mitigation shall be provided within the buffers along future SH-16 in accord with the standards listed in UDC [11-3H-4D](#) for residential uses adjoining a state highway.
- e. Private streets shall be required within the multi-family development for addressing purposes and shall comply with the standards listed in UDC [11-3F-4](#). The private street application shall be submitted prior to or concurrently with the final plat application.
- f. A 10-foot wide multi-use pathway shall be provided within the street buffers along SH-16 within a 14-foot wide public use easement.
- g. The final plat shall be recorded prior to issuance of building permits for any structures within this development.
- h. All future structures constructed on this site shall comply with the applicable design standards contained in the Architectural Standards Manual.

Preliminary Plat:

2. The final plat shall include the following revisions:
 - a. Include a note granting cross-access/ingress-egress easements between all commercial lots in the subdivision via a note on the final plat or a separate recorded easement.

- b. Depict all street landscape buffers in a common lot or on a permanent dedicated buffer easement, maintained by the property owner, homeowner's association or business owners' association as set forth in UDC [11-3B-7C.2a](#). *A minimum 35-foot wide buffer is required along future SH-16 and the interchange and along N. McDermott Rd., entryway corridors; a minimum 25-foot wide buffer is required along the western portion of W. Ustick Rd., an arterial street; and a minimum 10-foot wide buffer is required along local streets in the C-G zoning district, measured per the standards listed in UDC [11-3B-7C.1](#).*
 - c. Depict the easements for all waterways (i.e. the Sky Pilot Drain, the Eight Mile Lateral and the Noble Lateral) on the site; structures shall not encroach within these easements. *A License Agreement is required with NMID for any encroachments within the easements. If the location of the Eight Mile lateral changes, the new location shall be depicted on the plat.*
 - d. All R-15 zoned lots shall be a minimum of 2,000 square feet as set forth in UDC [Table 11-2A-7](#).
 - e. Graphically depict zero (0) lot lines on the internal lot lines where the townhomes are proposed (i.e. where structures will span across lot lines).
3. The landscape plan submitted with the final plat shall be revised as follows:
 - a. Depict the bollards proposed to restrict access to the emergency access driveway off W. Ustick Rd. completely outside of the right-of-way.
 - b. Depict a 10-foot wide multi-use pathway within the street buffers along SH-16 within a 14-foot wide public use easement; the easement shall be submitted to the Planning division prior to submittal of the final plat for City Engineer signature.
 - c. Depict landscaping along all pathways as set forth in UDC [11-3B-12C](#).
 - d. Landscaping is required within the street buffer as set forth in UDC [11-3B-7C](#). (*See updated standards.*)
 - e. Depict landscaping within common open space areas as set forth in UDC 11-3G-5B.3.
 - f. Change the Fraxinus Pennsylvanica "Marshall's Seedless" Green Ash tree to another variety per the City Arborists' comments.
 - g. Depict a minimum of two (2) points of site amenities for the townhome portion of the development from the Site Amenities and Point Value [Table 11-3G-4](#). **The Applicant should clarify prior to or at the Commission hearing what amenities are proposed.**
 4. Future development shall be consistent with the minimum dimensional standards listed in UDC Tables [11-2A-7](#) for the R-15 district and [11-2A-8](#) for the R-40 district; and UDC Table [11-2B-3](#) for the C-G zoning district.
 5. All waterways on this site shall be piped as set forth in UDC [11-3A-6B](#), unless otherwise waived by City Council.
 6. Cross-access/ingress-egress easements shall be provided between all commercial C-G zoned lots in the subdivision via a note on the final plat or a separate recorded easement.
 7. The emergency access driveway required and approved by the Fire Dept. off W. Ustick Rd. east of future SH-16 shall be approved by ITD as it's located within the influence area of their intersection project.
 8. All alleys shall comply with the standards listed in UDC [11-6C-3B.5](#).

Conditional Use Permit:

9. Compliance with the specific use standards listed in UDC [11-4-3-27](#): Multi-Family Development and the dimensional standards listed in UDC [Table 11-2A-8](#) is required.
10. The site/landscape plans included in Section VII shall be revised as follows:
 - a. All on-site service areas, outdoor storage areas, waste storage, disposal facilities, and transformer and utility vaults shall be located in an area not visible from a public street, or shall be fully screened from view from a public street in accord with UDC [11-4-3-27B.2](#).
 - b. Depict the location of the property management office; maintenance storage area; central mailbox location, including provisions for parcel mail, that provide safe pedestrian and/or vehicular access; and a directory and map of the development at an entrance or convenient location for those entering the development in accord with UDC [11-4-3-27B.7](#).
 - c. Depict safe pathway connections from the proposed multi-family development to the abutting high school to the west.
 - f. Depict landscaping along all the foundation of all street facing elevations in accord with the standards listed in UDC [11-4-3-27E](#).
 - g. Depict landscaping along all pathways per the standards listed in UDC [11-3B-12C](#). *A mix of trees, shrubs, lawn and/or other vegetative ground cover with a minimum of one (1) tree per 100 linear feet of pathway.*
 - i. Depict a minimum of 20 bicycle parking spaces per the standards listed in UDC 11-3C-6G; bicycle parking facilities shall comply with the standards listed in UDC [11-3C-5C](#). Bike racks should be provided in central locations for each multi-family building and the amenity building.
 - j. Depict a minimum of 495 off-street parking spaces for the development in accord with the standards listed in UDC [Table 11-3C-6](#) and [11-3C-6B.1](#) per the analysis in Section VI.
 - k. At a minimum, depict site amenities consisting of the following: a clubhouse with a fitness facility, a swimming pool and spa with cabanas and an outdoor lounge area; 10-foot wide multi-use pathways and internal walking trails; a plaza; a pickleball sports court; a bike repair station; a commercial outdoor kitchen with a BBQ; a picnic area with tables, benches, landscaping and a shade structure; and a children’s play structure.
 - k. Minimum 7-foot wide sidewalks shall be provided where parking abuts sidewalks if wheel stops aren’t proposed to prevent vehicle overhang in accord with UDC 11-3C-5B4; if 7-foot sidewalks are proposed, the length of the stall may be reduced to 17 feet.
11. No recreational vehicles, snowmobiles, boats or other personal recreation vehicles shall be stored on the site unless provided for in a separate, designated and screened area as set forth in UDC 11-4-3-27B.5.
12. All multi-family developments shall record legally binding documents that state the maintenance and ownership responsibilities for the management of the development, including, but not limited to, structures, parking, common areas, and other development features as set forth in UDC [11-4-3-27F](#). **A recorded copy of the document shall be submitted prior to issuance of the first Certificate of Occupancy for the development.**

13. In phased developments, common open space shall be provided in each phase of the development consistent with the requirements for the size and number of dwelling units in accord with UDC [11-4-3-27C.6](#).
14. A Certificate of Zoning Compliance and Design Review application is required to be submitted for approval of the multi-family and commercial development to ensure compliance with UDC standards and development provisions associated with this application. A Design Review application is required to be submitted for approval of the townhomes. Final design of all structures must comply with the design standards in the Architectural Standards Manual.

B. PUBLIC WORKS

1. Site Specific Conditions of Approval

- 1.1 There is a sewer loop on the northern section. Sewer connects to McDermont in Block 1 and the existing SSMH-06. Reconfigure the design so this is removed.
- 1.2 Manhole SSMH-11 and SSMH-12 has angles of pipe in/out of manhole at less than 90 degrees. Adjust these manholes so min angle of pipe through manhole is 90 degrees.
- 1.3 Provide Steel Casing for all locations where sewer crosses future Hwy 16 per City's casing requirements.
- 1.4 All manholes require 14ft graveled/paved access path.
- 1.5 End of the line requires minimum 0.6% slope.
- 1.6 Ensure manholes are not located in curb/gutter.
- 1.7 Sewer/water easement varies depending on sewer depth. Sewer 0-20 ft deep require a 30 ft easement, 20-25 ft a 40 ft easement, and 25-30 ft a 45 ft easement. Adjust easements accordingly.
- 1.8 Area is subject to the Oaks Lift Station and Pressure Sewer Reimbursement agreement.
- 1.9 No permanent structures (trash receptacle walls, trees, bushes, buildings, carports, fences, infiltration trenches, light poles, etc.) are to be built within the utility easement.
- 1.10 Sewer must be built 10ft from edge of easement.
- 1.11 Ensure no sewer services pass through infiltration trenches.
- 1.12 12-inch water main must be built to and through the development on McDermott Road. On west side of future SH-16, water must connect to north.
- 1.13 A streetlight plan will be required for the development of this property.

2. General Conditions of Approval

- 2.1 Applicant shall coordinate water and sewer main size and routing with the Public Works Department, and execute standard forms of easements for any mains that are required to provide service outside of a public right-of-way. Minimum cover over sewer mains is three feet, if cover from top of pipe to sub-grade is less than three feet then alternate materials shall be used in conformance of City of Meridian Public Works Departments Standard Specifications.
- 2.2 Per Meridian City Code (MCC), the applicant shall be responsible to install sewer and water mains to and through this development. Applicant may be eligible for a reimbursement agreement for infrastructure enhancement per MCC 8-6-5.

- 2.3 The applicant shall provide easement(s) for all public water/sewer mains outside of public right of way (include all water services and hydrants). The easement widths shall be 20-feet wide for a single utility, or 30-feet wide for two. The easements shall not be dedicated via the plat, but rather dedicated outside the plat process using the City of Meridian's standard forms. The easement shall be graphically depicted on the plat for reference purposes. Submit an executed easement (on the form available from Public Works), a legal description prepared by an Idaho Licensed Professional Land Surveyor, which must include the area of the easement (marked EXHIBIT A) and an 8 1/2" x 11" map with bearings and distances (marked EXHIBIT B) for review. Both exhibits must be sealed, signed and dated by a Professional Land Surveyor. **DO NOT RECORD.** Add a note to the plat referencing this document. All easements must be submitted, reviewed, and approved prior to development plan approval.
- 2.4 The City of Meridian requires that pressurized irrigation systems be supplied by a year-round source of water (MCC 12-13-8.3). The applicant should be required to use any existing surface or well water for the primary source. If a surface or well source is not available, a single-point connection to the culinary water system shall be required. If a single-point connection is utilized, the developer will be responsible for the payment of assessments for the common areas prior to receiving development plan approval.
- 2.5 All existing structures that are required to be removed shall be prior to signature on the final plat by the City Engineer. Any structures that are allowed to remain shall be subject to evaluation and possible reassignment of street addressing to be in compliance with MCC.
- 2.6 All irrigation ditches, canals, laterals, or drains, exclusive of natural waterways, intersecting, crossing or laying adjacent and contiguous to the area being subdivided shall be addressed per UDC 11-3A-6. In performing such work, the applicant shall comply with Idaho Code 42-1207 and any other applicable law or regulation.
- 2.7 Any wells that will not continue to be used must be properly abandoned according to Idaho Well Construction Standards Rules administered by the Idaho Department of Water Resources. The Developer's Engineer shall provide a statement addressing whether there are any existing wells in the development, and if so, how they will continue to be used, or provide record of their abandonment.
- 2.8 Any existing septic systems within this project shall be removed from service per City Ordinance Section 9-1-4 and 9 4 8. Contact Central District Health for abandonment procedures and inspections (208)375-5211.
- 2.9 Street signs are to be in place, sanitary sewer and water system shall be approved and activated, road base approved by the Ada County Highway District and the Final Plat for this subdivision shall be recorded, prior to applying for building permits.
- 2.10 A letter of credit or cash surety in the amount of 110% will be required for all uncompleted fencing, landscaping, amenities, etc., prior to signature on the final plat.
- 2.11 All improvements related to public life, safety and health shall be completed prior to occupancy of the structures. Where approved by the City Engineer, an owner may post a performance surety for such improvements in order to obtain City Engineer signature on the final plat as set forth in UDC 11-5C-3B.
- 2.12 Applicant shall be required to pay Public Works development plan review, and construction inspection fees, as determined during the plan review process, prior to the issuance of a plan approval letter.

- 2.13 It shall be the responsibility of the applicant to ensure that all development features comply with the Americans with Disabilities Act and the Fair Housing Act.
- 2.14 Applicant shall be responsible for application and compliance with any Section 404 Permitting that may be required by the Army Corps of Engineers.
- 2.15 Developer shall coordinate mailbox locations with the Meridian Post Office.
- 2.16 All grading of the site shall be performed in conformance with MCC 11-12-3H.
- 2.17 Compaction test results shall be submitted to the Meridian Building Department for all building pads receiving engineered backfill, where footing would sit atop fill material.
- 2.18 The design engineer shall be required to certify that the street centerline elevations are set a minimum of 3-feet above the highest established peak groundwater elevation. This is to ensure that the bottom elevation of the crawl spaces of homes is at least 1-foot above.
- 2.19 The applicants design engineer shall be responsible for inspection of all irrigation and/or drainage facility within this project that do not fall under the jurisdiction of an irrigation district or ACHD. The design engineer shall provide certification that the facilities have been installed in accordance with the approved design plans. This certification will be required before a certificate of occupancy is issued for any structures within the project.
- 2.20 At the completion of the project, the applicant shall be responsible to submit record drawings per the City of Meridian AutoCAD standards. These record drawings must be received and approved prior to the issuance of a certification of occupancy for any structures within the project.
- 2.21 A street light plan will need to be included in the civil construction plans. Street light plan requirements are listed in section 6-5 of the Improvement Standards for Street Lighting. A copy of the standards can be found at http://www.meridiancity.org/public_works.aspx?id=272.
- 2.22 The City of Meridian requires that the owner post to the City a performance surety in the amount of 125% of the total construction cost for all incomplete sewer, water and reuse infrastructure prior to final plat signature. This surety will be verified by a line item cost estimate provided by the owner to the City. The surety can be posted in the form of an irrevocable letter of credit, cash deposit or bond. Applicant must file an application for surety, which can be found on the Community Development Department website. Please contact Land Development Service for more information at 887-2211.
- 2.23 The City of Meridian requires that the owner post to the City a warranty surety in the amount of 20% of the total construction cost for all completed sewer, water and reuse infrastructure for duration of two years. This surety will be verified by a line item cost estimate provided by the owner to the City. The surety can be posted in the form of an irrevocable letter of credit, cash deposit or bond. Applicant must file an application for surety, which can be found on the Community Development Department website. Please contact Land Development Service for more information at 887-2211.

C. FIRE DEPARTMENT

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=272855&dbid=0&repo=MeridianCity>

D. POLICE DEPARTMENT

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=279522&dbid=0&repo=MeridianCity>

E. NAMPA & MERIDIAN IRRIGATION DISTRICT (NMID)

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=273744&dbid=0&repo=MeridianCity>

F. COMMUNITY PLANNING ASSOCIATION OF SOUTHWEST IDAHO (COMPASS)

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=276592&dbid=0&repo=MeridianCity>

G. WEST ADA SCHOOL DISTRICT (WASD)

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=279662&dbid=0&repo=MeridianCity&cr=1>

H. PARK'S DEPARTMENT

City Arborist:

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=272795&dbid=0&repo=MeridianCity>

I. COMMUNITY DEVELOPMENT SCHOOL IMPACT

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=275929&dbid=0&repo=MeridianCity>

J. ADA COUNTY DEVELOPMENT SERVICES

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=273537&dbid=0&repo=MeridianCity&cr=1>

K. IDAHO TRANSPORTATION DEPARTMENT (ITD)

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=278192&dbid=0&repo=MeridianCity>

L. ADA COUNTY HIGHWAY DISTRICT (ACHD)

<https://weblink.meridiancity.org/WebLink/DocView.aspx?id=275528&dbid=0&repo=MeridianCity>

IX. FINDINGS

A. Annexation and/or Rezone (UDC 11-5B-3E)

Required Findings: Upon recommendation from the commission, the council shall make a full investigation and shall, at the public hearing, review the application. In order to grant an annexation and/or rezone, the council shall make the following findings:

1. The map amendment complies with the applicable provisions of the comprehensive plan;

Staff finds the proposed zoning map amendment to R-15, R-40 and C-G and subsequent development is generally consistent with the Comprehensive Plan and the MU-R FLUM designation.

2. The map amendment complies with the regulations outlined for the proposed district, specifically the purpose statement;

Staff finds the proposed map amendment will allow for the development of commercial uses which will assist in providing for the service needs of area residents; and residential uses which will contribute to the range of housing opportunities in the City consistent with the purpose statement of the commercial and residential districts in accord with the Comprehensive Plan.

3. The map amendment shall not be materially detrimental to the public health, safety, and welfare;

Staff finds the proposed zoning map amendment should not be detrimental to the public health, safety and welfare.

4. The map amendment shall not result in an adverse impact upon the delivery of services by any political subdivision providing public services within the city including, but not limited to, school districts; and

Staff finds the proposed zoning map amendment will not result in an adverse impact on the delivery of services by any political subdivision providing public services within the City.

5. The annexation (as applicable) is in the best interest of city.

Staff finds the proposed annexation is in the best interest of the City.

B. Preliminary Plat:

In consideration of a preliminary plat, combined preliminary and final plat, or short plat, the decision-making body shall make the following findings:

1. The plat is in conformance with the Comprehensive Plan;

Staff finds that the proposed plat is in substantial compliance with the adopted Comprehensive Plan in regard to land use and transportation. (Please see Comprehensive Plan Policies in, Section IV of this report for more information.)

2. Public services are available or can be made available and are adequate to accommodate the proposed development;

Staff finds that public services will be provided to the subject property with development. (See Exhibit B of the Staff Report for more details from public service providers.)

3. The plat is in conformance with scheduled public improvements in accord with the City's capital improvement program;

Because City water and sewer and any other utilities will be provided by the development at their own cost, Staff finds that the subdivision will not require the expenditure of capital improvement funds.

4. There is public financial capability of supporting services for the proposed development;

Staff finds there is public financial capability of supporting services for the proposed development based upon comments from the public service providers (i.e., Police, Fire, ACHD, etc.). (See Section VIII for more information.)

5. The development will not be detrimental to the public health, safety or general welfare; and,
Staff is not aware of any health, safety, or environmental problems associated with the platting of this property. ACHD considers road safety issues in their analysis.
6. The development preserves significant natural, scenic or historic features.
Staff is unaware of any significant natural, scenic or historic features that exist on this site that require preserving.

C. Conditional Use Permit (UDC 11-5B-6E)

The Commission shall base its determination on the Conditional Use Permit requests upon the following:

1. That the site is large enough to accommodate the proposed use and meet all the dimensional and development regulations in the district in which the use is located.
Staff finds that the subject property is large enough to accommodate the proposed use and dimensional and development regulations of the R-40 zoning district (see Analysis, Section V for more information).
2. That the proposed use will be harmonious with the Meridian Comprehensive Plan and in accord with the requirements of this Title.
Staff finds that the proposed use is consistent with the future land use map designation of MU-R and is allowed as a conditional use in UDC Table 11-2B-2 in the R-40 zoning district.
3. That the design, construction, operation and maintenance will be compatible with other uses in the general neighborhood and with the existing or intended character of the general vicinity and that such use will not adversely change the essential character of the same area.
Staff finds the proposed design of the development, construction, operation and maintenance should be compatible with the mix of other uses planned for this area and with the intended character of the area and that such uses will not adversely change the character of the area.
4. That the proposed use, if it complies with all conditions of the approval imposed, will not adversely affect other property in the vicinity.
Staff finds that if the applicant complies with the conditions outlined in this report, the proposed use will not adversely affect other property in the area. The Commission and Council should weigh any public testimony provided to determine if the development will adversely affect other properties in the vicinity.
5. That the proposed use will be served adequately by essential public facilities and services such as highways, streets, schools, parks, police and fire protection, drainage structures, refuse disposal, water, and sewer.
Staff finds that essential public services are available to this property and that the use will be adequately served by these facilities.