

License # 2705 128824
Classifications H/H, LSC, PAV, CEM, RBC

Roc Construction LLC

Asphalt Paving Concrete Construction Demolition Hauling Sitework

P.O. Box 1401
Glen Allen Va. 23060
P- 804-615-3699
F- 804-723-5404

INVOICE

Date: 7-10-26

Contract Description: Asphalt Paving

Location: 2779 Pendleton Rd Mineral Va 23117

Customer: Spring Grove Memorial Park

Contract scope of work:

1. **Prep paved roads for asphalt. Approximately 44,000 square feet.**
2. **Overlay paved roads with 2 inches of SM 9.5A asphalt.**

Notes: net 15 days on completion. Job will take approximately 3 days to complete.

Total Price: \$116,950.00

Customer Signature

Roc Construction LLC

PROPOSAL

BARTON & BOYD, INC.
P.O. BOX 294, 4168 Davis Highway
LOUISA, VA 23093

OFFICE# (540) 967-0408

bartonboyd@yahoo.com

FAX# (540) 967-1596

Submitted to Town of Mineral c/o Pam Harlowe	Phone 540-894-6508	Date 06/17/2026
Street PO Box 316	Job Name: Spring Grove Cemetary	
City, State and Zip Code Mineral, VA 23117	Job Location	
Email: pharlowe@townonmineral.net	Job Phone	

WE HEREBY SUBMIT THE FOLLOWING SPECIFICATIONS AND ESTIMATES:

Pricing Based On Material And Haul Rate As Of 06/17/26.

Due To The Fluctuating Cost Of Fuel And Materials, Prices May Be Adjusted Accordingly At The Time The Work Is Performed.

GUESSTIMATE FOR BUDGET PURPOSES ONLY
AREA & SPECIFICATIONS TO BE VERIFIED

ASPHALT OPTION

Approximately 5247 Square Feet

Clean	5500.00
Patch With Asphalt – Approx. 32 Tons @ \$150.00 Per Ton*	4800.00
Apply 2" Asphalt Overlay	82200.00
2 Days Traffic Control	6000.00
Total	\$ 98500.00

**Asphalt For Patching Will Be Billed By The Actual Tons Used.*

Exclusions: Grading; Base Stone And/Or Base Stone Installation; Material Testing; Density Testing; Compaction Testing; Obtaining Grade Profiles; Permits; Vegetation Removal; Pavement Markings; Locating, Marking, Moving And/Or Damage To Utilities; Backfilling Edges; Shoulder Work; Ditch Work; Pipe Work; Etc.

We Propose Hereby To Furnish Material And Labor - Complete In Accordance With Above Specifications, For The Sum Of:
Dollars (\$)

PAYMENT TO BE MADE AS FOLLOWS: UPON COMPLETION

Any Balance Not Paid Within 30 Days Shall Bear Interest At 2% Per Month. In The Event Any Obligation Of Customer Hereunder Is Breached, Any And All Attorney And/Or Legal Fees Will Be Payable By Customer.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized

Signature *Michael Pleasants/dcs*

Note: This Proposal May Be
Withdrawn By Us If Not Accepted Within N/A Days.

Acceptance Of Proposal - The Above Prices, Specifications And Conditions Are Satisfactory And Are Hereby Accepted.
You Are Authorized To Do The Work As Specified. Payment Will Be Made As Outlined Above.

Signature: _____

Date Of Acceptance: _____

Signature: _____

PROPOSAL

BARTON & BOYD, INC.

P.O. BOX 294, 4168 Davis Highway

LOUISA, VA 23093

OFFICE# (540) 967-0408

bartonboyd@yahoo.com

FAX# (540) 967-1596

Submitted to Town of Mineral c/o Pam Harlowe	Phone 540-894-6508	Date 06/17/2026
Street PO Box 316	Job Name: Spring Grove Cemetary	
City, State and Zip Code Mineral, VA 23117	Job Location	
Email: pharlowe@townofmineral.net		Job Phone

WE HEREBY SUBMIT THE FOLLOWING SPECIFICATIONS AND ESTIMATES:

Pricing Based On Material And Haul Rate As Of 06/17/26.

Due To The Fluctuating Cost Of Fuel And Materials, Prices May Be Adjusted Accordingly At The Time The Work Is Performed.

GUESSTIMATE FOR BUDGET PURPOSES ONLY

AREA & SPECIFICATIONS TO BE VERIFIED

TAR & GRAVEL OPTION

Approximately 5247 Square Feet

Clean	5500.00
Patch With Asphalt – Approx. 32 Tons @ \$200.00 Per Ton*	6400.00
Apply 2 Shots Tar & Gravel With Brown Stone	38725.00
1 Day Traffic Control	3000.00
Total	\$ 53625.00

*Asphalt For Patching Will Be Billed By The Actual Tons Used.

Exclusions: Grading; Base Stone And/Or Base Stone Installation; Material Testing; Density Testing; Compaction Testing; Obtaining Grade Profiles; Permits; Vegetation Removal; Pavement Markings; Locating, Marking, Moving And/Or Damage To Utilities; Backfilling Edges; Shoulder Work; Ditch Work; Pipe Work; Etc.

We Propose Hereby To Furnish Material And Labor - Complete In Accordance With Above Specifications, For The Sum Of: Dollars (\$)

PAYMENT TO BE MADE AS FOLLOWS: UPON COMPLETION

Any Balance Not Paid Within 30 Days Shall Bear Interest At 2% Per Month. In The Event Any Obligation Of Customer Hereunder Is Breached, Any And All Attorney And/Or Legal Fees Will Be Payable By Customer.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized

Signature Michael Pleasants/dca

Note: This Proposal May Be
Withdrawn By Us If Not Accepted Within N/A Days.

Acceptance Of Proposal - The Above Prices, Specifications And Conditions Are Satisfactory And Are Hereby Accepted.
You Are Authorized To Do The Work As Specified. Payment Will Be Made As Outlined Above.


Signature: _____

Date Of Acceptance: _____

Signature: _____

Pyramid Paving LLC

3468 S BOSTON RD
TROY, VA 22974-3828 USA
+14345290975
lauren@pyramidpavingllc.com



Estimate

ADDRESS
Pam Harlowe
Town of Mineral

ESTIMATE 6728
DATE 07/14/2027
EXPIRATION DATE 09/01/2026

PROJECT NAME
Grave Yard - Tar & Chip

SALES REP
Kenny

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Tar & Chip	We will sweep all loose debris and dispose of it. After all rock is clean we will begin spraying the first coat of RC 250 and place the first layer of 68 grey stone. If you would like to go back with the brown stone we will have to give you another quote as it's hard to get and very high on coat. After first shot is down and rolled we well begin one more coat of tar and gravel. Total area being tar and gravel 35,440 SF	1	42,468.81	42,468.81
	Additional Info.	This quote is based on a liquid asphalt price not to exceed \$781.25/ton. Due to the volatility in the liquid asphalt market; the price will be based on the inflation of liquid asphalt per the VDOT Asphalt Index at the time of construction. Drainage will not be guaranteed on paved areas having 1% grade or less.	1	0.00	0.00


TOTAL \$42,468.81

Accepted By

Accepted Date

Pyramid Paving LLC

3468 S BOSTON RD
TROY, VA 22974-3828 USA
+14345290975
lauren@pyramidpavingllc.com



Estimate

ADDRESS
Pam Harlowe
Town of Mineral

ESTIMATE
DATE
EXPIRATION DATE

6729
07/14/2027
09/01/2026

PROJECT NAME
Grave Yard Asphalt

SALES REP
Kenny

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Overlay Existing Pavement	We will start by sweeping all the debris/ loose stone off the road. We will cut a tie-end joint at the end where the V-DOT road starts for a good smooth joint. After all loose stone is gone we will spray RC 250 tac coat for a good bond between the old and new asphalt. Pave 2.5 inches of sm 9.5 topping mix compacted to 2 inches. Total area being cleaned and paved is. 35,440 SF.	1	71,885.88	71,885.88
	Additional Info.	This quote is based on a liquid asphalt price not to exceed \$781.25/ton. Due to the volatility in the liquid asphalt market; the price will be based on the inflation of liquid asphalt per the VDOT Asphalt Index at the time of construction. Drainage will not be guaranteed on paved areas having 1% grade or less.	1	0.00	0.00

TOTAL

\$71,885.88

Accepted By

Accepted Date