



***** Customer Review *****
 Date / Time: 7/24/2025 1:31:08PM
 Repair Order: 500
 Customer: 384625
 Branch: UNIT 03
 Invoice Total: \$73,729.74
 on account
 Page 1 of 2

Bill To: MOBERLY FIRE DEPARTMENT
 310 N CLARK
 MOBERLY, MO 65270-1520
 Shop: 660/269-8705 X 2032Fax: 660/263-0596

Ship To: MOBERLY FIRE DEPARTMENT
 310 N CLARK
 MOBERLY, MO 65270-1520

Customer P/O Created By Completion Date
 Ryans

Task: 1 83-010006 Install compressor and perform startup procedure Department: Service

Complaint: Estimate to provide and install a Verticus VAC13- E3, 3 phase breathing air compressor capable of 13 CFM. Includes installation and all travel fees.
 Banner requires that the cascade bottles are within current hydrotest standards before plumbing to compressor. Electrical service will be verified before order. Freight charges are estimated and may vary by 5%. Approximate lead time is 45 days and installation shall be scheduled within 7 days of delivery.

Supp.	Part	Description / Ref Number	U/M	Quantity	Price	Ext Price
	FORKLIFT	Forklift rental	Misc	1.00	1,500.00	1,500.00
	Air test	air test lab fee	Misc	1.00	105.00	105.00
	EQUIP IN	Shipping and Handling Inbound - Equipment	Misc	1.00	1,800.00	1,800.00
	SUPPLIES	Misc hardware/supplies	Misc	1.00	37.00	37.00
	VAC13H-E3	Verticus 6000psi Breathing Air Compressor 3 phase	Part	Each 1.00	38,112.48	38,112.48
	GT/CO/III	ELECTRONIC CO MONITOR W/CAL	Part	Each 1.00	4,295.76	4,295.76

Task 1 Subtotals: Parts: \$42,408.24
 Labor: \$740.00
 Miscellaneous: \$3,442.00
Task 1 Totals: \$46,590.24

Task: 2 83-0100101 Provide and install cascade system Department: Service

Complaint: Estimate to provide and install CFS5.5-2, 2- position fill station with cascade controls, and plumb (4) 6000 psi cascade bottle to compressor unit

Supp.	Part	Description / Ref Number	U/M	Quantity	Price	Ext Price
	EQUIP IN	Shipping and Handling Inbound - Equipment	Misc	1.00	2,225.00	2,225.00
	SUPPLIES	Misc hardware/supplies	Misc	1.00	37.00	37.00
	AC10034	Nut/Nipple,7500,702,BR	Part	Each 4.00	41.60	166.40
	AC20022-1	Tee,6000,Street,1/4 M-Run,1/4 JIC-M,ST	Part	Each 1.00	32.33	32.33
	AC20023-1	TEE,FEMALE BRANCH.25FPPTX.25JIC	Part	Each 3.00	30.48	91.44
	AC20161	Cap, 7500, JIC #4 ST	Part	Each 1.00	9.53	9.53
	AC40060	AIR CYLINDER,6000 UN-ISO-DOT	Part	Each 4.00	1,995.00	7,980.00
	AC70080	RACK,DOT-1 EA, WALL W/ CLAMP	Part	Each 4.00	62.38	249.52
	AC80049-10	6000 PSI HOSE X 10'	Part	Each 1.00	176.25	176.25
	AC80052	PIGTAIL ASSY, 6000PSI	Part	Each 3.00	53.33	159.99
	CFS5.5-2SSP	CFS5.5-2S 2 POS Fill Station Spec Package	Part	Each 1.00	15,272.04	15,272.04

Dual function, top-mount, four bank cascade control panel.

Task 2 Subtotals: Parts: \$24,137.50



***** Customer Review *****

Date / Time: 7/24/2025 1:31:08PM
 Repair Order: 500
 Customer: 384625
 Branch: UNIT 03
 Invoice Total: \$73,729.74

on account
 Page 2 of 2

Bill To: MOBERLY FIRE DEPARTMENT
 310 N CLARK
 MOBERLY, MO 65270-1520
 Shop: 660/269-8705 X 2032 Fax: 660/263-0596

Ship To: MOBERLY FIRE DEPARTMENT
 310 N CLARK
 MOBERLY, MO 65270-1520

<u>Customer P/O</u>	<u>Created By</u>	<u>Completion Date</u>
	Ryans	

Labor:	\$740.00
Miscellaneous:	\$2,262.00
Task 2 Totals:	\$27,139.50

QUOTE

Totals	
Total Parts:	\$66,545.74
Total Core Chg:	\$0.00
Total Core Ret:	\$0.00
Total EHC:	\$0.00
Total Labor:	\$1,480.00
Total Miscellaneous:	\$5,704.00
Invoice Subtotal:	\$73,729.74
Total Tax:	\$0.00
Invoiced Total:	\$73,729.74

Payment Method
 Charge

ESTIMATE ONLY!
 PRICES SUBJECT TO CHANGE. CUSTOMER WILL BE NOTIFIED OF ANY CHANGES PRIOR TO ADDITIONAL WORK BEING PERFORMED. PRICING GOOD FOR (90) DAYS. STOCK PARTS RETURNED AFTER (30) DAYS ARE SUBJECT TO 25% RESTOCK FEE. ELECTRONIC COMPONENTS AND SPECIAL ORDER PARTS ARE NOT RETURNABLE. DUE TO VARIANCES IN COSTS AND AVAILABILITY THIS ESTIMATE CAN VARY UP TO 5%. IF ANY QUESTIONS, PLEASE CALL 618-251-4200.
 THANK YOU FOR YOUR BUSINESS!