



Reliable Pump, Inc.  
 P.O. Box 31115  
 Las Vegas, NV 89173  
 Ph: 702-243-5116 Fax: 702-240-9319

# Estimate

Date	Estimate #
2/18/2026	21176

<b>Name / Address</b>
City of Needles 817 Third Street Needles, CA 92363

<b>Ship To</b>
City of Needles 817 Third Street Needles, CA 92363 USA

<b>P.O. No.</b>	<b>Terms</b>	<b>Ship Via</b>	<b>FOB</b>	<b>Rep</b>
	Net 30	Will Call	Factory, FFA	BB(I)

Item	Description	Qty	Price	Total
	RE: Estimate to repair one Hydromatic Model S12LXP4000FA, 40 HP, 460 V, 3 PH, 60 HZ, 870 RPM, 14.25 IMP DIA, 61.00 FLA, SN: 10726414, Date Code: 01/22, Explosion Proof Pump.			
	2/18 - Revised to add Rewind per Customer			
	During evaluation our technician found that from the cord cap the pump failed high pot testing due to a split butt connector and insulation wrap that came off, the impeller was bound, lower chamber was filled with water, upper oil was a bit dirty, and rotor shaft is pitted where the lower seal sits. Technician fixed the butt connector and insulation wrap. Pump passed high pot testing and ran normal amps.			
	Estimate below for complete rebuild of pump.			
Diagnostic Fee	Shop labor to inspect and diagnose only. If repair is not approved, or a new replacement is not ordered within 30 days of receipt of estimate this amount will be billed and pump/motor will be subject to disposal.	1	560.00	560.00
Shop	Shop Labor to repair pump	1	1,120.00	1,120.00

*Notice: Due to a global spike in demand, combined with material and labor shortages, we are experiencing shipping delays with some of our manufactures. Any quoted lead times cannot be guaranteed.*

Upon approval, sign at bottom and fax to 702-240-9319.  
 Estimate expires within 30 days from date shown above. Any alteration or deviation from above specifications, involving extra costs will be executed and become an extra charge over and above the Estimate.

<b>Subtotal</b>
<b>Sales Tax (0.0%)</b> <i>Approx \$1,466.09</i>
<b>Total</b> <b>\$20,383.39</b>

Signature: \_\_\_\_\_

Date: \_\_\_\_\_



Reliable Pump, Inc.  
 P.O. Box 31115  
 Las Vegas, NV 89173  
 Ph: 702-243-5116 Fax: 702-240-9319

# Estimate

Date	Estimate #
2/18/2026	21176

<b>Name / Address</b>
City of Needles 817 Third Street Needles, CA 92363

<b>Ship To</b>
City of Needles 817 Third Street Needles, CA 92363 USA

<b>P.O. No.</b>	<b>Terms</b>	<b>Ship Via</b>	<b>FOB</b>	<b>Rep</b>
	Net 30	Will Call	Factory, FFA	BB(I)

Item	Description	Qty	Price	Total
Rewind Labor	Labor to rewind stator	1	2,022.16	2,022.16
Rewind Materials	Materials needed to rewind stator	1	866.64	866.64
Bearing 6309 C3	Bearing - Open	1	130.56	130.56
5316C3 - Bearing	Lower Bearing 5316C3	1	559.44	559.44
03718-300-1	SEAL-SHAFT 3.0 TYPE2100 B/CA/SC	1	942.50	942.50
27996A000	SEAL-SHAFT Silcar/Carbon Nitrile	1	1,228.50	1,228.50
27973D011	Rotor/Shaft Assembly S12LXP, 320 Frame	1	11,212.50	11,212.50
Supplies Income	Misc. Shop Supplies: Oil (11 Gallons), oil disposal, hardware, connectors, etc.	1	275.00	275.00
Insulation Test	Motor insulation test, performed with Crown Model 2109 insulation tester, S/N 020724, 115V 60Hz 6A. Cal. 2-21-25	1	0.00	0.00
	Estimated lead time is 5-7 weeks ARO.			
	No installation is included on this estimate.			

*Notice: Due to a global spike in demand, combined with material and labor shortages, we are experiencing shipping delays with some of our manufactures. Any quoted lead times cannot be guaranteed.*

Upon approval, sign at bottom and fax to 702-240-9319.  
 Estimate expires within 30 days from date shown above. Any alteration or deviation from above specifications, involving extra costs will be executed and become an extra charge over and above the Estimate.

<b>Subtotal</b>	\$18,917.30
<b>Sales Tax (0.0%)</b>	\$0.00
<b>Total</b>	\$18,917.30

Signature: \_\_\_\_\_

Date: \_\_\_\_\_