

### Summary of Piping Changes

Bulletin No. 2 REF	Reach	Original	Proposed	Net Change	Notes
2.A.	16" Main Line	264	209	-55	3x20' 16" Pipe Credit
2.A.	TL#1 & #2 - 16"	95	75	-20	1x20' 16" Pipe Credit
2.B.	DL#1 - 10"	0	0	0	No Change
2.A.	DL#2 - 10"	13	0	-13	1x20' 10" Pipe Credit
1.A.	DL#3 - 10" to 8"	93	49	-44	3x20' 10" Pipe Credit
1.B.	DL#4 - 8"	118	159	41	3x20' 8" Pipe Charge
1.C.	DL #5 - 10" to 8"	174	117	-57	3x20' 10" Pipe Charge
<b>Totals:</b>		<b>757</b>	<b>609</b>	<b>-148</b>	

Item Num	Section	Description	Unit of Measure	Quantity	Unit Price	Total	COR-002 for River Road		COR-003 for Manifold		
							Quantity Adjustment	Added Total	Quantity Adjustment	Added Total	
1	SCHEDULE A, B & C	MOB/DEMOB	LS	1	\$ 55,000.00	\$ 55,000.00		\$ -		\$ -	
2	SCHEDULE A, B & C	MISC COSTS (TC AND SURVEY / STAKING	LS	1	\$ 120,000.00	\$ 120,000.00		\$ -		\$ -	
3	SCHEDULE A, B & C	NPDEX, SWPPP, AND BMPs	LS	1	\$ 7,500.00	\$ 7,500.00		\$ -		\$ -	
4	SCHEDULE A, B & C	ENCROACHMENT PERMIT	EA	1	\$ 1,551.00	\$ 1,551.00		\$ -		\$ -	
5	SCHEDULE A - MANIFOLD	MANIFOLD REPLACEMENT LS	LS	1	\$ 244,000.00	\$ 244,000.00		\$ -		\$ -	
6	SCHEDULE B - RIVER ROAD	8" WATER PIPE	LF	1320	\$ 175.00	\$ 231,000.00		\$ -	200	\$ 35,000.00	
7	SCHEDULE B - RIVER ROAD	6" WATER PIPE	LF	20	\$ 175.00	\$ 3,500.00		\$ -		\$ -	
8	SCHEDULE B - RIVER ROAD	8" BEND	EA	3	\$ 3,000.00	\$ 9,000.00		\$ -		\$ -	
9	SCHEDULE B - RIVER ROAD	6" BEND	EA	2	\$ 3,000.00	\$ 6,000.00		\$ -		\$ -	
10	SCHEDULE B - RIVER ROAD	6" SLEEVE	EA	1	\$ 1,000.00	\$ 1,000.00		\$ -		\$ -	
11	SCHEDULE B - RIVER ROAD	8" GATE VALVE	EA	3	\$ 5,000.00	\$ 15,000.00	2	\$ 10,000.00		\$ -	
12	SCHEDULE B - RIVER ROAD	8" X 6" REDUCER	EA	1	\$ 1,000.00	\$ 1,000.00		\$ -		\$ -	
13	SCHEDULE B - RIVER ROAD	CONCRETE ENCASEMENT	LF	20	\$ 400.00	\$ 8,000.00	30	\$ 12,000.00		\$ -	
14	SCHEDULE B - RIVER ROAD	SERVICE LATERAL REPLACEMENT	EA	1	\$ 3,500.00	\$ 3,500.00	1	\$ 3,500.00		\$ -	
15	SCHEDULE B - RIVER ROAD	PLUG EX. LINE	EA	2	\$ 2,500.00	\$ 5,000.00		\$ -		\$ -	
16	SCHEDULE B - RIVER ROAD	ABANDON VALVE BOX	EA	2	\$ 2,000.00	\$ 4,000.00		\$ -		\$ -	
17	SCHEDULE B - RIVER ROAD	IMPORT ENGINEERED FILL	CY	440	\$ 50.00	\$ 22,000.00		\$ -		\$ -	
18	SCHEDULE B - RIVER ROAD	IMPORT ROAD BASE	TON	10	\$ 100.00	\$ 1,000.00		\$ -		\$ -	
19	SCHEDULE B - RIVER ROAD	ASPHALT REPLACEMENT	SF	435	\$ 25.00	\$ 10,875.00	-201	\$ (5,025.00)		\$ -	
20	SCHEDULE C - MONTEREY AV	8" CULINARY WATER PIPE	LF	20	\$ 150.00	\$ 3,000.00		\$ -		\$ -	
21	SCHEDULE C - MONTEREY AV	4" CULINARY WATER PIPE	LF	800	\$ 110.00	\$ 88,000.00		\$ -		\$ -	
22	SCHEDULE C - MONTEREY AV	4" HOT TAP w/tapping valve	EA	4	\$ 2,000.00	\$ 8,000.00		\$ -		\$ -	
23	SCHEDULE C - MONTEREY AV	8" BEND	EA	1	\$ 3,000.00	\$ 3,000.00		\$ -		\$ -	
24	SCHEDULE C - MONTEREY AV	8" SLEEVE	EA	1	\$ 2,000.00	\$ 2,000.00	2	\$ 4,000.00		\$ -	
25	SCHEDULE C - MONTEREY AV	8" GATE VALVE	EA	1	\$ 5,000.00	\$ 5,000.00		\$ -		\$ -	
26	SCHEDULE C - MONTEREY AV	4" Temporary Blow-Off	EA	4	\$ 1,000.00	\$ 4,000.00		\$ -		\$ -	
27	SCHEDULE C - MONTEREY AV	FIRE HYDRANT ASSEMBLY	EA	1	\$ 16,000.00	\$ 16,000.00		\$ -		\$ -	
28	SCHEDULE C - MONTEREY AV	DEMO & REMOVE EX. FIRE HYDRANT	EA	1	\$ 16,000.00	\$ 16,000.00		\$ -		\$ -	
29	SCHEDULE C - MONTEREY AV	FIRE HYDRANT TIE-OVER	EA	1	\$ 5,000.00	\$ 5,000.00		\$ -		\$ -	
30	SCHEDULE C - MONTEREY AV	WATER LAT. REPLACEMENT TAP TO 8"W	EA	27	\$ 3,750.00	\$ 101,250.00		\$ -	2	\$ 7,500.00	
31	SCHEDULE C - MONTEREY AV	WATER LAT. REPLACEMENT TAP TO 4"W	EA	17	\$ 3,500.00	\$ 59,500.00		\$ -		\$ -	
32	SCHEDULE C - MONTEREY AV	PLUG EX. WATER LINE	EA	2	\$ 1,000.00	\$ 2,000.00		\$ -		\$ -	
33	SCHEDULE C - MONTEREY AV	ABANDON EX. VALVE BOX	EA	7	\$ 1,000.00	\$ 7,000.00		\$ -		\$ -	
34	SCHEDULE C - MONTEREY AV	IMPORT ENGINEERED FILL	CY	425	\$ 50.00	\$ 21,250.00		\$ -		\$ -	
35	SCHEDULE C - MONTEREY AV	IMPORT ROAD BASE	TONS	65	\$ 50.00	\$ 3,250.00		\$ -		\$ -	
36	SCHEDULE C - MONTEREY AV	ASPHALT REPLACEMENT	SF	1420	\$ 25.00	\$ 35,500.00		\$ -	1456	\$ 36,400.00	
		CO1 - Monterey	LS	1	\$ 89,700.82	\$ 89,700.82					
		CO2 - River Road	LS	1	\$ 84,333.60	\$ 84,333.60					
		CO3 - Manifold	LS	1	\$ 92,903.46	\$ 92,903.46					
<b>Total:</b>							<b>\$ 1,395,613.88</b>	<b>\$ 24,475.00</b>	<b>\$ 78,900.00</b>	<b>\$ 1,498,988.88</b>	