



22750 Macomb Industrial Dr
Clinton Township, MI 48036
586-954-0008

Estimate



Date	Estimate #
6/2/2025	8407

Bill to Address
Village of New Haven 57775 Main Street New Haven, MI 48048 C/O Ann Pridemore, President

Work Performed Address
Decora Park

Project or PO #

Description	Qty	Cost	Total
Concrete Work: Remove and or replace concrete as follows: SEE ATTACHED OVERHEAD Remove and replace 3-areas of deteriorated concrete with integral curb. A. Breakout and remove the existing concrete. B. Sawcut the perimeter edges in order to establish proper vertical faces as required. C. Shape and grade the existing base material and compact. D. Install rerod dowels into existing concrete to prevent future shifting as required. E. Install expansion material where required as per industry standards. F. Install 10" of 4000 psi ready mix concrete. Finish according to standard industry practices that includes all necessary control joints. G. Cleanup and remove all debris off site from our construction. H. Price includes installation and removal of barricades as required. Notes: 1. Additional base material or remove and replace if needed. 2. Additional 21a 38 pcy. 3. Remove and replace 52 pcy. 4. Permits/Bonds/Drawings are not included and are additional if required. 5. Quote is valid for 30 days.		44,890.00	44,890.00
		Total	\$44,890.00