

[REDACTED]

[REDACTED]

Roof Service Work Proposal For:
Public Library – Slate to Brick Flashing Repair

Scope of Work:

- [REDACTED]
- Set up Safety Zone in front of work area, this may impact the ADA access ramp and close it for short periods.
 - Remove and preserve (some may break on removal and will be replaced as needed) slate shingles
 - Remove existing brick surface mounted lead coated copper counter flashing
 - Furnish and Install Grace Ultra High Temp Ice/Watershield as a waterproof Selfsealing underlayment for the shingles and brick counter flashing.
 - Furnish and install New Lead Coated Copper Step Flashing in too the brick and under slate
 - Replace original Slate and replace any slate damaged during the removal process.
 - Remove all safety zone set up
- [REDACTED]

[REDACTED] _____ Date: _____

[REDACTED]

Untitled Map

Write a description for your map.

1) Area of Brick
to Slate flashing
to be repaired

Open down through the roof

Google Earth
Version 4.2.2

7.1.1.1



Top Roofers

18 No. Main St.
Newmarket, NH 03857 US
603-292-5906
donna@toproofersllc.com
http://www.toproofersllc.com



ADDRESS

Newmarket Town Library
1 Elm St
Newmarket, NH 03857 USA

Estimate 1583

DATE 03/22/2022

ACTIVITY	QTY	RATE	AMOUNT
Commercial slate roof repairs: 1 Elm St, Newmarket, NH			
Mobilization.			
Remove slate tiles going up along brick wall where flashing needs to be replaced.			
Grind out mortar around existing lead flashing.			
Install ice and water shield from roof decking up to brick wall.			
Install new lead flashing with proper overlap to allow proper water drainage from underneath slate tiles.			
Install new slate tiles over flashing.			
Install new slate tiles if any were broken during repairs			
Labor, materials, clean-up.			
Sales			7,450.00
Total cost of repairs:			

TOTAL \$7,450.00

Accepted By

Accepted Date



TECTA AMERICA®

Date: 2/17/2022

From: Ethan Owens – Service Manager Tecta America – Portland, ME

Attn: David Riley – Director of Facilities

**Roof Service Work Proposal For:
Public Library – Slate to Brick Flashing Repair**

Scope of Work:

Tecta America New England Service Department will: *Please see attached site plan*

- Set up Safety Zone in front of work area, this may impact the ADA access ramp and close it for short periods.
- Remove and preserve (some may break on removal and will be replaced as needed) slate shingles
- Remove existing brick surface mounted lead coated copper counter flashing
- Furnish and Install Grace Ultra High Temp Ice/Watershield as a waterproof Selfsealing underlayment for the shingles and brick counter flashing.
- Furnish and install New Lead Coated Copper Step Flashing in too the brick and under slate
- Replace original Slate and replace any slate damaged during the removal process.
- Remove all safety zone set up

TOTAL LABOR & MATERIALS: \$9,575.00

Customer Approval: _____

Date: _____