


SURVEY CONTROL DATA

- 1) THE PROJECT HORIZONTAL DATUM IS BASED ON THE NAD88, OKLAHOMA STATE PLANE COORDINATE SYSTEM, SOUTH ZONE, (US SURVEY FEET DEFINITION), WITH NO COMBINED ADJUSTMENT FACTOR (CAF). ALL COORDINATE AND DIMENSIONS SHOWN ON THESE PLANS ARE ON STATE PLANE.
- 2) THE VERTICAL DATUM USED IS NAVD88.



DESIGN DATA

ADT 2025 - 220
ADT 2045 - 327
V 40 MPH
FLEX ESALS. 0.24 M

SCALES

PLAN 1:100
PROFILE HOR. 1:100
VER. 1:10
LAYOUT MAP 1"=2 MILES

CONVENTIONAL SYMBOLS

- PROPOSED ROADS
SECTION LINES
QUARTER SECTION LINES
FENCES
EXISTING GRADE
EXISTING ROADS
BASE LINE
PROPOSED GRADE
OHT OVERHEAD TELEPHONE LINES (EXISTING)
TUG COMMUNICATION LINES (EXISTING)
OHE OVERHEAD POWER LINES (EXISTING)
PUG POWER UNDER GROUND LINES (EXISTING)
G GAS LINE (EXISTING)
SS SANITARY SEWER LINES (EXISTING)
W WATER LINES (EXISTING)
TUG COMMUNICATION LINES (PROPOSED)
OHE POWER LINES (PROPOSED)
PUG POWER LINES (PROPOSED)
G GAS LINE (PROPOSED)
SS SANITARY SEWER LINES (PROPOSED)
W WATER LINES (PROPOSED)
BUILDINGS
DRAINAGE STRUCTURES (EXISTING)
DRAINAGE STRUCTURES (PROPOSED)
RIGHT-OF-WAY LINES (EXISTING)
RIGHT-OF-WAY LINES (PROPOSED)
RIGHT-OF-WAY FENCE
FLOWLINE (EXISTING)
FLOWLINE (PROPOSED)
TOE OF SLOPE (EXISTING)
TOP OF CUT (EXISTING)
TOE OF SLOPE/TOP OF CUT (PROPOSED)
LANDSCAPE
RAILROAD

2019 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION—ENGLISH GOVERN,
APPROVED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY
ADMINISTRATION. DECEMBER 18TH, 2019.

CITY OF NORMAN

PLAN OF PROPOSED

BRIDGE AND APPROACHES


PROJECT NO. K-2324-151

EXISTING NBI NO. 26914 NEW NBI NO. 33435
E. POST OAK ROAD OVER TRIB. TO JIM BLUE CREEK

BRIDGE 'A'

LOCATION NO. 14E1280N3200002
NBI NO. 33435
BEGIN BRIDGE STA. 112+80.00
BRIDGE LENGTH = 40.00
END BRIDGE STA. 113+20.00

STA. 111+10.00
BEGIN PROJ. NO. K-2324-151



STA. 114+87.00
END PROJ. NO. K-2324-151

PREPARED FOR:
THE CITY OF NORMAN



ROADWAY LENGTH 337.00 FT 0.063 MI
BRIDGE LENGTH 40.00 FT 0.007 MI
TOTAL PROJECT LENGTH 377.00 FT 0.071 MI
EXCEPTIONS NONE
EQUATIONS NONE

DESCRIPTION REVISIONS DATE

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
0001	TITLE SHEET
0002	TYPICAL SECTION
AB01	SUMMARY OF PAY QUANTITIES AND NOTES (BRIDGE)
AE01	ENVIRONMENTAL NOTES
AR01	SUMMARY OF PAY QUANTITIES AND NOTES (ROADWAY)
AR02	SUMMARY SHEETS (ROADWAY)
AT01	SUMMARY OF PAY QUANTITIES AND NOTES (TRAFFIC)
B001	GENERAL PLAN AND ELEVATION
B002	BRIDGE PAY QUANTITIES SUMMARY
B003-B004	FOUNDATION REPORTS
B005-B006	BARREL DETAILS
B007-B008	END SECTION DETAILS
B009	APPROACH SLAB DETAILS
B010	EXCAVATION DETAILS
R001	STORM WATER MANAGEMENT PLAN
R002	GEOMETRIC DATA
R003	EROSION CONTROL PLAN
R004	PLAN AND PROFILE SHEET
S001-S006	SURVEY DATA SHEETS
T001	DETOUR PLAN
T002	COUNTY ROAD CLOSURE DETAIL
U001-U002	FLEXAMAT STANDARD DETAIL
X001-X004	CROSS SECTION SHEETS

THE FOLLOWING ODOT STANDARDS ARE REQUIRED FOR THIS PROJECT:

2019 ROADWAY	2009 BRIDGE	2009 TRAFFIC
BMPR-0	TR4-2-00E	TCS1-1-01
TESCA-0	LECS-5-2	TCS9-1-01
RSF-0	SBI-5-2	TCS10-1-00
TSD-0		TCS14-1-00
SSS-2-1		THR1-1-02
PSE-2-1		SKT-1-00
SBI-5-2		

PREPARED BY:
MKEC ENGINEERING, INC.
CA#2958 06/30/25
OKLAHOMA CITY, OKLAHOMA

MKEC
Oklahoma City, OK • 405.342.2800

Jonathan T. Hisey
JONATHAN T. HISEY, P.E. S.E.
OKLA. REG. NO. 23127
(SHEETS AB01, B001-B010)

PROFESSIONAL STRUCTURAL ENGINEER
JONATHAN T. HISEY
23127
OKLAHOMA

DATE
4/11/2025

PREPARED BY:
MKEC ENGINEERING, INC.
CA#2958 06/30/25
OKLAHOMA CITY, OKLAHOMA

MKEC
Oklahoma City, OK • 405.342.2800


Chase R. Cole
CHASE R. COLE, P.E.
OKLA. REG. NO. 32407
(SHEETS 002, AR01-AT01, R001-R004, T001-X004)

PROFESSIONAL STRUCTURAL ENGINEER
CHASE R. COLE
32407
OKLAHOMA

DATE
4-11-25




PROJ. NO. K-2324-151

SHEET NO. 0001



PAVEMENT REQUIREMENTS -TYPICAL SECTION			
PAVEMENT STRUCTURE	DRIVING LANES	PAVED SHOULDER	SOD SHOULDER
SURFACE	2" SUPERPAVE TYPE S5 (PG 64-22 OK)	2" SUPERPAVE TYPE S5 (PG 64-22 OK)	SOD
BASE	3" SUPERPAVE TYPE S3 (PG 64-22 OK)	3" SUPERPAVE TYPE S3 (PG 64-22 OK)	
	3" SUPERPAVE TYPE S3 (PG 64-22 OK)	3" SUPERPAVE TYPE S3 (PG 64-22 OK)	
	8" STABILIZED SUBGRADE	8" STABILIZED SUBGRADE	8" STABILIZED SUBGRADE

- NOTES:**
- (1) SHOULDERS TO BE SHAPED OR FILLED AND COMPACTED AS PART OF FINISHING OPERATIONS. COST TO BE INCLUDED IN PRICE BID FOR UNCLASSIFIED BORROW.
- (2) PRIME COAT IS TO BE APPLIED IMMEDIATELY AFTER SUBGRADE MODIFICATION.
- (3) TOPSOIL NOTE:
THE CONTRACTOR SHOULD STRIP ALL AVAILABLE TOPSOIL, STOCK PILE IT, AND PLACE IT BACK ON THE SECTION IN ACCORDANCE WITH SECTION 205 OF THE STANDARD SPECIFICATION. RESERVED TOPSOIL SHALL BE SPREAD FIRST ON THE COMPLETED SLOPES OF THE CUT SECTIONS AND THE REMAINDER ON COMPLETED FILL SLOPES OR OTHER PRIORITY AREAS LOCATED BY THE ENGINEER. ALL ADDITIONAL COSTS ASSOCIATED WITH OPERATION SHALL BE INCLUDED IN THE PAY ITEM FOR SALVAGE TOPSOIL, LUMP SUM.
- THE GRADING LINE AS SHOWN ON THE TYPICAL AND CROSS SECTIONS IS TO THE TOP OF THE TOPSOIL. EARTHWORK QUANTITIES WERE NOT ADJUSTED FOR SALVAGE AND THE TOPSOIL QUANTITY IS INCLUDED IN THE GRADING SUMMARY.
- (4) VARIES AT SPECIAL DITCH LOCATIONS.
- (5) SEE ROUNDING DETAIL, THIS SHEET
- (6) SAFETY EDGE NOTE: CONSTRUCT ASPHALT SAFETY EDGE AS SHOWN IN SPECIAL PROVISION 411-14



G:\projects\2024\K-2324-151-TYPICAL SECTIONS.dwg
PLOTED: Thursday, April 10, 2025 @ 04:20PM

DESIGN

DWG

DRAWN

KMH

CHECKED

PROJECT NO.

K-2324-151

SHEET NO.

0002

E. POST OAK ROAD

CLEVELAND COUNTY

TYPICAL SECTION

GENERAL NOTES

SPECIFICATIONS –
COMPLY WITH THE REQUIREMENTS OF THE 2019 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EXCEPT AS MODIFIED BY THE PLANS AND SPECIAL PROVISIONS.

CONCRETE –
ALL EXPOSED CONCRETE EDGES SHALL HAVE A 1½” CHAMFER UNLESS OTHERWISE SHOWN OR NOTED. ALL CHAMFER STRIPS SHALL BE SIZED LUMBER.

REINFORCING STEEL –
ALL REINFORCING STEEL 2” MINIMUM CLEAR COVER UNLESS OTHERWISE SHOWN.


PAY ITEM NOTES

- B1 PAYMENT TO THE CONTRACTOR WILL BE BASED ON PLAN QUANTITIES
- B2 THE APPROACH SLABS CONTAIN AN ESTIMATED TOTAL OF 65.70 C.Y. OF CLASS AA CONCRETE AND 12,550.00 LB. OF REINFORCING STEEL. INCLUDE ALL COSTS FOR CONSTRUCTING THE APPROACH SLABS, INCLUDING CONCRETE, REINFORCING STEEL (INCLUDING SLAB TO BRIDGE RAILING BARS), BACKER ROD, RAPID CURE JOINT SEALANT, POLYSTYRENE, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK, IN THE CONTRACT UNIT PRICE OF "APPROACH SLAB".
- B3 ITEM "REMOVAL OF EXISTING BRIDGE STRUCTURE" INCLUDES REMOVAL AND DISPOSAL OF SUPERSTRUCTURE AND SUBSTRUCTURE OF 32’ LONG STEEL BEAM BRIDGE. ALL WORK SHALL BE DONE IN ACCORDANCE WITH SUBSECTION 619.04B(2) OF THE SPECIFICATIONS AND IN A MANNER APPROVED BY THE ENGINEER. ALL REMOVED MATERIALS SHALL BECOME THE PROPERTY OF THE CONTRACTOR. INCLUDE ALL COSTS FOR LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE THE WORK IN THE CONTRACT UNIT PRICE OF "REMOVAL OF EXISTING STRUCTURE".

MKEC // TRANSPORTATION

DESCRIPTION	REVISIONS	DATE

0200 BRIDGE				
NBI NO. 33435				
PAY QUANTITIES				
3 – 12’x7’x40’–2” AT GRADE RCB 0° SKEW W/ TR4 CONCRETE TRAFFIC RAILS, Ȣ STA. 113+00.00				
ITEM NO.		ITEM	UNIT	TOTAL
202 (A)	2210	UNCLASSIFIED EXCAVATION B1	C.Y.	1,010.00
501 (A)	1210	STRUCTURAL EXCAVATION UNCLASSIFIED B1	C.Y.	305.00
504 (A)	5200	APPROACH SLAB B1,B2	S.Y.	178.60
504 (B)	5300	SAW–CUT GROOVING B1	S.Y.	286.80
504 (D)	5420	CONCRETE RAIL (TR4) B1	L.F.	160.00
509 (A)	0210	CLASS AA CONCRETE B1	C.Y.	282.40
511 (A)	2210	REINFORCING STEEL B1	LB.	50,380.00
619 (D)	6700	REMOVAL OF EXISTING BRIDGE STRUCTURE B3	LSUM	1.00



DESIGN	J.T.H.
DRAWN	P.W.D.
CHECKED	J.T.H.

E. POST OAK RD. OVER TRIB. CITY OF NORMAN
TO JIM BLUE CRK.
**SUMMARY OF PAY QUANTITIES AND
NOTES (BRIDGE)**
PROJECT NO. K–2324–151 SHEET NO. AB01

SPECIFICATIONS:

COMPLY WITH THE REQUIREMENTS OF THE 2019 OKLAHOMA STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EXCEPT AS MODIFIED BY THE PLANS AND SPECIAL PROVISIONS.

GENERAL CONSTRUCTION NOTES:

IN ACCORDANCE WITH THE OKLAHOMA UNDERGROUND FACILITIES DAMAGE PREVENTION ACT THE CONTRACTOR SHALL NOTIFY THE OKLAHOMA ONE-CALL SYSTEM, INC. 48 HOURS PRIOR TO BEGINNING EXCAVATION. OKLAHOMA ONE-CALL SYSTEM, INC. CALL OKIE 1-800-522-6543 OR 811.

FOR PROJECTS THAT INCLUDE WIDENING AND/OR RESURFACING, THE CONTRACTOR SHALL SCHEDULE OPERATIONS TO MINIMIZE POTENTIAL DROPOFF HAZARDS AND SHALL SUBMIT A SEQUENCE OF CONSTRUCTION OPERATIONS TO THE RESIDENT ENGINEER FOR APPROVAL BEFORE OPERATIONS BEGIN. ANY PORTION OF THE CONSTRUCTION OPERATIONS, SUCH AS SUPERPAVE LAYING OPERATIONS, EXCAVATION FOR PAVEMENT WIDENING, OR EXTENSION OF ROADWAY STRUCTURES, SHALL BE LIMITED TO ONE SIDE AT A TIME, AND THE PROCEDURES OUTLINED IN THE PAVEMENT DROP-OFF TREATMENT STANDARD PDT-1 (LATEST REVISION) SHALL BE IMPLEMENTED. ONLY THAT AMOUNT OF OPEN TRENCH WILL BE ALLOWED THAT CAN BE SURFACED IN 1 (ONE) DAY'S TIME WITHOUT APPROVAL BY THE ENGINEER. LIGHTS, SIGNS AND BARRICADES SHALL BE MOVED AS WORK PROGRESSES.

ALL TREES, BRUSH, AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER SHALL BE CLEANED OUT TO THE RIGHT-OF-WAY LINE, AT EACH STRUCTURE AND BRIDGE, IN A MANNER APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

ALL FLOWLINES THAT ARE TO BE FILLED SHALL BE THOROUGHLY TAMPED BEFORE CONSTRUCTION OR EXTENSION OF DRAINAGE STRUCTURES. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

IN ORDER TO ALLEVIATE DUST CONDITIONS DURING GRADING OPERATIONS AND BEFORE PAVEMENT WORK IS COMPLETED, THE CONTRACTOR SHALL SPRINKLE GRADING AT INTERVALS APPROVED BY THE ENGINEER. ALL COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

THE CONTRACTOR SHALL NOT WASTE ANY EXCESS EXCAVATION UNTIL ALL PLANNED EMBANKMENTS AND BACKFILLS ARE COMPLETED. EXCESS UNCLASSIFIED EXCAVATION MATERIAL DETERMINED BY THE ENGINEER TO BE SUITABLE FOR BACKFILL SHALL BE USED TO REDUCE ANY UNCLASSIFIED BORROW NEEDED. COST OF SECOND HANDLING SHALL BE INCLUDED IN OTHER ITEMS OF WORK. ANY REMAINING EXCESS EXCAVATION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND BE DISPOSED OF IN A MANNER APPROVED BY THE ENGINEER.

PRIME COAT SHALL BE APPLIED TO THE SUBGRADE IMMEDIATELY AFTER FINAL COMPACTION AND SHAPING TO RETAIN MOISTURE FOR PROPER CHEMICAL REACTION OF THE SOIL ADDITIVE.

THE CONTRACTOR SHALL KEEP THE OPEN TRENCH DRAINED. COST TO BE INCLUDED IN OTHER ITEMS OF WORK.

VEGETATIVE MULCHING: THE VEGETATIVE MULCH SHALL BE ANCHORED IN ACCORDANCE WITH THE "MULCHING-TILLER METHOD", AS SPECIFIED IN 233.04B(2) OF THE STANDARD SPECIFICATIONS.

AREAS ON WHICH SALVAGED TOPSOIL IS TO BE REPLACED SHALL HAVE 18-46-0 FERTILIZER APPLIED, AT THE RATE OF 150 POUNDS PER ACRE, JUST PRIOR TO THE REPLACEMENT OF SALVAGED TOPSOIL.

AT THE BEGINNING OF TURFING OPERATIONS, ANY AREAS INCLUDED IN PLANNED QUANTITIES THAT HAVE GROWN A SATISFACTORY VOLUNTEER TURF OF PERENNIAL GRASS, AS DETERMINED BY THE ENGINEER, SHALL BE FERTILIZED AND WATERED AS CALLED FOR ON THE PLANS, BUT SHALL NOT BE SEEDED, SODDED, OR SPRIGGED.

EXCESS ASPHALT AT JOINTS AND CRACKS IN EXISTING PAVEMENT SHALL BE REMOVED FLUSH TO TOP OF PAVING IN A MANNER APPROVED BY THE ENGINEER.

THE BRIDGE SITE WILL BE CLOSED TO ALL PUBLIC TRAFFIC DURING CONSTRUCTION. CONTRACTOR SHALL MAINTAIN ACCESS TO LOCAL TRAFFIC DURING CONSTRUCTION.

ANY DAMAGE CAUSED BY THE CONTRACTOR TO ANY STRUCTURES, ROADWAY SURFACES, STRIPING, RAISED PAVEMENT MARKERS, GUARDRAIL, SLOPES, AND SIGNS SHALL BE REPLACED AT THE CONTRACTORS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER.

THE CITY OF NORMAN WILL BE RESPONSIBLE FOR:

- RELOCATION OF UTILITIES

CONTRACTOR SHALL GIVE NOTICE TO CITY OF NORMAN IN WRITING 14 DAYS BEFORE WORK BEGINS ON THE PROJECT.

ROADWAY PAY QUANTITY NOTES:

(R-1) PAYMENT FOR THIS ITEM WILL BE BASED ON PLAN QUANTITY ONLY. SEE SECTION 109.01B OF THE STANDARD SPECIFICATIONS.

(R-4) AN ESTIMATED QUANTITY OF 123 C.Y. TOPSOIL TO BE RESERVED FOR REPLACEMENT OF APPROXIMATELY 5" ON COMPLETED FORESLOPES, DITCHES, AND BACKSLOPES. THIS QUANTITY IS INCLUDED IN THE EARTHWORK BALANCE. ANY ADDITIONAL EXCAVATION REQUIRED IN CUT SECTIONS TO ALLOW FOR PLACEMENT OF TOPSOIL TO FINAL GRADE, SHALL BE INCLUDED IN THE PRICE BID.

(R-6) FOR SOLID SLAB SODDING PRICE BID TO INCLUDE COST OF 10-20-10 FERTILIZER, ESTIMATED AT 200 POUNDS PER 1000 S.Y.

(R-7) FOR SOLID SLAB SODDING PRICE BID TO INCLUDE COST OF WATERING, ESTIMATED AT 40 GALLONS PER S.Y.

(R-8) PRICE BID TO INCLUDE COST OF ALL NECESSARY MAINTENANCE, MAINTAINING DEVICE IN PROPER UPRIGHT POSITION, REMOVAL OF DEVICE, AND REMOVAL OF SEDIMENT WHEN IT REACHES HALF THE HEIGHT OF THE DEVICE.

(R-11) THE QUANTITIES ESTIMATED FOR TEMPORARY EROSION AND SEDIMENT CONTROL IS 0.18 ACRES.

(R-15) QUANTITY BASED ON TWO APPLICATIONS.

(R-19) PRICE BID TO INCLUDE THE CHEMICAL ADDITIVE(S) TO ACHIEVE THE RATE SPECIFIED FOR THE APPROPRIATE SOIL CLASSIFICATION AS SPECIFIED IN THE MOST CURRENT ODOT MATERIALS DIVISION OHD L-50. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CLASSIFY THE SOIL AND DETERMINE THE APPROPRIATE ADDITIVE(S).

(R-23) PRIME COAT SHALL BE APPLIED AT AN ESTIMATED RATE OF 0.35 GAL. PER SQ. YD. WHEN APPLIED TO SUBGRADE, AND 0.25 GAL. PER SQ. YD. WHEN APPLIED TO AGGREGATE BASE. THE ACTUAL CUTBACK PRIME COAT REQUIRED FOR PLACEMENT OPERATIONS WILL BE DETERMINED BY THE CONTRACTOR, AND SHALL CONSIDER THE RESIDUE FROM DISTILLATION PERCENTAGE SHOWN IN SECTION 708.03 OF THE STANDARD SPECIFICATIONS.

(R-25) ESTIMATED AT 0.075 GALLONS PER SQUARE YARD OF ORIGINAL EMULSION OF TACK COAT (BEFORE DILUTION FOR APPLICATION) IN ACCORDANCE WITH SECTION 407 OF THE STANDARD SPECIFICATIONS.

(R-26) ESTIMATED AT 112 LBS. PER SQ. YD. PER 1" THICK.

(R-33) QUANTITY INCLUDES AN ESTIMATED 5 C.Y. TO BE USED AS DIRECTED BY THE ENGINEER.

(R-39) INCLUDES REMOVAL OF ALL EXISTING ROADWAY DRAINAGE STRUCTURES, HEADWALLS (UNLESS OTHERWISE SPECIFIED), INLETS, FENCES, AND OTHER STRUCTURES WITHIN THE RIGHT OF WAY.

(R-40) TO BECOME THE PROPERTY OF AND BE DISPOSED OF BY THE CONTRACTOR IN A MANNER APPROVED BY THE ENGINEER.

(R-41) MATERIALS REMOVED SHALL NOT BE MEASURED FOR PAYMENT UNDER SECTION 202.06 UNCLASSIFIED EXCAVATION.

- (1) SEE SUMMARY OF EARTHWORK (SHEET NO. AR02)
- (2) ESTIMATED QUANTITY ONLY TO BE USED FOR EROSION AND SEDIMENT CONTROL IN A MANNER APPROVED BY THE ENGINEER. (SEE STDS. RSF-0 AND TSD-0)
- (3) IN ADDITION TO THE RESPONSIBILITIES SHOWN IN THE SPECIFICATIONS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND/OR RE-ESTABLISHING THE SURVEY CONTROL POINTS SHOWN ON THE PLANS, STAKING THE CENTERLINE OF CONSTRUCTION AND RE-ESTABLISHING RIGHT-OF-WAY STAKES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND VERIFYING BENCH MARKS SHOWN ON THE PLANS AND FOR ESTABLISHING NEW BENCH MARKS AS NEEDED TO CONSTRUCT THE PROJECT. THE CONTRACTOR SHALL PLACE STAKES AND HUBS EVERY 100' AND AT DRAINAGE STRUCTURES.
- (4) INCLUDES 31 C.Y. OF EXCAVATION FOR DRAINAGE GRADING AT STA. 114+65.00 LT. ESTIMATED QUANTITY BASED ON 4' DITCH BOTTOM WITH 3.5:1 BACKSLOPE.
- (5) PRICE BID TO INCLUDE COST OF PORTLAND CEMENT, FLEXAMAT UNDERLAYMENT MATERIALS, AND #3 REBAR U-ANCHORS (18") NECESSARY TO INSTALL ARTICULATING CONCRETE BLOCK (FLEXAMAT) AS SHOWN ON SHEET U001-U002 ANY EXCAVATION FOR ANCHOR TRENCHES SHALL ALSO BE INCLUDED IN THE PRICE BID. FLEXAMAT SHALL BE INSTALLED IN ACCORDANCE WITH THE PRODUCT TECHNICAL SPECIFICATIONS AND DETAILS DRAWINGS.

(6) DEBRIS FROM BRIDGE REMOVAL TO BE REMOVED FROM CHANNEL AT THE END OF EACH DAY.

(7) QUANTITY IS FOR BEDDING AND BACKFILL AT BRIDGE 'A'. SEE SHEET NO. B010 FOR MORE DETAIL.

(8) FLARED GUARDRAIL END TREATMENT TO BE INSTALLED AS DIRECTED BY THE FIELD ENGINEER, EACH LEG.

(9) QUANTITY INCLUDES 25 TONS OF SUPERPAVE TYPE S3 (PG 64-22 OK) TO BE USED AT THE TRANSITION FROM THE ASPHALT TO THE APPROACH SLAB EACH SIDE OF BRIDGE 'A'. SEE SHEET NO. 0002, SUBGRADE AT APPROACH SLAB DETAIL FOR MORE INFORMATION.

K-2324-151				
PAY QUANTITIES				
0100 ROADWAY				
ITEM		DESCRIPTION	UNIT	QUANTITY
201(A)	1200	CLEARING AND GRUBBING	L.SUM	1.00
202(A)	2200	UNCLASSIFIED EXCAVATION (1)(4)(R-1)	C.Y.	82.00
202(D)	2500	UNCLASSIFIED BORROW (1)	C.Y.	270.00
205(A)	6200	TYPE A-SALVAGED TOPSOIL (R-4)	L.SUM	1.00
221(B)	2300	TEMPORARY SILT FENCE (2)(R-8)	L.F.	574.00
221(E)	2600	TEMPORARY SILT DIKE (2)(R-8)	L.F.	21.00
230(A)	7200	SOLID SLAB SODDING (R-6)(R-7)	S.Y.	882.00
233(A)	0200	VEGETATIVE MULCHING (R-11)	AC.	0.18
241	3100	MOWING (R-15)	AC.	0.36
303(A)	1200	AGGREGATE BASE TYPE A (7)	C.Y.	300.00
307(K)	4200	STABILIZED SUBGRADE (R-19)	S.Y.	1,255.00
407(B)	7300	TACK COAT (R-25)	GAL.	135.00
408	8100	PRIME COAT (R-23)	GAL.	440.00
411(B)	1330	SUPERPAVE, TYPE S3 (PG 64-22 OK) (R-26)	TON	330.00
411(D)	1530	SUPERPAVE, TYPE S5 (PG 64-22 OK) (R-26)	TON	147.00
509(D)	0500	CLASS C CONCRETE (R-33)	C.Y.	5.00
602(B)	2300	ARTICULATING CONCRETE BLOCK (5)	S.F.	483.00
619(A)	6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS (6)(R-39)(R-40)	L.SUM	1.00
619(B)	6364	REMOVAL OF ASPHALT PAVEMENT (R-40)(R-41)	S.Y.	938.00
619(B)	6396	REMOVAL OF GUARDRAIL (R-40)	L.F.	144.00
619(C)	6600	SAWING PAVEMENT	L.F.	48.00
623(A)	1200	BEAM GUARDRAIL W-BEAM SINGLE	L.F.	50.00
623(G)	1820	GUARDRAIL END TREATMENT (31") (8)	EA.	4.00
623(I)	2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	EA.	4.00

K-2324-151				
PAY QUANTITIES				
0600 STAKING				
ITEM		DESCRIPTION	UNIT	QUANTITY
642(B)	3300	CONSTRUCTION STAKING LEVEL II (3)	L.SUM	1.00

K-2324-151				
PAY QUANTITIES				
0640 CONSTRUCTION				
ITEM		DESCRIPTION	UNIT	QUANTITY
220	1100	SWPPP DOCUMENTATION AND MANAGEMENT	L.SUM	1.00
641	2100	MOBILIZATION	L.SUM	1.00



DESIGN	DJG
DRAWN	KMH
CHECKED	---



E. POST OAK ROAD CLEVELAND COUNTY

SUMMARY OF PAY
QUANTITIES AND NOTES
(ROADWAY)

PROJECT NO. K-2324-151 SHEET NO. AR01

C:\projects\2024\2403000281_City of Norma_Post Oak Bridge\00_CAD\SWTS\Fwy\K-2324-151-SUMMARY SHEETS (ROADWAY).dwg
PLOTED: Wednesday, April 09, 2025 @ 02:41PM

SCHEDULE OF EARTHWORK				
SHEET NO.	STATION TO STATION	UNCLASSIFIED EXCAVATION	EMBANKMENT +15%	UNCLASSIFIED BORROW
		202(A)		202(D)
		C.Y.	C.Y.	C.Y.
R004	111+10.00 TO 114+87.00	51.00	352.00	301.00
R004	DRAINAGE GRADING	31.00	-	(31.00)
TOTAL		82.00	352.00	270.00


SUMMARY OF SURFACING						
SHEET NO.	STATION TO STATION	8" STABILIZED SUBGRADE	TACK COAT	PRIME COAT	SUPERPAVE, TYPE S3 (PG 64-22 OK)	SUPERPAVE, TYPE S5 (PG 64-22 OK)
		307(K)	407(B)	408	411(B)	411(D)
		S.Y.	GAL.	GAL.	TON	TON
R004	111+10.00 TO 112+60.00	634.00	68.00	222.00	154.00	50.00
R004	113+40.00 TO 114+87.00	621.00	67.00	218.00	151.00	49.00
TOTAL		1,255.00	135.00	440.00	305.00	99.00

SUMMARY OF REMOVALS				
SHEET NO.	STATION TO STATION	REMOVAL OF GUARDRAIL	REMOVAL OF ASPH. PVMT.	SAWING PAVEMENT
		619(B)	619(B)	619(C)
		L.F.	S.Y.	L.F.
R004	111+10.00 TO 114+87.00	144.00	938.00	48.00
TOTAL		144.00	938.00	48.00

SUMMARY OF GUARDRAIL & WIDENING							
SHEET NO.	STATION TO STATION	LANE		SUPERPAVE TYPE S5 (PG 64-22 OK)	BEAM GUARDRAIL (W-BEAM) SINGLE	GUARDRAIL CONNECTIONS	
						THRIE BEAM (31")	GUARDRAIL END TREATMENT (31")
		LT.	RT.	411(D) TON	623(A) L.F.	623(I) EA.	623(G) EA.
R004	111+50.75 TO 112+80.00	X	X	24.00	25.00	2.00	2.00
R004	113+20.00 TO 114+49.25	X	X	24.00	25.00	2.00	2.00
TOTAL				48.00	50.00	4.00	4.00

SUMMARY OF DITCH TREATMENT					
SHEET NO.	STATION TO STATION	LOCATION	LENGTH	BOTTOM WIDTH	ARTICULATING CONC. BLOCK
					602(B)
			FT.	FT.	S.F.
R004	114+07.25 TO 114+87.00	LT.	79.75	2.00	163.00
R004	114+07.25 TO 114+87.00	RT.	79.75	4.00	320.00
TOTAL					483.00

SUMMARY OF EROSION CONTROL					
SHEET NO.	STATION TO STATION	TEMPORARY SILT FENCE	TEMPORARY SILT DIKE	SOLID SLAB SODDING	VEGETATIVE MULCHING
		221(B)	221(E)	230(A)	233(A)
		L.F.	L.F.	S.Y.	AC.
R003	111+10.00 TO 114+87.00	574.00	21.00	882.00	0.18
TOTAL		574.00	21.00	882.00	0.18



DESIGN	DJG
DRAWN	KMH
CHECKED	---

E. POST OAK ROAD

CLEVELAND COUNTY

SUMMARY SHEETS (ROADWAY)

PROJECT NO. K-2324-151 SHEET NO. AR02

GENERAL TRAFFIC NOTES:

CONTRACTOR SHALL MAINTAIN ACCESS TO LOCAL TRAFFIC DURING CONSTRUCTION.

CONTRACTOR SHALL GIVE NOTICE TO CITY OF NORMAN IN WRITING 14 DAYS BEFORE WORK BEGINS ON THE PROJECT.

TRAFFIC OPERATIONS GENERAL CONSTRUCTION NOTES

ANY DAMAGE CAUSED BY THE CONTRACTOR TO ANY STRUCTURES, ROADWAY SURFACES, STRIPING, RAISED PAVEMENT MARKERS, GUARDRAIL, SLOPES, AND SIGNS SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE ENGINEER.

TRAFFIC SIGNING GENERAL CONSTRUCTION NOTES

ALL REGULATORY SIGNS SHALL HAVE HIGH INTENSITY SHEETING. THE HIGH INTENSITY SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956--(LATEST REVISION) FOR TYPE III SHEETING.

ALL WARNING SIGNS SHALL HAVE FLUORESCENT YELLOW SHEETING. THE FLUORESCENT YELLOW SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956--(LATEST REVISION) REQUIREMENTS FOR TYPE VIII SHEETING.

THE STATIONS AND LOCATIONS OF THE SIGN PLACEMENT, AS SHOWN ON THE PLAN SHEETS, ARE APPROXIMATE. EXACT STATIONS AND LOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR SO THAT THE SIGN IS INSTALLED IN ACCORDANCE WITH DEPARTMENT STANDARDS AND THE MUTCD IN ORDER TO PROVIDE OPTIMUM VISIBILITY TO THE ONCOMING/APPROACHING MOTORIST. IF A PROPOSED LOCATION CONFLICTS WITH OTHER SIGNS, UTILITIES OR OTHER ROADWAY FEATURES, THE ENGINEER SHALL BE NOTIFIED.

TRAFFIC CONSTRUCTION PAY QUANTITY NOTES:

(TC--26) ALL CONSTRUCTION TRAFFIC CONTROL WILL BE IMPLEMENTED ACCORDING TO CONSTRUCTION PLANS, AND INSTALLED IN A MANNER APPROVED BY THE ENGINEER, IN ACCORDANCE WITH CHAPTER VI OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, (CURRENT EDITION), AND COMPLIANT WITH APPLICABLE O.D.O.T. STANDARD DRAWINGS. PRICE BID FOR THIS ITEM SHALL BE PAYMENT IN FULL FOR THE INSTALLATION, MAINTENANCE AND SUBSEQUENT REMOVAL OF ALL NECESSARY CONSTRUCTION TRAFFIC CONTROL DEVICES AND PAVEMENT MARKINGS REQUIRED FOR COMPLETION OF THE PROJECT.

ALL SIGNS AND BARRICADES, WHICH ARE SHOWN WITH TYPE 'A' LIGHTS IN THE STANDARD DRAWINGS SHALL HAVE THE CORRESPONDING LIGHT ATTACHED DURING NON--DAYLIGHT HOURS.

(TC--33) ALL CONSTRUCTION WORK ZONE SIGNS SHALL HAVE FLUORESCENT SHEETING. THE FLUORESCENT SHEETING SHALL MEET THE REQUIREMENTS OF ASTM D4956 (LATEST REVISION).

THE MANUFACTURER SHALL FURNISH A TYPE D' CERTIFICATION IN ACCORDANCE WITH O.D.O.T. STANDARD SPECIFICATIONS (CURRENT EDITION) SUBSECTION 106.04. THE CERTIFICATION SHALL INCLUDE TEST RESULTS ON MATERIAL SUBMITTED FOR APPROVAL.

(TC--84) 90 CONSTRUCTION CALENDAR DAYS WERE USED TO COMPUTE THE SIGN DAY PAY THE AMOUNT OF CALENDAR DAYS USED TO COMPUTE THE SIGN DAY PAY ITEMS IS AN ESTIMATED QUANTITY ONLY, BASED ON THE CURRENT O.D.O.T. STANDARDS AND SUGGESTED CONSTRUCTION SEQUENCE FOR THIS PROJECT THESE ESTIMATED SIGN DAY QUANTITIES MAY CHANGE AS THE PROJECTS CONSTRUCTION TRAFFIC CONTROL IS MODIFIED DURING CONSTRUCTION.

REVISIONS		
REV. NO.	DESCRIPTION	DATE

K-2324-151

PAY QUANTITIES

0300 TRAFFIC TEMPORARY

ITEM		DESCRIPTION		UNIT	QUANTITY
880(B)	6300	CONSTRUCTION SIGNS 0 TO 6.25 SF (TC-26)(TC-33)(TC-84)		S.D.	900.00
880(B)	6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF (TC-26)(TC-33)(TC-84)		S.D.	360.00
880(B)	6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF (TC-26)(TC-33)(TC-84)		S.D.	360.00
880(C)	6410	CONSTRUCTION BARRICADES (TYPE III) (TC-26)(TC-84)		S.D.	1,620.00
880(E)	6600	WARNING LIGHTS (TYPE A) (TC-26)(TC-84)		S.D.	360.00

CONSTRUCTION SIGN SUMMARY

SHEET NO.	CONSTRUCTION SIGN									
	CONST. SIGNS 0 - 6.25 S.F.		CONST. SIGNS 6.26 - 15.99 S.F.		CONST. SIGNS 16.00 - 32.99 S.F.		CONSTRUCTION BARRICADES (TYPE III)		WARNING LIGHTS (TYPE A)	
	880(B)		880(B)		880(B)		880(C)		880(E)	
	EA.	S.D.	EA.	S.D.	EA.	S.D.	EA.	S.D.	EA.	S.D.
M4-9	8.00	90.00					8.00	90.00		
M4-10	2.00	90.00					2.00	90.00		
R11-2			2.00	90.00			2.00	90.00		
R11-3A			2.00	90.00			2.00	90.00		
W20-2					2.00	90.00	2.00	90.00	2.00	90.00
W20-3					2.00	90.00	2.00	90.00	2.00	90.00
PHASE TOTAL	10.00	90.00	4.00	90.00	4.00	90.00	18.00	90.00	4.00	90.00
TOTAL		900.00		360.00		360.00		1,620.00		360.00
SIGN DAY= 90 DAYS										



DESIGN	DJG
DRAWN	KMH
CHECKED	---



E. POST OAK ROAD CLEVELAND COUNTY
**SUMMARY OF PAY
QUANTITIES AND NOTES
(TRAFFIC)**
PROJECT NO. K-2324-151 SHEET NO. AT01

MKEC PROJECT NUMBER: 2403010281
PLOTTED: Friday, April 11, 2025 @ 08:50AM

MKEC // TRANSPORTATION

DESCRIPTION	REVISIONS	DATE

DESIGN DATA

CLASS AA CONCRETE
REINFORCING STEEL, AASHTO M 31 (GRADE 60) $f'_c = 4$ K.S.I.
 $F_y = 60$ K.S.I.

LOADING:
HL-93

DESIGN:
AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 9TH EDITION.

LRFR INVENTORY RATING FACTOR: 1.34
LRFR OPERATING RATING FACTOR: 1.74
EV3 LEGAL LOAD RATING FACTOR: 1.81
NRL LEGAL LOAD RATING FACTOR: 3.46

HYDRAULIC DATA

TOTAL DRAINAGE AREA = 0.63 SQ. MI.
CONTROLLED DRAINAGE AREA = 0.00 SQ. MI.
EFFECTIVE DRAINAGE AREA = 0.63 SQ. MI.

Q2 = 261 CFS Q25 = 993 CFS
CHW = 1119.59 CHW = 1121.73
V2 = 2.74 FPS V25 = 6.01 FPS

Q5 = 490 CFS Q50 = 1330 CFS
CHW = 1120.46 CHW = 1122.39
V5 = 3.92 FPS V50 = 7.19 FPS


Q10 = 688 CFS Q100 = 1560 CFS
CHW = 1121.02 CHW = 1122.89
V10 = 4.81 FPS V100 = 7.94 FPS

RDW OT > 412 YR QOT = 2260 CFS
CHW OT = 1124.45 VOT = 10.05 FPS

ODOT STANDARDS

TR4-2-00E
LECS-5-2
SBI-5-2


NOTE:
FOR SHEET INDEX, SUMMARY OF BRIDGE PAY QUANTITIES, SEE SHEET B002.




BM 202 - BM / SET 3/4IN IP
STA. 108+51.02 37.96' RT.
N = 665617.7271 E = 2179047.2370
ELEV. = 1138.79

BM 204 - BM / SET CUT X ON CURB
STA. 116+92.99 13.90' RT.
N = 665652.2509 E = 2179888.5750
ELEV. = 1139.64

PLAN
(1" = 10')



ELEVATION
(ALONG C.B.)
(1" = 10')



PROFILE GRADE LINE DATA

	DESIGN	J.T.H.	E. POST OAK RD. OVER TRIB. TO JIM BLUE CRK. GENERAL PLAN AND ELEVATION 3 - 12'x7'x40'-2" AT GRADE RCB 0' SKEW, W/ TR4 CONCRETE TRAFFIC RAILS, C STA. 113+00.00 PROJECT NO. K-2324-151 SHEET NO. B001
	DRAWN	J.D.H.	
	CHECKED	J.T.H.	

PLOTTED: Friday, April 11, 2025 @ 08:50AM
 MKEC PROJECT NUMBER: 2403010281


SHEET INDEX

SUMMARY OF PAY QUANTITIES AND NOTES (BRIDGE)	AB01
GENERAL PLAN AND ELEVATION	B001
BRIDGE PAY QUANTITIES SUMMARY	B002
FOUNDATION REPORTS (SHEET 1 OF 2)	B003
FOUNDATION REPORTS (SHEET 2 OF 2)	B004
BARREL DETAILS (SHEET 1 OF 2)	B005
BARREL DETAILS (SHEET 2 OF 2)	B006
END SECTION DETAILS (SHEET 1 OF 2)	B007
END SECTION DETAILS (SHEET 2 OF 2)	B008
APPROACH SLAB DETAILS	B009
EXCAVATION DETAILS	B010


SUMMARY OF BRIDGE QUANTITIES					
ITEM	UNIT	APPROACH SLABS	RCB BARREL	RCB END SECTIONS	TOTAL
UNCLASSIFIED EXCAVATION	C.Y.		100.00	910.00	1,010.00
STRUCTURAL EXCAVATION UNCLASSIFIED	C.Y.		190.00	115.00	305.00
APPROACH SLAB	S.Y.	178.60			178.60
SAW-CUT GROOVING	S.Y.	139.40	147.40		286.80
CONCRETE RAIL (TR4)	L.F.	80.00	80.00		160.00
CLASS AA CONCRETE	C.Y.		201.00	81.40	282.40
REINFORCING STEEL	LB.		40,000.00	10,380.00	50,380.00
REMOVAL OF EXISTING BRIDGE STRUCTURE	L.SUM				1.00

MKEC // TRANSPORTATION

DESCRIPTION	REVISIONS	DATE



DESIGN	J.T.H.
DRAWN	P.W.D.
CHECKED	J.T.H.



E. POST OAK RD. OVER TRIB. CITY OF NORMAN
TO JIM BLUE CRK.

BRIDGE PAY QUANTITIES SUMMARY

PROJECT NO. K-2324-151
SHEET NO. B002


C:\USERS\BRYCE\HANLON\ARROWHEAD ENG. CO. DROPBOX\AEC JOBS-2024\11_PROJECTS_2024\1941_MKEC_EPOSTOAKOVTRIBJIMBLUECREEK_CLEVELANDCO_RCBRIDGEREPLACEMENT7_GINT FILE\1941_GINT.GPJ FIRE

C:\USERS\BRYCE\HANNARROWHEAD.ENG.CO.DROPBOX\AEC JOBS-2024\11 PROJECTS_2024\11941 MKEC EPOSTOAKOVTRIBJIMBLUECREEK_CLEVELANDCO RCBBRIDGEREPLACEMENT7_GINT FILE\1941 GINT.GPJ FIRE


C:\USERS\BRYCE\HANLON\ARROWHEAD ENG. CO. DROPBOX\AEC JOBS-2024\11_PROJECTS_2024\1941_MKEC_EPOSTOAKOVTRIBJIMBLUECREEK_CLEVELANDCO_RCBRIDGEREPLACEMENT7_GINT FILE\1941_GINT.GPJ FIRE

C:\USERS\BRYCE\HANNARROWHEAD.ENG.CO.DROPBOX\AEC JOBS-2024\11 PROJECTS_2024\11941 MKEC EPOSTOAKOVTRIBJIMBLUECREEK_CLEVELANDCO RCBBRIDGEREPLACEMENT7_GINT FILE\1941 GINT.GPJ FIRE


DESCRIPTION	REVISIONS	DATE




TYPICAL ELEVATION ALONG CL RCB BARREL



TYPICAL APPROACH SLAB SEAT DETAIL



TYPICAL SECTION THRU BARREL



REINFORCING DETAIL AT PARAPET OPENINGS

Ⓐ FOR ADDITIONAL CL1 OR CL2 #5 BAR DETAILS, SEE "SOUTH CONCRETE TRAFFIC RAIL (TR4) AND ADDITIONAL CHAMFER DETAIL" ON SHEET B006.

NOTES:
FOR CONCRETE TRAFFIC RAIL (TR4) AND ADDITIONAL END OF BARREL DETAILS, SEE SHEET B006.

FOR CURTAIN WALL DETAILS, BAR BENDS AND BAR LIST, SEE SHEETS B006, B007, AND B008.

FOR WING WALL DETAILS AND WING WALL QUANTITIES, SEE SHEET B007 AND B008.

RCB BARREL QUANTITIES

ITEM	UNIT	TOTAL
SAW-CUT GROOVING	S.Y.	147.40
CONCRETE RAIL (TR4)	L.F.	80.00
CONCRETE CLASS AA	C.Y.	201.00
REINFORCING STEEL	LB.	40,000.00



DESIGN	J.T.H.
DRAWN	J.D.H.
CHECKED	J.T.H.




E. POST OAK RD. OVER TRIB. CITY OF NORMAN
TO JIM BLUE CRK.

BARREL DETAILS (SHEET 1 OF 2)

PROJECT NO. K-2324-151 SHEET NO. B005

MKEC PROJECT NUMBER: 2403010281
 PLOTTED: Friday, April 11, 2025 @ 08:50AM



MKEC // TRANSPORTATION		
DESCRIPTION	REVISIONS	DATE

4 - CL1 #5 (NORTH END) OR
4 - CL2 #5 (SOUTH END)


(EQUALLY SPACED
BTWN. SR2 #5 BARS
AT TR4 OPENINGS)
(TYP.)

SOUTH CONCRETE TRAFFIC RAIL (TR4) AND ADDITIONAL CHAMFER DETAIL
(ELEVATION SHOWN IS LOOKING AT THE OUTSIDE FACE OF CONCRETE TRAFFIC RAIL)


NOTES:
FOR RCB BARREL QUANTITIES, SEE SHEET B005.
FOR WING WALL DETAILS, SEE SHEET B007 AND B008.

Ⓐ USE SR2 #5 AT OUTSIDE FACE OF CONCRETE TRAFFIC RAIL ONLY ON TOP OF BARREL IN LIEU OF SR1 #5 BAR.


RCB BARREL BAR LIST					
MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
A1	#6	162	STR.	39'-8"	
A2	#8	162	STR.	39'-8"	
AS	#5	82	BNT.	5'-0"	
B1	#5	162	BNT.	5'-7"	
B2	#5	162	BNT.	10'-5"	
C1	#4	242	STR.	3'-1"	
C2	#4	242	STR.	7'-11"	
CL1	#5	12	BNT.	3'-7"	
CL2	#5	12	BNT.	3'-6"	
E1	#4	88	STR.	39'-10"	
E2	#4	40	STR.	38'-8"	
E3	#4	28	STR.	38'-8"	
E4	#4	88	STR.	46'-0"	
SR1	#5	128	BNT.	4'-1"	
Ⓐ SR2	#5	52	BNT.	5'-7"	
SV1	#5	82	BNT.	6'-3"	



TYPICAL END OF BARREL DETAIL AT EXTERIOR WALL




TYPICAL END OF BARREL DETAIL AT INTERIOR WALL



	DESIGN	J.T.H.	E. POST OAK RD. OVER TRIB. CITY OF NORMAN TO JIM BLUE CRK. BARREL DETAILS (SHEET 2 OF 2) PROJECT NO. <u>K-2324-151</u> SHEET NO. <u>B006</u>
	DRAWN	J.D.H.	
	CHECKED	J.T.H.	

DESCRIPTION	REVISIONS	DATE



HALF REINFORCING PLAN

HALF PLAN

WINGWALL AND APRON PLAN
(NORTH END SECTION SHOWN, SOUTH END SECTION SIMILAR)

NORTH RCB END SECTION QUANTITIES

ITEM	UNIT	TOTAL
CONCRETE CLASS AA	C.Y.	40.80
REINFORCING STEEL	LB.	5,190.00


SOUTH RCB END SECTION QUANTITIES

ITEM	UNIT	TOTAL
CONCRETE CLASS AA	C.Y.	40.60
REINFORCING STEEL	LB.	5,190.00

F.F. = FAR FACE / ROADWAY FACE
N.F. = NEAR FACE / OUTSIDE FACE

Ⓐ TIE WV1 #6 (F.F.) TO WD1 #7 BARS AND WT2 #4 (N.F.) TO WH1 #4 BARS.

Ⓑ TIE BOTTOM LEGS OF WL1 #6 (F.F.) AND WT1 #4 (N.F.) TO AL2 #5 BARS.



WINGWALL AND APRON ELEVATION

(NORTH END SECTION SHOWN, SOUTH END SECTION SIMILAR)

NOTES:

FOR TYPICAL WINGWALL AND APRON SECTION, SEE SHEET B008.

FOR BARREL DETAILS, SEE SHEETS B005 - B006.




DESIGN	P.W.D.	E. POST OAK RD. OVER TRIB.	CITY OF NORMAN
DRAWN	J.D.H.	TO JIM BLUE CRK.	
CHECKED	J.T.H.		

END SECTION DETAILS (SHEET 1 OF 2)


PROJECT NO. K-2324-151 SHEET NO. B007

PLOTTED: Friday, April 11, 2025 @ 08:50AM
 MKEC PROJECT NUMBER: 2403010281

DESCRIPTION	REVISIONS	DATE




TYPICAL WINGWALL SECTION



TYPICAL PLAN OF WING AT BARREL

WINGWALL BAR LIST					
(ONE SHOWN, TWO REQUIRED)					
MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
AL1	#7	40	STR.	6'-8"	
AL2	#5	40	STR.	6'-8"	
AT1	#4	24	STR.	39'-10"	
AT2	#4	16	STR.	18'-8"	
WD1	#7	28	BNT.	8'-0"	
WH1	#4	36	STR.	18'-8"	
WL1	#6	40	BNT.	4'-7"	
WT1	#4	40	BNT.	3'-5"	
WT2	#4	40	STR.	8'-0"	
WV1	#6	40	STR.	8'-0"	

CURTAIN WALL BAR LIST					
(ONE SHOWN, TWO REQUIRED)					
MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
AT1	#4	16	STR.	39'-10"	
CS1	#5	84	BNT.	5'-10"	
CS2	#5	84	BNT.	7'-1"	



MKEC PROJECT NUMBER: 2403010281
 PLOTTED: Friday, April 11, 2025 @ 08:50AM


DESCRIPTION	REVISIONS	DATE

NOTES:

PLACE REINFORCING IN THE TOP OF THE APPROACH SLAB 2" FROM EITHER OF THE SAWED AND SEALED LONGITUDINAL JOINTS.




FOR ADDITIONAL DETAILS OF LONGITUDINAL JOINT, SEE O.D.O.T. STD. LECS-5.

Ⓐ AS BARS SHALL BE TIED TO THE TOP LAYER OF REINFORCING STEEL IN THE RCB AND TO THE BOTTOM LAYER OF REINFORCING STEEL IN THE APPROACH SLAB. AS BARS SHALL BE INSTALLED BEFORE PLACING THE RCB CONCRETE.



APPROACH SLAB QUANTITIES				
ITEM	UNIT	APPROACH SLAB NO. 1	APPROACH SLAB NO. 2	TOTAL
APPROACH SLAB	S.Y.	89.30	89.30	178.60
SAW-CUT GROOVING	S.Y.	69.70	69.70	139.40
CONCRETE RAIL (TR4)	LF.	40.00	40.00	80.00


APPROACH SLAB BAR LIST					
(ONE SHOWN, TWO REQUIRED)					
MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
AL1	#4	42	STR.	19'-8"	
AL2	#9	61	STR.	19'-8"	
AT1	#4	42	STR.	19'-9"	
AT2	#4	21	STR.	39'-10"	
SR1	#5	124	BNT.	4'-1"	




SECTION A

SECTION B

WING JOINT DETAIL




DESIGN	J.T.H.	E. POST OAK RD. OVER TRIB. CITY OF NORMAN TO JIM BLUE CRK.
DRAWN	P.W.D.	
CHECKED	J.T.H.	




PROJECT NO. K-2324-151 SHEET NO. B009

APPROACH SLAB DETAILS


PLOTTED: Friday, April 11, 2025 @ 08:50AM
 MKEC PROJECT NUMBER: 2403010281



LIMITS OF UNCLASSIFIED AND STRUCTURAL EXCAVATION
 TYPICAL SECTION




LIMITS OF BACKFILL
 TYPICAL SECTION




PLAN OF LIMITS OF UNCLASSIFIED AND STRUCTURAL EXCAVATION

- UNCLASSIFIED EXCAVATION
- STRUCTURAL EXCAVATION UNCLASSIFIED
- AGGREGATE BASE TYPE A
- NATIVE BACKFILL
- STABILIZED SUBGRADE


LEGEND



LIMITS OF UNCLASSIFIED AND STRUCTURAL EXCAVATION
 ELEVATION



LIMITS OF BACKFILL
 ELEVATION



TYPICAL WING WALL EXCAVATION AND BACKFILL DETAIL

SUMMARY OF EXCAVATION QUANTITIES				
ITEM	UNIT	BARREL	END SECTION	TOTAL
UNCLASSIFIED EXCAVATION	C.Y.	100.00	910.00	1,010.00
AGGREGATE BASE TYPE A	C.Y.	170.00	130.00	300.00
STRUCTURAL EXCAVATION UNCLASSIFIED	C.Y.	190.00	115.00	305.00

NOTE:
 AGGREGATE BASE TYPE A BACKFILL TO BE PAID AS ROADWAY PAY ITEM.

DESIGN

J.T.H.

DRAWN

P.W.D.

CHECKED

J.T.H.

E. POST OAK RD. OVER TRIB. TO JIM BLUE CRK.

CITY OF NORMAN

EXCAVATION DETAILS

PROJECT NO. K-2324-151 SHEET NO. B010

STORM WATER MANAGEMENT PLAN

DESCRIPTION

REVISIONS

DATE

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: 200 FEET EAST AND 200 FEET WEST OF BRIDGE ON
E. POST OAK RD.

PROJECT DESCRIPTION: BRIDGE AND APPROACHES ON E POST OAK RD.
OVER TRIBUTARY TO JIM BLUE CREEK

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES:

PRIOR TO INITIATING SOIL DISTURBING ACTIVITIES, THE CONTRACTOR WILL INSTALL ALL PERIMETER
TEMPORARY SEDIMENT CONTROLS SPECIFIED. STRIP, STOCKPILE AND STABILIZE TOPSOIL. CLEAR
AND GRUB ONLY IN NECESSARY AREAS, PRESERVING AS MUCH NATIVE VEGETATION AS POSSIBLE.
INSTALL, MAINTAIN AND/OR MOVE TEMPORARY SEDIMENT ITEMS WITH CONSTRUCTION OPERATIONS
AS PRACTICAL. IF DIRECTED BY THE ENGINEER, PLANT TEMPORARY SEEDING. REPLACE SALVAGED
TOPSOIL. REMOVE TEMPORARY SEDIMENT CONTROL DEVICES WHEN AN ACCEPTABLE VEGETATIVE
COVER (AT LEAST 70%) HAS BEEN ATTAINED. AS SITE CONDITIONS WARRANT, THE CONTRACTOR
MAY CHOOSE TO MODIFY THE TYPE OR ARRANGEMENT OF SPECIFIED PRACTICES TO IMPROVE
THEIR EFFECTIVENESS AS APPROVED BY THE ENGINEER. THE CONTRACTOR WILL MAINTAIN A LOG
OF THE DATES OF MAJOR SOIL DISTURBANCE ACTIVITIES, AND ALSO THE DATES OF INSTALLATION
OF EROSION.

SOIL TYPE: FINE SANDY LOAM

TOTAL AREA OF THE
CONSTRUCTION SITE: 0.61 AC.

ESTIMATED AREA TO BE DISTURBED: 0.58 AC.

OFFSITE AREA TO BE DISTURBED:
(FOR CONTRACTOR USE) 0.00 AC.

TOTAL IMPERVIOUS AREA
PRE-CONSTRUCTION: 0.21 AC.

TOTAL IMPERVIOUS AREA
POST-CONSTRUCTION: 0.34 AC.

POST-CONSTRUCTION RUNOFF
COEFFICIENT OF THE SITE: 0.35

LATITUDE & LONGITUDE
OF CENTER OF PROJECT: N= 35° 9'37.37"N E= 97°17'38.87"W

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: JIM BLUE CREEK

SENSITIVE WATERS OR WATERSHEDS: YES ☒ NO ☐

303 (d) IMPAIRED WATERS: YES ☐ NO ☒

IF YES, LIST IMPAIRMENT:

LOCATED IN A TMDL: YES ☒ NO ☐

LAKE THUNDERBIRD TMDL: YES ☒ NO ☐

MS4 ENTITY YES ☐ NO ☒

IF YES, LOCATION:

NOTE:
THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP
THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS
FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION
CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- TEMPORARY SEEDING
- ☒ PERMANENT SODDING, SPRIGGING OR SEEDING
- ☒ VEGETATIVE MULCHING
- SOIL RETENTION BLANKET
- ☒ PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON
ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED
FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS,
OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- STABILIZED CONSTRUCTION EXIT
- ☒ TEMPORARY SILT FENCE
- ☒ TEMPORARY SILT DIKES
- TEMPORARY FIBER LOG
- DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- ROCK FILTER DAMS
- TEMPORARY SLOPE DRAIN
- PAVED DITCH W/ DITCH LINER PROTECTION
- TEMPORARY DIVERSION CHANNELS
- TEMPORARY SEDIMENT BASINS
- TEMPORARY SEDIMENT TRAPS
- TEMPORARY SEDIMENT FILTERS
- ☒ TEMPORARY SEDIMENT REMOVAL
- ☒ RIP RAP
- INLET SEDIMENT FILTER
- TEMPORARY BRUSH SEDIMENT BARRIERS
- SANDBAG BERMS
- TEMPORARY STREAM CROSSINGS
- ☒ FLEXAMAT / ARTICULATED CONCRETE BLOCK
- COMPOST FILTER SOCKS
- EROSION CONTROL MATS AND BLANKETS

OFFSITE VEHICLE TRACKING:

- ☒ HAUL ROADS DAMPENED FOR DUST CONTROL
- ☒ LOADED HAUL TRUCKS TO BE COVERED WITH TARPULIN
- ☒ EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE
FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM
THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED.
INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY
7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS
RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE
AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND
EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT
NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE
CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS
FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING,
SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE
REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE
CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND
FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP
MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS,
CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE
OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS
INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE
ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT
CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL
QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING
THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH
THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL
SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO
IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF
FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND
THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE
PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE
INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST
PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2019 ODOT STANDARD SPECIFICATIONS SHOULD
BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE
STATE OF OKLAHOMA." ODEQ, WATER QUALITY DIVISION, OCTOBER 18, 2022.

ADDITIONAL PERMITS REQUIRED FROM OKLAHOMA WATER RESOURCES BOARD

NORMAN




DESIGN DJG
DRAWN KMH
CHECKED ---


E. POST OAK ROAD
CLEVELAND COUNTY
**STORM WATER
MANAGEMENT PLAN**
PROJECT NO. K-2324-151 SHEET NO. R001

SEC. 16, T8N, R1W

SEC. 15, T8N, R1W


SEC. 14, T8N, R1W



SEC. 21, T8N, R1W

SEC. 22, T8N, R1W

SEC. 23, T8N, R1W




DESIGN	---	E. POST OAK ROAD	CLEVELAND COUNTY
DRAWN	---	GEOMETRIC DATA	
CHECKED	---		
MKEC		JOB PIECE NO. <u>K-2324-151</u>	SHEET NO. <u>R002</u>

G:\projects\2024\4403010281 City of Norcross Post Oak Rd\GIS\Drawings\K-2324-151-GEOMETRIC LAYOUT.dwg PLOTTED: Wednesday, April 08, 2026 @ 02:47PM

DESCRIPTION	REVISIONS	DATE

DRAINAGE AREAS			
DA	DISTURBED AREA	TO	E.C. METHOD
1	0.14 AC.	BRIDGE A	SILT FENCE
2	0.13 AC.	BRIDGE A	SILT FENCE SILT DIKE
3	0.01 AC.	OFFSITE	SILT DIKE
4	0.14 AC.	BRIDGE A	SILT FENCE
5	0.13 AC.	BRIDGE A	SILT FENCE SILT DIKE

SEC. 15, T8N, R1W



SEC. 22, T8N, R1W

LEGEND

TEMPORARY SILT DIKE

TEMPORARY SILT FENCE

SOLID SLAB SODDING

ARTICULATING CONC. BLOCK

SOLID SLAB SODDING
THIS SHEET = 882 SY

DESIGN	---	E. POST OAK ROAD	CLEVELAND COUNTY
DRAWN	---	EROSION CONTROL PLAN	
CHECKED	---		
MKEC		JOB PIECE NO. <u>K-2324-151</u>	SHEET NO. <u>R003</u>


G:\projects\2024\K-2324\0281 City of Norman Post Oak Bridge\00 CAD\STDS\Plan\K-2324-151-EROSION CONTROL.dwg
PLOTED: Wednesday, April 08, 2026 @ 02:47PM

NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY, FENCES, UTILITIES, AND OTHER EXIST. OBJECTS ARE FROM CONSTRUCTION REFERENCE LINE.

SEC. 15, T8N, R1W

SEC. 22, T8N, R1W

PLOTTED: Wednesday, April 09, 2025 @ 02:41PM BY: Kim Hendley G:\projects\2024\K-2324\00281-City of Norman_Plan_04e_Bridge_00_CAD\SP15\proj\K-2324-15-PLAN AND PROFILE.dwg



SURVEY CONTROL DATA

1. POSITIONAL CONTROL:
- A. POSITIONAL CONTROL FOR THIS SURVEY IS THE NGS OKLAHOMA STATE PLANE COORDINATE SYSTEM, NAD88 (1993), LAMBERT PROJECTION (SOUTH ZONE).

B. ACCURACY – THE POSITIONAL CONTROLS FOR THIS SURVEY MEETS OR EXCEEDS THE FOLLOWING ACCURACY CRITERIA:

1. NETWORK ACCURACY: 0.10 FOOT

2. LOCAL ACCURACY: 0.05 FOOT
2. BEARINGS:

THE BEARINGS SHOWN HEREIN OR HEREON ARE GRID BEARINGS DERIVED FROM THE NGS OKLAHOMA STATE PLANE COORDINATE SYSTEM AND ARE NOT ASTRONOMICAL.


3. VERTICAL CONTROLS:
- A. LEVEL DATUM IS NAVD 88 FROM Differential Leveling
- B. ACCURACY – VERTICAL CONTROL FOR THIS SURVEY MEETS OR EXCEEDS THE FOLLOWING ACCURACY CRITERIA:

1. NETWORK ACCURACY (FROM GPS OR LEVELING): 0.10 FOOT

2. LOCAL ACCURACY (CONFIRMED BY LEVELING): 0.02 FOOT

Point Table				
Point #	Description	Northing	Easting	Elevation
1	CP / SET 1/2IN IP W/ CP CAP	665,613.5710	2,178,204.4740	1,181.37
2	CP / SET 1/2IN IP W/ CP CAP	665,694.3894	2,180,928.6440	1,196.72
201	BM / SET 3/4IN IP	665,606.2776	2,178,592.7251	1,189.40
202	BM / SET 3/4IN IP	665,617.7271	2,179,047.2370	1,138.79
203	BM / SET CUT X ON BRIDGE	665,678.0427	2,179,513.5970	1,123.36
204	BM / SET CUT X ON CURB	665,652.2509	2,179,888.5750	1,139.64
205	BM / SET 3/4IN IP	665,640.1612	2,180,362.3020	1,175.98

POST OAK BRIDGE
NORMAN, OKLAHOMA



UTILITY OWNER INFORMATION

CITY OF NORMAN

JARED MATTERN 405-329-0703
JARED.MATTERN@NORMANOK.GOV

AT&T DISTRIBUTION

JOE ANDERSON 539-444-1026
JA492C@ATT.COM

OEC FIBER

MORGAN EDERER 405-217-6615
MORGAN.EDERER@OKCOOP.ORG

OG&E

MATT HILL
HLLMC@OGE.COM


LEGEND		
	BENCHMARK	
	BOLLARD	
	BUSH	
	CONTROL POINT	
	DOWNSPOUT	
	ELECTRIC MARKER	
	ELECTRIC METER	
	ELECTRIC PEDESTAL	
	ELECTRIC VAULT	
	FIBER OPTIC MARKER	
	FIBER OPTIC PEDESTAL	
	FIBER OPTIC VAULT	
	FIRE HYDRANT	
	GAS MARKER	
	GAS METER	
	SIGN	
	SPRINKLER	
	TANK FILLER	
	TELEPHONE PEDESTAL	
	TIE-DOWN	
	TREE CONIFEROUS	
	WATER METER	
	WATER VAULT	

DEPICTED PROPERTY LINE

TOPOGRAPHY CERTIFICATION –
I, J. WYATT BISHOP, CERTIFY THAT THIS PROJECT WAS COMPLETED UNDER MY DIRECT AND RESPONSIBLE CHARGE FROM AN ACTUAL SURVEY MADE UNDER MY SUPERVISION; THAT THIS GROUND TOPOGRAPHIC SURVEY WAS PERFORMED AT THE 95 PERCENT CONFIDENCE LEVEL TO MEET FEDERAL GEOGRAPHIC DATA COMMITTEE STANDARDS; THAT THIS SURVEY WAS PERFORMED TO MEET THE REQUIREMENTS FOR A TOPOGRAPHIC PLANIMETRIC SURVEY, ACCORDING TO THE OKLAHOMA MINIMUM TECHNICAL STANDARDS FOR THE PRACTICE OF LAND SURVEYING AS ADOPTED BY THE OKLAHOMA STATE BOARD OF LICENSURE FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS. THE ORIGINAL DATA WAS OBTAINED ON 2 MAY 2024 – 31 MAY 2024; THE SURVEY WAS COMPLETED ON 3 JUNE 2024; ALL COORDINATES ARE BASED ON NAD83 OKLAHOMA STATE PLANE, SOUTH ZONE AND ALL ELEVATIONS ARE BASED ON NAVD88.

**THIS IS A TOPOGRAPHIC SURVEY AND IS NOT A BOUNDARY SURVEY. ANY PROPERTY LINE OR RIGHT-OF-WAY INFORMATION SHOWN HEREON IS FOR REFERENCE IN DESIGNING IMPROVEMENTS AND WAS PLOTTED USING METHODS OF RELATING PROPERTY DESCRIPTIONS TO SECTION BOUNDARY LINES AND PHYSICAL EVIDENCE, HOWEVER, THIS DOES NOT CONSTITUTE A BOUNDARY SURVEY PER OKPELS MINIMUM STANDARDS OF THE PROPERTY LINES OR RIGHT-OF-WAY BEING DEPICTED.

J. WYATT BISHOP P.L.S. #1649



PERSONNEL:

KELLY FARMER

JOE FARMER

ADAM HINDS

WYATT BISHOP

JESSICA BISHOP

ALLYSON BRUEGGEN

STEPHANIE VILLANELLA

CHASE KILE

JAMIL EHTISHAM

ALBERT SMITH

ALEC CENICEROS

MATT DAFFERN

LEVI WOOD

DREW KNIGHT

JJ VALENTINE

COOPER VAUGHN

DAWSON HUDDLESTON

KADEN VANBUSKIRK

COOPER SMITH

BRADEN DAVENPORT

TITLE:

PRESIDENT

PROFESSIONAL LAND SURVEYOR

PROFESSIONAL LAND SURVEYOR

PROFESSIONAL LAND SURVEYOR

SENIOR CAD TECHNICIAN

SENIOR CAD TECHNICIAN

CAD TECHNICIAN

CAD TECHNICIAN

LIDAR SPECIALIST

SENIOR PARTY CHIEF

SURVEY PARTY CHIEF

SURVEY PARTY CHIEF

SURVEY PARTY CHIEF

SURVEY CREW MEMBER

SURVEY CREW MEMBER

SURVEY CREW MEMBER


SURVEY CREW MEMBER

SURVEY CREW MEMBER

SURVEY CREW MEMBER

SURVEY CREW MEMBER

SURVEY NOTES:
1) UTILITY LINES ARE SHOWN BY MAPPING THE MARKINGS IN THE FIELD PRODUCED FROM THE OKIE 811 UTILITY LOCATE TICKET #'S 24041907580417, 24041908020435, 24041908080461, 24041908130487, 24041908150511.



REV		DATE	DESCRIPTION		BY	APP'D
1	06/03/24	NT	TOPOGRAPHIC SURVEY - COMPLETE	ABB	ABB	JFB
2	06/03/24	NT	AS-BUILT TREE LINES ADDED	ABB	ABB	JFB

P.O. BOX 7197
Edmond, OK 73083
405.285.0433

frontier
LAND SURVEYING

CA #7232

POST OAK BRIDGE OVER JIM BLUE CREEK	TOPOGRAPHIC SURVEY
DRAWN BY ABB	DATE 06/03/2024
SCALE 1"=50'	JOB NO. 24-0049
SHEET S001	

POB STA: 100+00
POST OAK ROAD
SET MAG NAIL

SE/4, SW/4, SW/4
Bk2378, Pg881

SECTION 22
T-8-N, R-1-W
NW/4

SHEET 3

TOPOGRAPHIC
SURVEY

SHEET S002

[illegible]


P.O. BOX 7197
Edmond, OK 73083
405.285.0433

frontier
LAND SURVEYING

CA #7232

SW/4 - Bk6349, Pg918

TITLE RESEARCH PROVIDES THAT AREA WAS
SUBJECT TO "CONSTRUCTION AND
IMPOUNDMENT" EASEMENT PER BK431 PG 466,
FILED IN 1965, SINCE HAS BEEN PARTIALLY
RELEASED PER BK 578 PG326 FILED IN 1974

[illegible]

Frontier LAND SURVEYING

0A #1202

POST OAK BRIDGE
OVER JIM BLUE
CREEK

SURVEY

DRAWN BY ABB	DATE 06/03/2024
SCALE 1"=50'	JOB NO. 24-0049

HEET S003

SHEET 2

SHEET 3

SHEET 3

SHEET 4

SECTION 22
T-8-N, R-1-W
NW/4

BK5406, Pg1079

TITLE RESEARCH PROVIDES THAT AREA WAS
SUBJECT TO "CONSTRUCTION AND
IMPOUNDMENT" EASEMENT PER BK431 PG 466,
FILED IN 1965, SINCE HAS BEEN PARTIALLY
RELEASED PER BK 578 PG326 FILED IN 1974

1" = 50'


SHEET 4

SW/4 - Bk6349, Pg918

STA: 120+27.91 CL 3-W-Pwr.O.H.
"X"ing CL - 12.4' Rt.
Low Wire Elev. = 1193.39' at SAG

STA: 120+39.08 CL 1-W-Pwr.O.H.
"X"ing CL - 7.5' Rt.
Low Wire Elev. = 1193.92' at SAG


PI STA: 120+64.42
S 1/4 COR. SEC 15
FOUND RAILROAD SPIKE



SECTION 22
T-8-N, R-1-W
NW/4

Bk5406, Pg1079

STA: 120+87.14 18"x39.5' CMP
S.D. CL 13.3' Rt.
FLL Elev. = 1173.97' In & 1172.18' Out
Note: East End Crushed and has
Concrete in Bottom

[illegible]

P.O. BOX 7197
Edmond, OK 73083
405.285.0433

405.285.0433

frontier
LAND SURVEYING

CA #7232

POST OAK BRIDGE
OVER JIM BLUE
CREEK

TOPOGRAPHIC
SURVEY

DRAWN BY ABB	DATE 06/03/2024
SCALE 1"=50'	JOB NO. 24-0049

SHEET S004

W/2, W/2. SE/4
Bk6351, Pg1026

POT STA: 123+14.42
SET MAG NAIL

POE STA: 127+00
SET MAG NAIL

127+00

CP #2

N 89°58'40" E
2,598.45'

[illegible]

P.O. BOX 7197
Edmond, OK 73083
405.285.0433

405.285.0433

frontier
LAND SURVEYING

2021 2022

POST OAK BRIDGE
OVER JIM BLUE
CREEK

TOPOGRAPHIC SURVEY

DRAWN BY ABB	
SCALE 1"=50'	

DATE
6/03/2024

JOB NO.
24-0049

HEET S005

TRACT 17 BENT OAKS
RANCH Bk5345, Pg387


STA: 122+62.82 18"x39.5' CMP
S.D. CL 11.9' Rt.
17"x13" CMP FL Elev. = 1176.51
9" Smooth Plstc FL Elev. = 1172
Note: Transition of pipe is underground and undetermined

TRACT 16 BENT OAKS
RANCH Bk4485, Pg399


STA: 125+59.62 21"x15"x19.8' CMP
S.D. CL 9.1' Rt.
FL Elev. = 1185.33' In & 1184.57' Out
Note: Both Ends are Buried

SECTION 22
T-8-N, R-1-W
NE/4


$$1'' = 50'$$



- 1) FOUND 60D NAIL IN RAILROAD TIE POST - 47.00' @ N 37°53'34" E
- 2) FOUND 1/2" IRON PIN - 46.86' @ N 38°20'18" E
- 3) FOUND 1/2" IRON PIN - 41.59' @ S 34°29'25" W
- 4) FOUND 60D NAIL IN WOOD POST - 41.71' @ S 35°06'51" W
- 5) FOUND 1/2" IRON PIN - 48.21' @ N 38°35'49" W



- 1) SET 60D NAIL IN W FACE OF POWER POLE 1.5' HIGH
29.78' @ S 07°17'33" E
- 2) SET 60D NAIL IN NE FACE OF POWER POLE 1.5' HIGH
70.54' @ N 59°53'11" W
- 3) FOUND 1/2" IRON PIN
38.69' @ N 00°23'08" W



- 1) FOUND 60D NAIL IN S FACE OF RAILROAD TIE CORNER POST
41.57' @ N 35°30'15" E
- 2) 60D NAIL IN W FACE OF POWER POLE
45.06' @ S 30°12'34" E
- 3) SET CUT "X" IN CONCRETE PAD FOR STRUCTURE
53.17' @ S 21°19'33" W

[illegible]

P.O. BOX 7197
Edmond, OK 73083
405.285.0433




CA #1232

POST OAK BRIDGE
OVER JIM BLUE
CREEK

TOPOGRAPHIC
SURVEY

DRAWN BY ABB	
SCALE 1"=50'	

SHEET S006



LEGEND



DETOUR AHEAD



DETOUR DIRECTION SIGN



WORK AREA

NOTE:
SEE COUNTY ROAD CLOSURE DETAIL FOR
SIGN DETAILS AND PLACEMENT, SHEET T002



DESIGN

DJG

DRAWN

KMH

CHECKED

D	---




E. POST OAK ROAD	CLEVELAND COUNTY
------------------	------------------

DETOUR PLAN

PROJECT NO. K-2324-151 SHEET NO. T001


C:\projects\2024\2403012261 City of Norwalk Post Oak Bridge\00 CAD\Signs\plan\K-2324-151-COUNTY ROAD CLOSURE DETAIL.dwg
PLOTED: Wednesday, April 09, 2025 @ 02:14PM



**TYPICAL APPLICATION
COUNTY ROAD (DETOUR IS ESTABLISHED)**

NOTES:
WHEN A DETOUR ROUTE IS ESTABLISHED IN CONJUNCTION WITH THE CONSTRUCTION THE DETOUR ROUTE SHALL BE SHOWN IN THE PLANS. EITHER THE CONTRACTOR OR THE COUNTY WILL BE RESPONSIBLE FOR THE DETOUR SIGNING AND THIS RESPONSIBILITY SHALL BE STATED IN THE PLANS.


THE CONSTRUCTION SIGNING SHOWN ON THIS PLAN SHEET AND FROM THE OPPOSITE DIRECTION (NOT SHOWN) SHALL ALWAYS BE THE RESPONSIBILITY OF THE CONTRACTOR.



**TYPICAL APPLICATION
COUNTY ROAD (NO DETOUR ESTABLISHED)**

	DESIGN	DJG	E. POST OAK ROAD CLEVELAND COUNTY
	DRAWN	KMH	
	CHECKED	---	
COUNTY ROAD CLOSURE DETAIL			PROJECT NO. <u>K-2324-151</u> SHEET NO. <u>T002</u>

DESCRIPTION	REVISIONS	DATE



FLEXAMAT STANDARD CHANNEL - LAYOUT PARALLEL TO FLOW

CONSTRUCTION NOTES:

1. AN ENGINEER OR MANUFACTURES REPRESENTATIVE SHALL BE ONSITE FOR THE START OF THE INSTALLATION.
2. GRADE CHANNEL SO THAT WATER WILL FLOW DOWN CENTER OF THE CHANNEL AND BE CONTAINED TO THE CHANNEL. ALL SUBGRADE SURFACES PREPARED FOR PLACEMENT OF MATS SHALL BE SMOOTH AND FREE OF ALL ROCKS, STICKS, ROOTS, OTHER PROTRUSIONS, OR DEBRIS OF ANY KIND.
3. PRIOR TO FLEXAMAT STANDARD INSTALLATION SEED AND FERTILIZE THE PREPARED SUBGRADE WITH SITE SPECIFIC SEED MIX AND IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS.
4. INSTALL FLEXAMAT STANDARD ROLLS, USING THE WIDEST ROLLS POSSIBLE TO AVOID SEAMS.
 - 4.1. FOR CHANNELS THAT ARE WIDER THAN 16', INSTALL 15.5' WIDE FLEXAMAT STANDARD ROLLS THAT INCLUDE 12" GEOGRID EXTENSIONS WITH A 6" STANDARD UNDERLAYMENT EXTENSIONS. THESE SEAMS ARE PARALLEL WITH FLOW, THE ADJACENT MAT INSTALLED OVER THE EXTENSIONS. ENSURE GEOGRID AND STANDARD UNDERLAYMENT EXTENSIONS ARE LAYING FLAT ON SUBGRADE PRIOR TO INSTALLING ADJACENT MAT.
 - 4.2. SECURE THE ABUTMENT PARALLEL WITH FLOW BY INSTALLING 18" U-ANCHORS IN 2' INCREMENTS OR 20" STAINLESS STEEL ZIP TIES IN 1' INCREMENTS THROUGH THE EXTENSION OVERLAP. U ANCHORS OR ZIP TIES TO BE INSTALLED PERPENDICULAR TO FLOW. ZIP TIES SHALL ENCOMPASS 3 CORDS OF GEOGRID FROM EACH MAT.
5. FOR ADDITIONAL SECTIONS OF MAT, SECURE SEAM PERPENDICULAR WITH FLOW BY OVERLAPPING THE DOWNSTREAM SECTION 18" WITH UPSTREAM SECTION OF MAT. PRIOR TO INSTALLING OVERLAP, FLIP UPSTREAM MAT BACK 24". EXCAVATE 2.25" OF SOIL 18" FROM END OF UPSTREAM MAT. DOWNSTREAM SECTION IS LAID IN THE SHALLOW TRENCH. RETURN AND TAMP SOIL OVER INITIAL EDGE AND SEED.
 - 5.1. SECURE OVERLAPS PERPENDICULAR TO FLOW BY INSTALLING 18" U-ANCHORS IN 2' INCREMENTS OR 20" STAINLESS STEEL ZIP TIES IN 1' INCREMENTS THROUGH THE OVERLAP. ZIP TIES SHALL ENCOMPASS 3 CORDS OF GEOGRID FROM EACH MAT.
6. AT THE INITIAL LEADING EDGE OF THE FLEXAMAT STANDARD ARMORED CHANNEL, EMBED THE MAT 18" IN A VERTICAL ANCHOR TRENCH. FILL AND COMPACT ANCHOR TRENCH WITH SUITABLE FILL. AT ENDING EDGE OF PROTECTION, EMBED THE MAT 18" IN A TERMINATION TRENCH. THE TRENCH SHALL BE FILLED AND COMPACTED WITH SUITABLE FILL, AS DETERMINED BY THE ENGINEER OF RECORD.

**MOTZ
ENTERPRISES, INC.**

Flexamat

(513)772-6689

Info@Flexamat.com

Flexamat.com



REV - 2




DESIGN	DJG
DRAWN	KMH
CHECKED	---
MKEC	

E. POST OAK ROAD CLEVELAND COUNTY

**FLEXAMAT
STANDARD DETAIL
(SHEET 1 OF 2)**

PROJECT NO. K-2324-151 SHEET NO. U001

DESCRIPTION	REVISIONS	DATE



FLEXAMAT STANDARD - SLOPE ARMORING

CONSTRUCTION NOTES:

1. AN ENGINEER OR MANUFACTURERS REPRESENTATIVE SHALL BE ONSITE FOR THE START OF THE INSTALLATION.
2. ALL SUBGRADE SURFACES PREPARED FOR PLACEMENT OF MATS SHALL BE SMOOTH AND FREE OF ALL ROCKS, STICKS, ROOTS, OTHER PROTRUSIONS, OR DEBRIS OF ANY KIND.
3. PRIOR TO FLEXAMAT STANDARD INSTALLATION SEED AND FERTILIZE SUBGRADE WITH SITE SPECIFIC SEED MIX IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS.
4. INSTALL FLEXAMAT STANDARD ROLLS THAT ARE CONTINUOUS FOR ENTIRE SLOPE LENGTH. FOR SLOPES LONGER THAN 16', USE MATS WITH EXTENSIONS CUT TO THE LENGTH OF THE SLOPE. INSTALL MATS TO THAT THE MATTING EXTENDS PAST THE CREST OF SLOPE AND INTO AN 18" ANCHOR TRENCH.
 - 4.1. FOR ARMORED SLOPE LENGTHS 16' OR LESS, INSTALL CURLEX ECB EQUALLY UNDER ADJACENT MATS. SECURE SEAM WITH #3 REBAR 18" U-ANCHORS IN 2' INCREMENTS THE LENGTH OF THE ABUTMENT.
 - 4.2. ARMORED SLOPE LENGTHS LONGER THAN 16', INSTALL NEXT MAT OVER EXTENSIONS.
5. INSTALL SUBSEQUENT MATS OVER THE GEOGRID EXTENSION AND STANDARD UNDERLAYMENT EXTENSION OF THE PREVIOUSLY INSTALLED MAT. ENSURE THE GEOGRID AND STANDARD UNDERLAYMENT EXTENSIONS ARE LAYING FLAT ON THE SUBGRADE BEFORE INSTALLING ADJACENT MAT OVER THE EXTENSIONS.
6. INSTALL #3 REBAR 18" U-ANCHORS IN 2' INCREMENTS ACROSS THE GEOGRID AND STANDARD EXTENSION ABUTMENT. INSTALL ANCHORS PERPENDICULAR TO THE SLOPE DIRECTLY BEHIND FIRST ROW OF BLOCKS ON THE ADJACENT MAT.
7. AT THE END OF THE ARMORED SLOPE, IF HEAD CUT IS ANTICIPATED, EMBED THE MAT 18" IN A TERMINATION TRENCH. FILL AND COMPACT TERMINATION TRENCH WITH SUITABLE FILL.

**MOTZ
ENTERPRISES, INC.**

Flexamat

(513)772-6689

Info@Flexamat.com

Flexamat.com



REV - 2




DESIGN	DJG
DRAWN	KMH
CHECKED	---

E. POST OAK ROAD CLEVELAND COUNTY


**FLEXAMAT
STANDARD DETAIL
(SHEET 2 OF 2)**

PROJECT NO. K-2324-151 SHEET NO. U002





Plotted: Wednesday, April 09, 2025 @ 02:49PM C:\projects\2024\2324\0001\City of Norman_Post Oak Bridge\00 CAD\REV Models\K-2324-151-DESIGN.dwg



113 + 20
112 + 80
112 + 50

110120130140150160

CROSS SECTION

05'10'20'


100

FACILITY E. POST OAK ROAD

PROJECT. NO. K-2324-151

CLEVELAND COUNTY

SHEET NO. X002



Plotted: Wednesday, April 09, 2025 @ 02:49PM
C:\projects\2024\2403010281_City of Norma_Post Oak Bridge\00_CAD\REF Models\K-2324-151_DESIGN.dwg

100

CROSS SECTION

0 5' 10' 20'

FACILITY


E. POST OAK ROAD

PROJECT. NO.

K-2324-151

CLEVELAND COUNTY

SHEET NO. X003



17
PLOTED: Wednesday, April 09, 2025 @ 02:49PM
C:\projects\2024\2403010281_City of Norma_Post Oak Bridge\00_CAD\REF_Model\K-2324-151_DESIGN.dwg