

## KEY NOTE SYMBOL LEGEND:

REFER TO - BUBBLE NOTE WITHOUT ARROWS APPLIES TO ENTIRE ROOM IN WHICH IT IS LOCATED UNLESS SHOWN OTHERWISE.

REFER TO - BUBBLE NOTE WITH ARROWS APPLIES TO OBJECT INDICATED.

## **KEY NOTES:**

- DEMOLISH WALL FOR NEW WINDOW OPENING INSPECT EXIST.CMU FOR BOND BEAM, SUPPORT AS REQUIRED PRIOR TO DEMO.
- DEMOLISH INTERIOR WALL.
- REMOVE OVERHEAD DOOR.
- REMOVE DOOR.
- REMOVE WINDOW.
- DEMOLISH CURB.
- DEMOLISH FLOORING.
- DEMOLISH WALL SIGN.

## **GENERAL NOTES - DEMOLITION**

DATA PRESENTED IN THESE DRAWINGS ARE AS ACCURATE AS SURVEYS AND PLANNING CAN DETERMINE, BUT ABSOLUTE ACCURACY IS NOT GUARANTEED. FIELD VERIFICATION OF THE PLANS IS THE RESPONSIBILITY OF THE CONTRACTOR SINCE FINAL DISTANCES, LOCATIONS AND HEIGHTS WILL BE GOVERNED BY ACTUAL FIELD CONDITIONS. CONTRACTOR TO FIELD VERIFY

EXISTING CONDITIONS IN AREAS TO BE RENOVATED PRIOR TO BID IN ORDER TO PROVIDE AN ACCURATE BID AND BE AWARE OF ALL CONSTRUCTION METHODS NEEDED TO PROVIDE THE FINISHED PRODUCT AS SHOWN ON THE

> ARCHITECT FOR A DECISION TO RESOLVE CONFLICTS PRIOR TO BID. CONTRACTOR SHALL FINISH ALL EXPOSED ITEMS IN NEW CONSTRCUTION.

PLANS. DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE

CONSTRUCTION IN AREAS TO BE RENOVATED SHALL BE CAREFULLY COORDINATED WITH THE OWNER AND ARCHITECT PRIOR TO CONSTRUCTION. EXISTING EQUIPMENT WILL BE RENOVATED SHALL BE CAREFULLY COORDONATED WITH THE OWNER AND ARCHITECT PRIOR TO CONSTRUCTION. EXISTING EQUIPMENT WILL BE RELOCATED OR STORED AS PER OWNER'S DIRECTION. EQUIPMENT AND FURNISHINGS TO BE STORED SHALL BE PROTECTED FROM DAMAGE AND VANDALISM IN LOCATIONS ACCEPTABLE TO

DASHED LINES ON DEMOLITION PLANS/ ELEVATIONS INDICATE EXISTING MATERIALS TO BE REMOVED, UNLESS OTHERWISE NOTED. EQUIPMENT TO BE REUSED SHALL BE STORED AND PROTECTED FROM DAMAGE DURING CONSTRUCTION, ANY DAMAGE RESULTING FROM CONSTRUCTION WILL BE REPAIRED TO ITS ORIGINAL STATE.

ITEMS TO REMAIN AND TO BE PROTECTED ARE DESIGNATED WITH LIGHT CONTINUOUS LINES. IF DAMAGE OCCURS, PATCH, REPAIR, REFINISH OR REPLACE DAMAGED ITEMS AT NO COST TO OWNER.

REPAIR SOFFITS, CEILING. WALL AND FLOOR FINISHES LEFT VOID OR DAMAGED BY DEMOLITION WORK TO MATCH EXISTING ADJACENT FINISHES.

REPAIR ALL EXIST. CONSTRUCTION DAMAGED BY DEMOLITION TO LIKE NEW

APPEARANCE.

REPAIR WALLS DAMAGED BY DEMOLITION TO PROVIDE SMOOTH SURFACE,

WITH PATCHES DRESSED FLUSH, SMOOTH AND READY TO RECEIVE FINISH MATERIAL.

COORDINATE DEMOLITION AND CONSTRUCTION OPERATIONS WITH OWNER WHERE THEY EFFECT EXISTING WORK AREAS AND NORMAL OPERATING PROCEDURES.

DEMOLITION EXPOSING THE INTERIOR OF THE BUILDING TO THE OUTSIDE ELEMENTS OR TO THE PUBLIC SHALL BE PROPERLY SEALED AND PROTECTED TO DAMAGE FROM VANDALISM OR WEATHER DURING CONSTRUCTION.

PROVIDE SCREENING FROM DUST, FUMES, SMOKE, WATER, AND NOISE WHERE DEMOLITION REQUIRES CONSTRUCTION TO BE TO BE EXPOSED TO NORMAL OPERATIONS OF THE FACILITY.

CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO THE DEMOLITION WORK. PROBLEMS OR DISCREPANCIES IN THE PLAN SHALL BE REPORTED AT ONCE TO THE ARCHITECT AND ALL WORK INVOLVED AT SAID QUESTIONED AREA SHALL BE HALTED UNTIL ARCHITECT GIVES NOTICE TO

PROTECT ALL EXISTING FLOORING FROM DAMAGE & REPAIR ANY DAMAGE TO LIKE NEW APPEARANCE UNLESS NOTED W/ NEW FLOORING.

PATCH SURFACES AS REQUIRED TO MATCH EXISTING WHERE PLUMBING, MECHANICAL, AND ELECTRICAL ITEMS OR EQUIPMENT HAVE BEEN REMOVED.

GENERAL CONTRACTOR TO PROPERLY DISPOSE, DONATE, AND/OR RECYCLE ALL DEMO ITEMS, UNLESS OTHERWISE NOTED "RETURN TO OWNER". COORD. W/ ARCH. & OWNER.

COORDINATE ALL HVAC DUCTWORK, RETURNS & SYSTEM SPECS W/ HVAC SUB-CONTRACTOR & ARCHITECT.

Q. SECURE & LEVEL ALL FLOOR & SUB-FLOOR, TYP.

INSTALL ALL APPLIANCES (SELECTED & SUPPLIED BY OWNER) & PRODUCTS AS PER MANUFACTURE'S SPECIFICATIONS, REWORK PLUMBING & ELECTRICAL, COORD W/ OWNER & ARCHITECT, RE: POWER PLAN.

ALL EXTERIOR WALLS & SOFFITS WILL HAVE A MIN. OF R-19 INSULATION TO COMPLY W/ CITY IN WHICH CONSTRUCTION IS BEING DONE COORD. W/ ARCHITECT & OWNER - WHERE NECESSARY.

ATTICS SHALL INCLUDE INSULATION W/ A MIN OF R-30 & RADIANT BARRIER BACKED OSB AT ALL NEW ROOF DECKING, COORD. W ARCHITECT & OWNER-

ALL GLASS IN WINDOWS & DOORS TO BE COMPLIANT W/ IRC 2021, E.G. U-FACTOR, SOLAR HEAT GAIN COEFFICIENT, ETC., COORD. ALL SELECTIONS

DOORS/WINDOWS TO BE RE-USED IN NEW CONSTRUCTION (COORD. W/ OWNER).


W. ALL NEW WALLS TO RECEIVE A LEVEL 4 TEXTURE AND TO BE PAINTED TO MATCH EXISTING WHERE APPLY.

X. ADD SMOKE DETECTORS & CO2 DETECTORS PER CURRENT CODE.

DOORS @ 45° ARE EXISTING TO REMAIN & 90° ARE NEW.

## LEGEND:

----- INDICATES ELEMENTS TO BE DEMOLISHED, NOTE: WALL MAY CONTAIN DOOR AND/OR WINDOW TO BE DEMO'D. VERIFY EXISTING CONDITION & PROCEED ACCORDINGLY. RE: GENERAL NOTES.



ARCHITECTURE PLANNING **INTERIORS** 119 W. MAIN STREET NORMAN, OK 73069 405.579.7883

FAX 405.292.0545

STRUCTURAL CONSULTANT: STRUCT-ENG

STRUCT-ENG-ADDR PHONE: PHONE

FAX: FAX MECHANICAL CONSULTANT:

MECH. ENG MECH-ENG-ADDR

PHONE: PHONE FAX: FAX

ELECTRICAL CONSULTANT: ELEC. ENG ELEC-ENG-ADDR


PHONE: PHONE FAX: FAX

OSBORN DRUGS 1035 36TH AVE. N.W. NORMAN OK 73072

PERMIT SET

RK	DATE	DESCRIPTION
REVISIONS		

PRIMARY ISSUE MARK DATE DESCRIPTION 07-09-25 | PERMIT ISSUE 07-15-25 BID ISSUE 00-00-00 | CONST. ISSUE



JOB NO.: K1125 2024 KRITTENBRINK ARCHITECTURE LLC ALL RIGHTS

RESERVED THESE DOCUMENTS NOT BE USED FOR DRAWN BY CHECKED BY

ARCHITECTURAL **DEMOLITION** 

SITE PLAN