



13 August 2025

Mr. Jason Murphy
Stormwater Program Manager
City of Norman
225 N. Webster
Norman, OK 73069

Re: Imhoff Creek Cut/Fill Quantities

Dear Mr. Murphy

The cut/fill quantities for the Imhoff Creek bank stabilization project are presented below. These quantities represent the cut and fill within the flood plan for this project.

CUT/FILL WITHIN FEMA BFE		
ITEM/OPERATION	CUT (CY)	FILL (CY)
REVETMENT	1355.95	834.67
RSS WALL	98.63	4051.31
CROSS VANES	0	24
TOTAL	1454.58	4909.98
NET	FILL	3455.4

The table shows a net Fill of **3455.4 Cubic Yards**.

Sincerely,

Harris Wilson, PE
Senior Project Manager



405.229.3260 (c)
-
615 N Hudson Avenue, Suite 300
Oklahoma City, OK 73102
wsbeng.com