

DRAWING REFERENCE LEGEND REFERS TO A PROFILE OR ELEVATION PROFILE NUMBER SHEET NUMBER ON WHICH IT IS LOCATED DETAIL DESCRIPTION SCALE: 1"=XX'

DATUM INFORMATION HORIZONTAL DATUM NAD83 (2011) OKLAHOMA SOUTH ZONE (3502) VERTICAL DATUM

CONTACT INFORMATION

CITY OF NORMAN PUBLIC WORKS DEPARTMENT 225 N WEBSTER AVE NORMAN, OK 73069 405-366-5453

NAVD88 (GEOID 12B)

NORMAN POLICE 201 WEST GRAY, BLDG. B, NORMAN, OK 73069

COX MARK BOWLING (405) 417-4064

OG&E 800-522-6870

AT&T CHRIS BURGESS

(405) 291-6569

<u>ONG</u> 800-458-4251

CITY OF NORMAN STANDARDS SPECIFICATIONS AND CONSTRUCTION DRAWINGS


OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) REGULATIONS SHALL APPLY FOR ALL WASTE

CITY OF NORMAN, OKLAHOMA

CONSTRUCTION PLANS FOR IMHOFF CREEK BANK STABILIZATION

CLEVELAND COUNTY





DRAWING INDEX

Sheet Number	Sheet Title
1	COVER
2	PAY ITEM AND CONSTRUCTION NOTES
3	SWMP
4	EROSION CONTROL PLAN 1
5	EROSION CONTROL PLAN 2
6	EROSION CONTROL PLAN 3
7	DEMOLITION PLAN 1
8	DEMOLITION PLAN 2
9	RSS WALL P&P
10	RSS WALL P&P 2
11	RSS WALL P&P 3
12	RSS WALL P&P 4
13	PR CRL DATA
14	NORTH GRADING
15	Section Sheet - (1)
16	Section Sheet - (2)
17	Section Sheet - (3)
18	Section Sheet - (4)
19	Section Sheet - (5)
20	Section Sheet - (6)
21	Section Sheet - (7)
22	Section Sheet - (8)
23	Section Sheet - (9)
24	Section Sheet - (10)
25	Section Sheet - (11)
26	MESHEK DETAILS
27	DETAIL STR-001 - REINF. SOIL SLOPE WAL
28	DETAIL STR-002 - REINF. SOIL SLOPE WAL
29	DETAIL STR-003 - REINF. SOIL SLOPE WAL
30	DETAIL STR-004 - REINF. SOIL SLOPE WAL

APPLICABLE STANDARDS:

<u>ODOT</u>

SSS-2-1 SOLID SLAB SODDING TESCA-0 TEMPORARY SEDIMENT CONTROLS TSD-0TEMPORARY SILT DIKE STANDARD PIPE INSTALLATION SPI - 5 - 2PBB-1-2 STANDARD PIPE BEDDING

APPROVED BY

CITY ENGINEER

ADVERTISEMENT DATE

Prepared By: MESHEK & ASSOCIATES, L.L.C.





3/22/24

MESHEK & ASSOCIATES, L.L.C. C.A. 1487 EXPIRES 6/30/25 1437 S. BOULDER AVE, STE. 1550 TULSA, OK 74119 (PH) 918-392-5620 (FAX) 918-392-5621 SHEET 1 OF 30 SHEETS

& ASSOCIATES, LLC

APPLICABLE SPECIFICATIONS:

CURRENT OKLAHOMA DEPARTMENT OF TRANSPORTATION LATEST EDITION (O.D.O.T.) STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION SHALL BE USED FOR THE TECHNICAL SPECIFICATIONS. (CITY OF NORMAN STANDARD SPECIFICATIONS AND CONSTRUCTION DRAWINGS TAKE PRECEDENTS OVER O.D.O.T.)

AND SEWER RELATED WORK.

ENTIRE PROJECT IS WITHIN CORPORATE LIMITS OF CITY OF NORMAN.

GENERAL CONSTRUCTION NOTES

GENERAL NOTES

- 1. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THESE DRAWINGS, DETAILS, AND SPECIFICATIONS, IN ADDITION TO THE CURRENT CITY OF NORMAN'S STANDARD SPECIFICATIONS, STANDARD DETAILS, AND STANDARD DRAWINGS AS WELL AS THE 2019 OKLAHOMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
- 2. THE CONTRACTOR SHALL COMPLY WITH ALL FEDERAL, STATE AND LOCAL LAWS GOVERNING SAFETY, HEALTH AND SANITATION. THE CONTRACTOR SHALL PROVIDE ALL SAFEGUARDS, SAFETY DEVICES AND PROTECTIVE EQUIPMENT, AND TAKE ANY OTHER NEEDED ACTION ON AS HIS OWN RESPONSIBILITY OR AS THE ENGINEER MAY DETERMINE REASONABLY NECESSARY TO PROTECT PROPERTY IN CONNECTION WITH THE PERFORMANCE OF WORK COVERED BY THE CONTRACT.
- 3. PAY ITEMS SHALL BE AS SPECIFIED ON THE CITY OF NORMAN OR ODOT STANDARD DRAWINGS EXCEPT AS MODIFIED BY THE CONTRACT.
- 4. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK IN EACH AREA. THE CONTRACTOR IS FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT RESULT FROM HIS FAILURE TO LOCATE AND PRESERVE ANY AND ALL UTILITIES.
- 5. THE LOCATIONS OF THE UTILITIES ARE SHOWN ACCORDING TO ALL AVAILABLE INFORMATION. THE CONTRACTOR SHALL NOTIFY EACH UTILITY OWNER PRIOR TO COMMENCEMENT OF WORK TO VERIFY BOTH HORIZONTAL AND VERTICAL LOCATIONS. THE FOLLOWING IS A LIST OF UTILITY OWNERS; AT&T, OKLAHOMA ELECTRIC COOPERATIVE (OEC), OKLAHOMA NATURAL GAS (ONG), OG&E, AND THE CITY OF NORMAN. SEE TITLE SHEET FOR CONTACT INFORMATION.
- 6. THE CONTRACTOR SHALL GIVE THE NOTIFICATION CENTER OF OKLAHOMA ONE—CALL SYSTEM, INC. NOTICE OF ANY EXCAVATION NO SOONER THAN TEN DAYS NOR LATER THAN 48 HOURS, EXCLUDING SATURDAYS, SUNDAYS AND LEGAL HOLIDAYS, PRIOR TO THE COMMENCEMENT OF WORK. PHONE 1—811—522—6543.
- 7. THE CONTRACTOR SHALL PRESERVE THE INTEGRITY OF THE EXISTING STRUCTURES WITHIN THE PROJECT EXTENTS UNLESS OTHERWISE SHOWN TO BE REMOVED OR ADJUSTED.
- 9. ALL EXCAVATED MATERIAL NOT REQUIRED IN THE PROJECT AS FILL SHALL BECOME THE PROPERTY OF THE CONTRACTOR. WASTE MATERIAL, INCLUDING BROKEN CONCRETE, BRICKS, OLD PIPE AND OTHER DEBRIS SHALL ALSO BE REMOVED FROM THE WORK ZONE. THE CONTRACTOR SHALL DISPOSE OF ALL WASTE MATERIAL IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS. ALL COSTS FOR REMOVAL OF WASTE MATERIAL SHALL BE INCLUDED IN THE BID PRICING FOR THIS PROJECT. NO ADDITIONAL PAYMENT WILL BE MADE FOR THE DISPOSAL OF THIS MATERIAL.
- 10. ALL TREES, BRUSH AND OTHER DEBRIS THAT MIGHT INTERFERE WITH THE FLOW OF WATER ARE TO BE CLEANED OUT AS NOTED IN THE PLANS. DISPOSAL SHALL BE IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS. ALL COST TO BE INCLUDED IN THE PRICE BID FOR THE PROJECT. TREES OUTSIDE THE FILL SLOPES AND THE TOP OF CUT SLOPES SHALL NOT BE DISTURBED EXCEPT WITH THE WRITTEN APPROVAL OF THE ENGINEER.
- 11. WHERE MATERIALS ARE TRANSPORTED IN THE PROSECUTION OF WORK, VEHICLES SHALL NOT BE LOADED BEYOND THE CAPACITY RECOMMENDED BY THE VEHICLE MANUFACTURER OR AS PRESCRIBED BY ANY FEDERAL, STATE OR LOCAL LAW OR REGULATION.
- 12. ANY DAMAGE TO THE ROADWAY PAVEMENT, CURB, DRIVEWAYS OR SIDEWALK CAUSED BY THE CONTRACTOR'S OPERATION SHALL BE REPAIRED TO THE ENGINEER'S SATISFACTION AND SHALL BE ACCOMPLISHED AT THE CONTRACTOR'S SOLE EXPENSE. ALL DISTURBED ITEMS SHALL BE REPAIRED TO MATCH EXISTING MATERIALS AND PATTERNING.
- 13. PHYSICAL TESTING FOR QUALITY ASSURANCE SHALL BE FURNISHED BY THE CITY.
- 14. REFLECTORIZED SHEETING ON SIGNS AND BARRICADES SHALL BE OF A CUBIC PRISMATIC TYPE AND SHALL MEET THE SPECIFICATIONS ESTABLISHED FOR ASTM D 4956-01 TYPE IX RETROREFLECTIVE SHEETING. REFLECTORIZED SHEETING ON DRUMS AND TUBE CHANNELIZERS SHALL BE OF A HIGH-INTENSITY TYPE AND SHALL MEET THE SPECIFICATIONS ESTABLISHED FOR ASTM D 4956-01 TYPE III RETROREFLECTIVE SHEETING.

- 15. THE CONTRACTOR SHALL REPLACE ANY SECTION CORNERS OR OTHER PERMANENT RIGHT OF WAY MARKERS REMOVED OR DISTURBED AS A RESULT OF THE CONSTRUCTION OF THIS PROJECT. REPLACEMENT OF SECTION CORNERS OR ANY OTHER MONUMENTS SHALL BE PERFORMED BY A LICENSED LAND SURVEYOR AUTHORIZED TO PERFORM WORK IN THE STATE OF OKLAHOMA.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTROL AND MAINTENANCE OF STORMWATER DRAINAGE.
- 17. STRAW OR HAY BALES AS STORMWATER BEST MANAGEMENT PRACTICES ARE NO LONGER ALLOWED ON CONSTRUCTION PROJECTS.
- 18. THE CONTRACTOR MUST CALL 1-800-458-4251 IMMEDIATELY IF A NATURAL GAS PIPELINE IS CUT, DAMAGED, OR OTHERWISE DISTURBED.
- 19. THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH THE REQUIREMENTS OF THE 404 PERMIT ISSUED BY THE ACOE FOR THIS PROJECT, IDENTIFICATION NUMBER SWT—2022—73. A COPY OF THE PERMIT IS AVAILABLE FROM THE CITY.
- 20. AS—BUILTS: THE CONTRACTOR SHALL KEEP ON SITE A CURRENT SET OF THE APPROVED CONSTRUCTION WORKING DRAWINGS AT ALL TIMES. THE CONTRACTOR SHALL MARK (IN RED INK) ALL APPROVED CHANGES INCURRED FOLLOWING PUBLIC WORKS DEPARTMENT APPROVAL OF THE INITIAL DRAWINGS. THESE CHANGES MAY BE INITIATED FROM FIELD CONDITIONS OR CHANGES MADE BY THE DESIGN ENGINEER OR THE PUBLIC WORKS ENGINEER. EXCEPT FOR MINOR FIELD ADJUSTMENTS, ALL CHANGES SHALL BE REVIEWED AND AGREED TO BY THE DESIGN ENGINEER AND THE PUBLIC WORKS ENGINEER PRIOR TO FINAL APPROVAL OF THE PROJECT. THE CONTRACTOR SHALL SUBMIT THE WORKING DRAWINGS TO THE ENGINEER OF RECORD (DESIGN ENGINEER) AFTER FINAL INSPECTION OF THE PROJECT TO SERVE AS A BASIS FOR DEVELOPMENT OF FINAL AS—BUILT RECORD DRAWINGS.
- 21. THE CONTRACTOR SHALL MONITOR THE WEATHER AND FORECASTS. ALL EQUIPMENT SHALL BE REMOVED FROM THE CREEK PRIOR TO SEVERE WEATHER/RAIN CAUSING THE CREEK TO RISE.

SPECIAL PAY ITEM NOTES:

- 1. ALL COSTS FOR REMOVING SHRUBS, STUMPS, POSTS, AND ALL OTHER DEBRIS AND/OR OBSTRUCTIONS NOT COVERED BY A SEPARATE PAY ITEM ARE INCLUDED IN THE PRICE BID.
- 2. ITEM TO INCLUDE ALL COSTS FOR REMOVING TREES AND SHRUBS IN THE CREEK BED AND ON THE CREEK EMBANKMENTS THAT ARE TO BE STABILIZED. THIS INCLUDES TREE FALLS ACROSS THE CREEK.
- 3. CONSTRUCTION STAKING SHALL INCLUDE SURVEYING AND THE FURNISHING, PLACING, AND MAINTAINING OF THE CONSTRUCTION LAYOUT STAKES NECESSARY FOR THE PROPER COMPLETION AND INSPECTION OF THE ENTIRE PROJECT.
- 4. EROSION PROTECTION SHALL BE PLACED AS NECESSARY TO PREVENT EROSION WASH TO ADJACENT PROPERTY. EROSION PROTECTION SHALL BE REMOVED AT THE END OF THE PROJECT AS DIRECTED BY THE ENGINEER, COST TO BE INCLUDED IN THE PRICE BID. THE PRICE INCLUDES THE COST OF SEDIMENT REMOVAL PER THE STORMWATER MANAGEMENT PLAN. COST SHALL BE INCLUDED IN THE PRICE BID.
- 5. THE PAY ITEM FOR SOLID SLAB SODDING INCLUDES QUANTITIES FOR PLACEMENT AND COMPACTION OF SUITABLE BACKFILL AND SOD AT EXISTING GRASS AREAS WHICH MAY BE DAMAGED DURING CONSTRUCTION ACTIVITY OF THE CONTRACTOR ACCESSING THE WORK ZONE FROM IMHOFF ROAD, BACK YARDS AFFECTED BY THE CONSTRUCTION OF THE WALL, AND OTHER MISCELLANEOUS AREAS DAMAGED BY CONSTRUCTION ACTIVITIES.
- 6. COST OF WATERING AND FERTILIZING SHALL BE INCLUDED. FERTILIZERS SHALL BE 10-20-10 AND SHALL BE APPLIED AT THE RATE OF 1.5 LBS PER 10 SQ YDS. FERTILIZER SHALL BE APPLIED PER SECTION 230.04H OF ODOT STANDARD SPECIFICATIONS. WATERING SHALL BE APPLIED AS NECESSARY UNTIL VEGETATION IS ESTABLISHED OR UNTIL THE WORK IS ACCEPTED AS COMPLETE.
- 7. THE CONTRACTOR SHALL BE PAID FOR UNCLASSIFIED EXCAVATION ON THE BASIS OF PLAN QUANTITY.
- 8. SILT FROM DISCHARGE SHALL BE MANAGED, REMOVED & DISPOSED OF AS REQUIRED BY THE STORMWATER MANAGEMENT PLAN.
- 9. STREET WASH DOWN SHALL BE INCLUDED IN THE PRICE FOR

UNCLASSIFIED EXCAVATION.

- 10. PRICE TO INCLUDE ALL COSTS, LABOR, AND MATERIALS REQUIRED FOR A COMPLETE INSTALLATION. SEE DETAIL 1 ON SHEET 26.
- 11. PAY ITEM REFERS TO EMBANKMENT FILL BEHIND REINFORCED FILL IN REINFORCED SOIL SLOPE (RSS) WALL AND FILL ABOVE RSS WALL TYING INTO EXISTING GROUND. SEE DETAIL 1 ON SHEET 26.
- 12. REFER TO SHEET 27, NOTE 2.4 FOR REINFORCED FILL MATERIAL DEFINITION.
- 13. NOT USED
- 14. PAY ITEM IS FOR DIVERSION OF WATER THROUGH CONSTRUCTION AREA. TO INCLUDE THE COST OF FLEXIBLE PIPES, INLETS, OUTLETS, AND DIVERSION DIKES. SEE ODOT ROADWAY DESIGN STANDARD DETAIL SD-0-0 (R-12).
- 15. PAY ITEM INCLUDES ROCK, WIRE MESH, AND ALL OTHER INCIDENTALS REQUIRED FOR CONSTRUCTION AND REMOVAL. SEE DETAIL 3 ON SHEET 26.
- 16. THESE PAY ITEMS ARE FOR THE ROCK TOE REVETMENT. SEE DETAIL ON SHEET 30 FOR ROCK TOE REVETMENT.
- 17. THESE PAY ITEMS ARE FOR THE REINFORCED SOIL SLOPE (RSS) RETAINING WALL.
- 18. THESE PAY ITEMS ARE FOR THE CROSS VANES. SEE DETAIL ON SHEET 30.
- 19. THESE PAY ITEMS ARE FOR CONSTRUCTION ACCESS AND ANY TEMPORARY WORK PLATFORMS AND SHALL INCLUDE REMOVAL AFTER CONSTRUCTION.
- 20. PAY ITEM TO INCLUDE TRENCH EXCAVATION, CONNECTION TO EXISTING PIPES, FITTINGS, AND ALL OTHER INCIDENTALS FOR INSTALL.
- 21. PAY ITEMS ARE FOR REESTABLISHING EXISTING DRAINAGE CONDUIT FROM PROPERTIES ALONG THE EAST EMBANKMENT WITHIN THE LIMITS OF THE WORK AREA.
- 22. PAY ITEM IS FOR THE REMOVAL OF DEBRIS IN WORK AREA.
- 23. PAY ITEM TO INCLUDE TRAFFIC CONTROL PLAN PROVIDED BY CONTRACTOR.
- 24. CONTRACTOR SHALL INCLUDE THE COST OF THE FOLLOWING ITEMS IN URBAN R/W RESTORATION:
- 24.1. REPAIR OF IRRIGATION SYSTEMS
- 24.2. ANY ITEMS DAMAGED DURING CONSTRUCTION. REPAIRED ITEMS SHALL BE TO THE SATISFACTION OF THE ENGINEER.
- 24.3. THE CONTRACTOR SHALL INCLUDE THE COST OF FLEXAMAT SHOWN ON SHEET 14 WITH THIS PAY ITEM.
- 25. PAY ITEM SHALL INCLUDE ALL NECESSARY PUMPING OF POOLED WATER TO ESTABLISH WORK AREAS FOR INSTALLATION OF RSS RETAINING WALL.
- 26. LIVES STAKES SHALL BE INSTALLED ACCORDING TO DETAIL 5 ON SHEET 26 WITHIN THE EXTENTS OF THE ROCK TOE REVETMENT AS INDICATED ON PLANS.
- 27. PAY ITEM INCLUDES RIPRAP PLACEMENT ON END SECTIONS OF RSS WALL AS DESCRIBED ON THE P&P SHEETS.

ITEM	PAY QUANTITIES DESCRIPTION	PAY ITEM NOTES	UNITS	QUANTITY
201(A)1200	CLEARING AND GRUBBING	1	AC	2.5
202(A)2200	UNCLASSIFIED EXCAVATION	7,9	CY	11,807.1
202(F)2700	EMBANKMENTS (FILL)	11	CY	11,362.7
205(A)6210	TYPE A-SALVAGED TOPSOIL	N/A	CY	246.9
220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	N/A	EA	1.0
221(A)2200	TEMPORARY SLOPE DRAIN	14	LF	625.0
221(B)2300	TEMPORARY SILT FENCE	4,8	LF	210.0
221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	15	CY	109.7
228 5100	EROSION CONTROL BLANKET (700 SERIES COIR)	16	SY	775.0
230(A)7200	SOLID SLAB SODDING	5,6	SY	1,860.0
240(A)	SELECTIVE TREE & SHRUB REMOVAL	2	AC	2.5
242 4101	STABILIZED CONSTRUCTION EXIT	N/A	EA	1.0
303(G)1510	AGGREGATE BASE TYPE D (NO. 57 STONE) (WORK PLATFORM 8" LAYER)	19	CY	485.9
303(G)1510	AGGREGATE BASE TYPE D (NO. 57 STONE) (FILL FOR RSS WALL)	17	CY	2,700.0
325 0100	SEPARATOR FABRIC (WORK PLATFORM)	19	SY	925.9
514(I)6000	SHEET PILING, DRIVEN (CROSS VANE)	18	SY	66.7
601(A)1100	TYPE I-A PLAIN RIPRAP (CROSS VANE)	18	TON	35.8
601(A)1110	TYPE I PLAIN RIPRAP (ROCK TOE REVETMENT)	16,27	TON	1,378.4
602(A)2200	GABIONS (CROSS VANE)	18	CY	4.0
612(A)3200	MANHOLES ADJUST TO GRADE	N/A	EA	1.0
613(B)5500	12" CORR. GALV. STEEL PIPE	20,21	LF	280.0
613(L)6700	12" PREFAB. CULVERT END SEC., ROUND	21	EA	14.0
613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	21	CY	70.0
619(A)6210	REMOVAL OF STRUCTURES & OBSTRUCTIONS	22	CY	1,000.0
619(B)6352	REMOVAL OF FENCE	N/A	LF	1,200.0
619(B)6440	REMOVAL OF EXISTING PIPE	21	LF	100.0
619(B)6452	REMOVAL OF EXISTING RETAINING WALL	N/A	LF	80.0
624 3110	(PL) WOOD PRIVACY FENCE (6-FT STOCKADE)	N/A	LF	1,275.0
641 2100	MOBILIZATION	23	EA	1.0
642(A)3200	CONSTRUCTION STAKING LEVEL I	3	ACRE	2.5
880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	N/A	SD	360.0
SPECIAL	TREES - LIVE STAKING (3/4 TO 1 1/2 DIA.)	16,26	EA	1,395.0
SPECIAL	NATIVE SHRUB & GRASS PLANTING	16	SY	516.7
SPECIAL	REINFORCED SOIL SLOPE (RSS) RETAINING WALL	10,17	SF	22,407.0
SPECIAL	REINFORCED FILL (FOR RSS WALL)	12,17	CY	9,034.5
SPECIAL	URBAN R/W RESTORATION	24	ACRE	2.5
SPECIAL	PUMPING	25	DAY	35.0

NOTES IMHOFF CREEK BANK STABILIZATION CITY OF NORMAN PLANS AND ESTIMATES PREPARED BY: MESHEK & ASSOCIATES, L.L.C. 1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392–5620 2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594–0127

PAY ITEM AND CONSTRUCTION

REVISION BY DATE DRAWN CGH 12/2023

DESIGNED HCW 12/2023

SURVEY MR 7/2021

C.A. 1487 EXPIRES 6/30/25

SHEET: 2 OF 30

4 M:\City_of_Norman\15N0R01_Lower_lı

STORM WATER MANAGEMENT PLAN

SITE DESCRIPTION PROJECT LIMITS: EAST AND WEST EMBANKMENT OF IMHOFF CREEK. LOCATED SOUTH OF IMHOFF ROAD AND NORTH OF HIGHWAY 9. **SOIL STABILIZATION PRACTICES:** _ TEMPORARY SEEDING X PERMANENT SODDING, SPRIGGING OR SEEDING PROJECT DESCRIPTION: APPLICATION FOR A NATIONWIDE PERMIT AND THE **VEGETATIVE MULCHING** DEVELOPMENT OF CONSTRUCTION PLANS TO INSTALL WIRE FORMED RETAINING WALL X SOIL RETENTION BLANKET WITH NATURAL VEGETATED FACE TO ADDRESS BANK EROSION OF IMHOFF CREEK AND X PRESERVATION OF EXISTING VEGETATION FUTURE LOSS OF PROPERTY. NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES: OR AS DIRECTED BY THE ENGINEER. 1. TEMPORARY EROSION CONTROL 2. PERMANENT EROSION CONTROL STRUCTURAL PRACTICES: X STABILIZED CONSTRUCTION EXIT TEMPORARY SILT FENCE X TEMPORARY SILT DIKES TEMPORARY FIBER LOG DIVERSION, INTERCEPTOR OR PERIMETER DIKES DIVERSION. INTERCEPTOR OR PERIMETER SWALES PORT SILT LOAM, HYDROLOGIC GROUP B X ROCK FILTER DAMS TEMPORARY SLOPE DRAIN TOTAL AREA OF THE CONSTRUCTION SITE: 2.85 ACRES PAVED DITCH W/ DITCH LINER PROTECTION TEMPORARY DIVERSION CHANNELS ESTIMATED AREA TO BE DISTURBED: 2.5 ACRES TEMPORARY SEDIMENT BASINS OFFSITE AREA TO BE DISTURBED: TEMPORARY SEDIMENT TRAPS (FOR CONTRACTOR USE) X TEMPORARY SEDIMENT FILTERS TOTAL IMPERVIOUS AREA X TEMPORARY SEDIMENT REMOVAL PRE-CONSTRUCTION: 0 ACRES X RIP RAP TOTAL IMPERVIOUS AREA INLET SEDIMENT FILTER POST-CONSTRUCTION: 0 ACRES TEMPORARY BRUSH SEDIMENT BARRIERS POST-CONSTRUCTION RUNOFF SANDBAG BERMS COEFFICIENT OF THE SITE: N/A X TEMPORARY STREAM CROSSINGS LATITUDE & LONGITUDE OF CENTER OF PROJECT: <u>35°11'16.42"N</u>, 97°27'30.27"W PROJECT WILL DISCHARGE TO: OFFSITE VEHICLE TRACKING: CANADIAN RIVER NAME OF RECEIVING WATERS: __X__ HAUL ROADS DAMPENED FOR DUST CONTROL NO X __X__ LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN SENSITIVE WATERS OR WATERSHEDS: X EXCESS DIRT ON ROAD REMOVED DAILY NO X 303 IMPAIRED WATERS: IF YES, LIST IMPAIRMENT: NOTES: NO X YES LOCATED IN A TMDL: NO X LAKE THUNDERBIRD TMDL: MS4 ENTITY NO NEIGHBORHOOD STORM DRAINS, CITY OF NORMAN IF YES, LOCATION: NOTE: THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS

EROSION AND SEDIMENT CONTROLS

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), THE NOTICE OF INTENT, & THE NOTICE OF TERMINATION FOR THIS PROJECT. THE SWPPP IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED PRIOR TO MOBILIZATION, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITHTHE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2009 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

103.05 BONDING REQUIREMENTS

104.10 FINAL CLEANING UP

104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK

104.13 ENVIRONMENTAL PROTECTION

106.08 STORAGE AND HANDLING OF MATERIAL

107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED

107.20 STORM WATER MANAGEMENT

220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL

221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES

FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA."

ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.


 1 1							
SWMP							
IMHOFF CREEK BANK STABILIZATION							
CI ⁻	TY (OF N	IORMAN				
PLANS AND ESTIMATES MESHEK 1437 S. BOULDER AVENU 2000 N. CLASSEN BLVD.	& A	SS0 E 1550 T	CIATES, ULSA, OK 74119 (918)392	-5620		
REVISION	BY	DATE	DRAWN	CGH	12/2023		
			DESIGNED	HCW	12/2023		
			SURVEY	MR	7/2021		
			C.A. 1487 EXF	PIRES 6	6/30/25		
			SHEET:	3 OF	30		

PRINT DATE: 3/22/24 M:\

REVISED 08 / 18 / 2017

FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION

CONTROL SUMMARIES, PAY ITEMS, & NOTES.



SOLID SLAB SOD

TEMPORARY SILT FENCE

SOIL STABILIZATION PRACTICES

- 1. ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OR REPLACEMENT OF ALL EROSION CONTROL DEVICES DAMAGED DUE TO CONSTRUCTION OR INCLEMENT WEATHER CONDITIONS.
- 3. A COPY OF THE EROSION CONTROL SITE PLAN MUST BE ON SITE AT ALL TIMES AND MADE AVAILABLE TO THE INSPECTOR UPON REQUEST.
- 4. PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED.

SOD AND SEED

- 1. THE CONTRACTOR SHALL ESTABLISH A VEGETATIVE COVER OVER ALL SOIL SURFACES DISTURBED DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ASSURING ALL VEGETATION COVERS ARE WELL ESTABLISHED PRIOR TO FINAL COMPLETION OF PROJECT.
- 2. THE CONTRACTOR SHALL PROVIDE A 3' WIDE SOD STRIP AT THE EDGE OF ALL NEW PAVEMENT SURFACES AND AT THE TOP OF THE GABION WALL IF NOT DEPICTED OTHERWISE ON PLANS.





EROSION CONTROL


IMHOFF CREEK BANK STABILIZATION


CITY OF NORMAN


REVISION	BY	DATE	DRAWN	CGH	12/2023	
			DESIGNED	HCW	12/2023	
			SURVEY	MR	7/2021	
			C.A. 1487 EXPIRES 6/30/25			
		:				
			SHEET: 4	4 Of	- 30	




















L1		167.26	N1° 47′ 47.69″W	N: 674217.38 E: 2130062.48	10+00.00
C1	100.00	6.79	N0° 08' 55.21"E	N: 674384.56 E: 2130057.24	11+67.26
L2		63.70	N2° 05' 38.12"E	N: 674391.35 E: 2130057.25	11+74.06
C2	176.24	25.84	N2° 06' 24.43"W	N: 674455.01 E: 2130059.58	12+37.76
L3		132.87	N6° 18' 26.97"W	N: 674480.81 E: 2130058.63	12+63.60
С3	100.00	13.29	N10° 06' 57.38"W	N: 674612.88 E: 2130044.04	13+96.47
L4		0.20	N13° 55′ 27.80″W	N: 674625.96 E: 2130041.70	14+09.77
C4	36.72	20.82	N2° 19' 12.73"E	N: 674626.15 E: 2130041.65	14+09.96
L5		36.53	N18° 33' 53.25"E	N: 674646.68 E: 2130042.49	14+30.78
C5	36.72	5.80	N14° 02' 29.28"E	N: 674681.30 E: 2130054.12	14+67.31
L6		12.23	N9° 31' 05.30"E	N: 674686.92 E: 2130055.52	14+73.11
C6	35.30	20.88	N7° 25′ 26.83″W	N: 674698.98 E: 2130057.54	14+85.33
L7		26.02	N24°21′58.95″W	N: 674719.38 E: 2130054.88	15+06.21
C7	35.30	26.40	N2° 56′ 38.36″W	N: 674743.09 E: 2130044.15	15+32.24
L8		97.10	N18°28′42.24″E	N: 674768.84 E: 2130042.82	15+58.64
C8	35.30	8.15	N11° 51' 48.64"E	N: 674860.94 E: 2130073.60	16+55.74
L9		59.38	N5° 14' 55.04"E	N: 674868.90 E: 2130075.27	16+63.89
С9	35.30	30.67	N19° 38' 14.76"W	N: 674928.03 E: 2130080.70	17+23.27
L10		61.55	N44° 31′ 24.56″W	N: 674956.01 E: 2130070.72	17+53.94
C10	35.30	20.20	N28° 08' 01.83"W	N: 674999.90 E: 2130027.55	18+15.50

PR. CRL

Number Radius Length Line/Chord Direction Start Coord. Start Station


PR. CRL								
Number	Radius	Length	Line/Chord Direction	Start Coord.	Start Station			
L11		36.47	N11° 44′ 39.09"W	N: 675017.47 E: 2130018.16	18+35.69			
C11	35.30	7.02	N6° 02' 55.25"W	N: 675053.18 E: 2130010.74	18+72.17			
L12		36.26	N0° 21' 11.41"W	N: 675060.15 E: 2130010.00	18+79.18			
C12	35.30	20.49	N16° 58' 41.89"W	N: 675096.41 E: 2130009.77	19+15.45			
L13		13.97	N33° 36' 12.36"W	N: 675115.73 E: 2130003.87	19+35.93			
C13	35.30	11.51	N42° 56' 46.31"W	N: 675127.37 E: 2129996.14	19+49.91			
L14		19.96	N52° 17' 20.27"W	N: 675135.76 E: 2129988.33	19+61.42			
C14	18.90	23.15	N17° 12′ 32.29"W	N: 675147.96 E: 2129972.55	19+81.38			
L15		17.21	N17° 52' 15.69"E	N: 675168.72 E: 2129966.12	20+04.52			
C15	18.90	6.44	N27° 38' 04.15"E	N: 675185.10 E: 2129971.40	20+21.73			
L16		39.88	N37° 23' 52.62"E	N: 675190.78 E: 2129974.37	20+28.17			
C16	18.90	10.11	N52° 43' 12.26"E	N: 675222.46 E: 2129998.59	20+68.06			
L17		175.70	N68° 02' 31.90"E	N: 675228.51 E: 2130006.54	20+78.17			
C17	58.88	15.20	N75° 26' 21.09"E	N: 675294.21 E: 2130169.50	22+53.86			
L24		26.15	N82° 50′ 10.28″E	N: 675298.02 E: 2130184.17	22+69.07			
C23	112.44	41.63	N72° 13' 44.42"E	N: 675301.28 E: 2130210.12	22+95.22			
L25		48.67	N61° 37' 18.55"E	N: 675313.92 E: 2130249.54	23+36.85			
C24	164.85	69.84	N73° 45' 32.03"E	N: 675337.05 E: 2130292.36	23+85.52			
L23		0.88	N85° 53' 45.52"E	N: 675356.44 E: 2130358.91	24+55.36			
C18	34.17	22.74	N66° 50′ 02.11″E	N: 675356.50 E: 2130359.79	24+56.24			


PR. CRL								
Number	Radius	Length	Line/Chord Direction	Start Coord.	Start Station			
L22		103.40	N47° 46' 18.70"E	N: 675365.28 E: 2130380.31	24+78.98			
L26		74.48	N48° 49' 13.61"E	N: 675434.77 E: 2130456.87	25+82.38			
C25	130.19	28.63	N55° 07' 09.66"E	N: 675483.81 E: 2130512.93	26+56.86			
L27		65.50	N61° 25' 05.71"E	N: 675500.15 E: 2130536.37	26+85.48			
C19	129.26	152.28	N27° 40' 05.25"E	N: 675531.49 E: 2130593.89	27+50.99			
L20		22.77	N6° 04' 55.21"W	N: 675658.69 E: 2130660.58	29+03.27			
C20	325.12	30.52	N8° 46' 16.74"W	N: 675681.33 E: 2130658.17	29+26.04			
L21		87.41	N11°27′38.28"W	N: 675711.48 E: 2130653.52	29+56.56			
C21	18.90	1.53	N13° 46' 51.79"W	N: 675797.15 E: 2130636.15	30+43.97			
L18		55.70	N16° 06' 05.31"W	N: 675798.64 E: 2130635.78	30+45.50			
C22	18.90	2.19	N19° 25′ 20.92″W	N: 675852.16 E: 2130620.33	31+01.20			
L19		89.97	N22° 44′ 36.54″W	N: 675854.22 E: 2130619.61	31+03.39			


PR CRL DATA IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

2000 N. CLASSEN BEVD., E230 OKLAHOMA CITT, OK 75106 (403)394-0127							
REVISION	BY	DATE	DRAWN	CGH 12/202			
			DESIGNED	HCW 12/202			
			SURVEY	MR 7/2021			
			C.A. 1487 EXF	PIRES 6/30/25			
			SHEET: 1	3 OF 30			
			JIILLI. I	5 01 50			








EMBANKMENT FILL (NATIVE SOIL)
REINFORCED FILL
ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (1)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

BY	DATE	DRAWN		12/2023			
		DESIGNED	HCW	12/2023			
		SURVEY	MR	7/2021			
		C.A. 1487 EXPIRES 6/30/25					
		SHEET: 1	5 OF	30			
	BY	BY DATE	DESIGNED SURVEY C.A. 1487 EXF	DESIGNED HCW SURVEY MR			





EMBANKMENT FILL (NATIVE SOIL)

REINFORCED FILL


ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (2)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

REVISION	BY	DATE	DRAWN	CGH	12/2023	
			DESIGNED	1	12/2023	
			SURVEY	MR	7/2021	
			C.A. 1487 EXPIRES 6/30/25			
		:	SHEET: 1	6 OF	- 30	





EMBANKMENT FILL (NATIVE SOIL)

REINFORCED FILL


ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (3)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

	REVISION	BY	DATE	DRAWN	CGH	12/2023		
				DESIGNED	HCW	12/2023		
				SURVEY	MR	7/2021		
				C.A. 1487 EXF	C.A. 1487 EXPIRES 6/30/25			
-				SHEET: 1	7 OF	30		
					·			





EMBANKMENT FILL (NATIVE SOIL)

REINFORCED FILL


ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (4)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

REVISION	BY	DATE	DRAWN	CGH	12/2023
			DESIGNED	HCW	12/2023
			SURVEY	MR	7/2021
			C.A. 1487 EXF	PIRES 6	5/30/25
			SHEET: 1	8 OF	30





	EMBANKMENT FILL (NATIVE SOIL)
	REINFORCED FILL
	ODOT TYPE 'D' AGGREGATE

SECTION SHEET - (5)

IMHOFF CREEK BANK STABILIZATION


CITY OF NORMAN


PLANS AND ESTIMATES PREPARED BY:

MESHEK & ASSOCIATES, L.L.C.

1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392-5620
2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594-0127

REVISION BY DATE DRAWN CGH 12/2023
DESIGNED HCW 12/2023
SURVEY MR 7/2021
C.A. 1487 EXPIRES 6/30/25
SHEET: 19 OF 30





EMBANKMENT FILL (NATIVE SOIL)

REINFORCED FILL


ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (6)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

REVISIO	N BY	′ D,	ATE	DRAV	۷N		CGH	12	/20)23
				DESI	GNED		HCW	12	/20)23
				SUR	/EY		MR	7	/20	21
				C.A.	1487	EXPI	RES (6/3	30/2	25
				SHE	ET:	20) 0	F	30	
· · · · · · · · · · · · · · · · · · ·							·			






EMBANKMENT FILL (NATIVE SOIL)
REINFORCED FILL
ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (7)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

REVISION	BY	DATE	DRAWN		12/2023
			DESIGNED	HCW	12/2023
			SURVEY	MR	7/2021
			C.A. 1487 EXF	PIRES 6	5/30/25
			SHEET: 2	21 OF	30






EMBANKMENT FILL (NATIVE SOIL)
REINFORCED FILL
ODOT TYPE 'D' AGGREGATE


SECTION SHEET - (8)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

REVISION	BY	DATE	DRAWN	CGH	12/2023
			DESIGNED	HCW	12/2023
			SURVEY	MR	7/2021
			C.A. 1487 EXF	PIRES 6	5/30/25
			SHEET: 2	2 OF	- 30
			2		- 50





EMBANKMENT FILL (NATIVE SOIL)
REINFORCED FILL
ODOT TYPE 'D' AGGREGATE

SECTION SHEET - (9)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

PLANS AND ESTIMATES PREPARED BY:

MESHEK & ASSOCIATES, L.L.C.

1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392-5620

2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594-0127


REVISION BY DATE DRAWN CGH 12/2023


DESIGNED HCW 12/2023


SURVEY MR 7/2021

C.A. 1487 EXPIRES 6/30/25

SHEET: 23 OF 30







SECTION SHEET - (10)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN

PLANS AND ESTIMATES PREPARED BY:

MESHEK & ASSOCIATES, L.L.C.

1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392-5620

2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594-0127


REVISION BY DATE DRAWN CGH 12/2023


DESIGNED HCW 12/2023

SURVEY MR 7/2021

C.A. 1487 EXPIRES 6/30/25

SHEET: 24 OF 30





EMBANKMENT FILL (NATIVE SOIL)
REINFORCED FILL
ODOT TYPE 'D' AGGREGATE

SECTION SHEET - (11)

IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN


PLANS AND ESTIMATES PREPARED BY:


MESHEK & ASSOCIATES, L.L.C.

1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392-5620
2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594-0127

BY DATE DRAWN CGH 12/2023 REVISION


DESIGNED HCW 12/2023 SURVEY MR 7/2021 C.A. 1487 EXPIRES 6/30/25 SHEET: 25 OF 30





* SEE PLAN & PROFILE SHEETS FOR LENGTH

2 WALL TIE-IN DETAIL SCALE: NONE STA. 31+05




6' PRIVACY FENCE SCALE: NONE

MESHEK DETAILS IMHOFF CREEK BANK STABILIZATION

CITY OF NORMAN PLANS AND ESTIMATES PREPARED BY:


MESHEK & ASSOCIATES, L.L.C. 1437 S. BOULDER AVENUE, SUITE 1550 TULSA, OK 74119 (918)392-5620 2000 N. CLASSEN BLVD., E250 OKLAHOMA CITY, OK 73106 (405)594-0127

BY DATE DRAWN CGH 12/202 REVISION HCW 12/2023 DESIGNED MR 7/2021 SURVEY C.A. 1487 EXPIRES 6/30/25 SHEET: 26 OF 30



ROCK FILTER DAM

SCALE: NONE



LIVE STAKING NOTES:

1. AVOID PLANTING DURING SUMMER MONTHS

2. STAKES ARE TO BE PLANTED AFTER THE RIPRAP IS PLACED.

3. LIVE STAKES ARE TO BE INSTALLED IN ROCK TOE REVETMENT 2' ABOVE CHANNEL BASE FLOW.

4. INSTALL <u>3 STAKES PER LINEAR FOOT</u> ALONG ROCK TOE REVETMENT. 5. USE HEALTHY, STRAIGHT AND LIVE WOOD AT LEAST 1 YEAR OLD.

6. MAKE CLEAN CUTS AND DO NOT DAMAGE STAKES OR SPLIT ENDS DURING INSTALLATION; USE AN IRON BAR TO MAKE A PILOT HOLE PRIOR TO DRIVING THE STAKE. DRIVE THE STAKE USING A RUBBER MALLET TO REDUCE SPLITTING DAMAGE TO THE STAKE.

7. SOAK CUTTINGS FOR AT LEAST 24 HOURS PRIOR TO INSTALLATION.

(5-7 DAYS RECOMMENDED) 8. KEEP STAKES MOIST AND COVERED AT ALL TIMES: FROM HARVEST, THROUGH STORAGE AND TRANSPORT, TO INSTALLATION.

9. TAMP THE SOIL AROUND THE STAKE.

10. 2 TO 5 BUDS SCARS SHALL BE ABOVE GROUND.

11. CONTACT MISSOURI DEPARTMENT OF CONSERVATION (573-674-3229) FOR PURCHASING LIVE PLANTING STAKES. OTHER SOURCES ARE ACCEPTABLE.

12. CONTRACTOR MUST PROVIDE PROOF OF PURCHASE AND SPECIES TYPE

PURCHASED TO THE ENGINEER AND CITY. 13. SPECIES TO BE SANDBAR WILLOW (SALIX INTERIOR ROWLEE). ALTERNATIVES

INCLUDE BLACK WILLOW AND WEEPING WILLOW.

- 1.1 DEFINITIONS
- A. MINIMUM AVERAGE ROLL VALUE (MARV): PROPERTY VALUE CALCULATED AS TYPICAL MINUS TWO STANDARD DEVIATIONS. STATISTICALLY, IT YIELDS A 97.7 PERCENT DEGREE OF CONFIDENCE THAT ANY SAMPLE TAKEN DURING QUALITY ASSURANCE TESTING WILL EXCEED VALUE REPORTED.
- B. <u>CURRENT CERTIFICATION:</u> A CERTIFICATION DATED WITHIN THE LAST CALENDAR YEAR, ATTESTED BY A PERSON HAVING LEGAL AUTHORITY FOR THE MANUFACTURER.
- C. LONG-TERM DESIGN STRENGTH (LTDS)
- 1.2 THE OVERALL STABILITY OF THE RETAINING WALL SYSTEM IS BASED ON THE STRUCTURAL INTEGRITY OF THE GEOGRID REINFORCEMENT. PROPERTY OWNERS SHOULD BE MADE AWARE THAT DISTURBANCE OF THE GEOGRID REINFORCEMENT WILL IMPACT THE STABILITY OF THE WALL.
- 1.3 SUBMITTALS: PROVIDE SUBMITTALS TO ENGINEER ON THE SCHEDULE INDICATED FOR EACH ITEM FOR APPROVAL.
- A. SUBMIT QUALITY CONTROL ITEMS WITHIN 15 BUSINESS DAYS FOR APPROVAL AS FOLLOWS:
- 1. PROVIDE CURRENT CERTIFICATION THAT EACH GEOSYNTHETIC MATERIAL MEETS MARV REQUIREMENTS OF THE SPECIFICATION AS EVALUATED UNDER THE MANUFACTURER'S QUALITY CONTROL PROGRAM.
- a. EACH CERTIFICATION SHALL INCLUDE:
- THE NAME OF THE MANUFACTURER
- PRODUCT NAME
- STYLE NUMBER
 BATCH NUMBER
- CHEMICAL COMPOSITION OF THE FILAMENTS OR YARNS
- PROVIDE TO THE WALL ENGINEER THE MANUFACTURER'S CURRENT QUALITY CONTROL PLAN CERTIFICATIONS FOR A2LA, GAI-LAP, OR ISO 9001.
- B. PROVIDE CURRENT CERTIFICATION OF MILL REPORTS FOR STEEL PRODUCTS.
- C. PROVIDE CURRENT CERTIFICATION OF GALVANIZATION PRODUCTS AND PROCEDURES.
- 1.4 QUALITY CONTROL
- A. GEOSYNTHETIC MANUFACTURING QUALITY CONTROL: CERTIFY THAT GEOSYNTHETIC MATERIAL TESTING PERFORMED BY A LABORATORY ACCREDITED BY GAI-LAP OR A2LA FOR REQUIRED TESTS.
- B. CERTIFY THAT ULTRAVIOLET STABILITY VERIFIED BY AN INDEPENDENT LABORATORY ON THE GEOSYNTHETIC OR A GEOSYNTHETIC OF SIMILAR CONSTRUCTION AND YARN TYPE.
- C. TEST STRIP:
 - LABORATORIES CANNOT EASILY TEST THE REINFORCING FILL PER TRADITIONAL METHODS FOR MAXIMUM DENSITY. CONTRACTOR SHALL WORK WITH ENGINEER AND GEOTECHNICAL TECHNICIAN TO CONSTRUCT A TEST STRIP TO DETERMINE THE TARGET MAXIMUM DRY DENSITY FOR COMPACTION TESTING.
 - a. PLACE A LIFT OF FILL IN TEST STRIP AREA (MAY BE PRODUCTION AREA). TEST AREAS SHALL BE COMPACTED USING COMPACTION EQUIPMENT INTENDED TO BE USED DURING PRODUCTION.
 - 2. PREPARE AND TEST UP TO FOUR LOCATIONS IN TEST STRIP AREA TO DETERMINE MAXIMUM DRY DENSITY USING WATER REPLACEMENT METHOD. CONTRACTOR SHALL ALSO PROVIDE CONSTRUCTION EQUIPMENT TO BE USED TO ASSIST GEOTECHNICAL TECHICIAN IN RUNNING PLATE LOAD TESTS (ASTM D 1196) AT DESIGNATED LOCATIONS IN THE TEST STRIP AREAS. THE REQUIRED ALLOWABLE BEARING CAPACITY SHALL BE A MINIMUM 3,000 PSF WITH A FACTOR OF SAFETY = 2.
 - 3. ADDITIONALLY, IN-PLACE DENSITY SHALL BE DETERMINED USING NUCLEAR GAUGE PLACED ON BACKSCATTER SETTING IN NO LESS THAN FIVE ADDITIONAL LOCATIONS.
 - 4. THE AVERAGE IN-PLACE DENSITY RECORED IN STEPS C.1.a.1 AND C.1.a.2 SHALL BE THE LIFT'S IN-PLACE DESITY
 - b. COMPACT THE TEST STRIP AGAIN WITH 2 PASSES OF A COMPACTOR AND RETEST AS IN STEP C.1.a.
 - c. RECORD THE VALUES AND REPEAT STEP b UNTIL ADDITIONAL PASSES DO NOT INCREASE THE DRY DENSITY. THE MINIMUM DRY DENSITY DETERMINED BY THE TEST STRIP SHALL BE THE TARGET DENSITY FOR COMPACTION TESTING. THE MINIMUM NUMBER OF PASSES BY COMPACTION EQUIPMENT TO MEET THIS DENSITY SHALL BE USED AS A GUIDELINE FOR SUCCESSIVE FILL PLACEMENT.
- D. COMPACTIVE EFFORT OF SUCCESSIVE LIFTS SHALL, AT A MINIMUM, EQUAL THE NUMBER OF PASSES DETERMINED DURING THE TEST STRIP. ONCE INSTALLED, THE ONSITE ENGINEERING REPRESENTATIVE SHALL PERFORM A MINIMUM OF 10 IN-PLACE DENSITY TESTS (RANDOMLY LOCATED) USING A NUCLEAR GAUGE PLACED ON BACKSCATTER SETTING. THE AVERAGE OF THE 10 READINGS WILL BE IN-PLACE DENSITY OF THE COMPACTED LIFT. IF IN-PLACE DENSITY DOES NOT MEET OR EXCEED THAT ESTABLISHED DURING DEVELOPMENT OF ROLL PATTERN, ADDITIONAL COMPACTIVE EFFORT WILL BE REQUIRED. IF AFTER 4 ADDITIONAL PASSES, THE COMPACTED FILL DOES NOT MEET THE DENSITY DETERMINED IN THE TEST STRIP, THE ENGINEER SHALL BE NOTIFIED TO DETERMINE WHETHER A NEW TEST STRIP/ROLL PATTERN NEEDS TO BE PERFORMED/DEVELOPED.

1.5 QUALITY ASSURANCE

- A. MANUFACTURER QUALIFICATIONS: THE GEOSYNTHETIC MANUFACTURER SHALL HAVE ONE OF THE FOLLOWING CURRENT CREDENTIALS:
- 1. GEOSYNTHETIC ACCREDITATION INSTITUTE (GAI) LABORATORY ACCREDITATION PROGRAM (LAP)
- 2. AMERICAN ASSOCIATION FOR LABORATORY ACCREDITATION (A2LA)
- 3. ISO 9001 QUALITY MANAGEMENT SYSTEM
- B. A GAI-LAP ACCREDITED LABORATORY SHALL PERFORM ROUTINE TESTS OF THE GEOSYNTHETIC MANUFACTURER'S PRODUCTS.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. GEOSYNTHETIC LABELING, SHIPMENT, AND STORAGE SHALL FOLLOW ASTM D4873. PRODUCT LABELS SHALL CLEARLY SHOW THE MANUFACTURER OR SUPPLIER NAME, STYLE NAME, AND ROLL NUMBER. GEOGRID SHALL BE MARKED WITH PRODUCT TYPE AND TENSILE STRENGTH ORIENTATION CONTINUOUSLY ALONG ENTIRE ROLL EDGE.
- MARKED WITH PRODUCT TYPE AND TENSILE STRENGTH ORIENTATION CONTINUOUSLY ALONG ENTIRE ROLL EDGE.

 B. WRAP EACH GEOSYNTHETIC ROLL WITH A MATERIAL THAT WILL PROTECT THE GEOSYNTHETIC FROM DAMAGE DUE
 TO SHIPMENT, WATER, SUNLIGHT, AND CONTAMINANTS.
- C. DURING STORAGE, ELEVATE GEOSYNTHETIC ROLLS OFF THE GROUND AND ADEQUATELY COVERED TO PROTECT THEM FROM SITE CONSTRUCTION DAMAGE, PRECIPITATION, SUNLIGHT, CHEMICALS, FLAMES, SPARKS, EXCESS TEMPERATURES, AND ANY OTHER ENVIRONMENTAL CONDITIONS THAT MAY DAMAGE THE PHYSICAL PROPERTY VALUES OF THE GEOSYNTHETIC.

PART 2 PRODUCTS

2.1 GEOSYNTHETIC MATERIAL

1-706-693-2083, FAX

WWW.MIRAFI.COM

A. TENCATE GEOSYNTHETICS AMERICAS 365 SOUTH HOLLAND DRIVE PENDERDRASS, GA, USA 30567 1-800-685-9990 1-706-693-2226

- B. MATERIALS
- 1. APPROVED GEOGRID IS TENCATE MIRAGRID 24XT AND MIRAGRID 10XT AS INDICATED ON THE PLANS.
- 2. APPROVED GEOTEXTILE FACING IS MIRAMESH.
- 3. MANUFACTURER SHALL LABEL APPROVED GEOGRIDS WITH PRODUCT TYPE. APPROVED GEOGRID MANUFACTURER SHALL BE TESTED BY A GAI LABORATORY AND SHALL BE MADE IN NORTH AMERICA.
- 4. GEOSYNTHETICS SHALL RETAIN A MINIMUM OF 70% OF THE ULTIMATE TENSILE STRENGTH PER ASTM D4595 AFTER UV EXPOSURE.
- 2.2 ULTRA-VIOLET LIGHT (UV) OR SUNLIGHT BARRIER
- A. UV BARRIER SHALL CONSIST OF PLANTABLE FILL WITHIN THE EXPOSED PORTION OF THE WRAP FACE TO ALLOW PERMANENT VEGETATION.
- B. PERMANENT VEGETATION OF THE STEEPENED SLOPE SHALL BE SET WITH APPROVED HYDROSEED MIXTURE AND METHOD.

2.3 WELDED WIRE FACING:

- WIRE FACING UNITS SHALL BE WIRE WALL SYSTEM AS MANUFACTURED BY TENCATE, WITH ASTM A-82 WIRE.
 THE MESH CONFIGURATION SHALL BE AS SHOWN ON THE CONSTRUCTION DRAWINGS. THE MESH SHALL BE
 FORMED BY WELDING THE WIRES IN ACCORDANCE WITH ASTM A-185 AND BENT AS NECESSARY TO ACHIEVE
 THE BASKET SHAPE OF THE UNITS.
- 2. BRACING COMPONENTS SHALL BE 0.24 INCH DIAMETER ELECTROPLATED WIRE LOCKING TAIL STRUTS AS PER CONSTRUCITON DRAWINGS AND DETAILS.

2.4 REINFORCED FILL MATERIAL

1. ALL RETAINING WALL BACKFILL AND EMBANKMENT FILLS SHALL BE BENCHED INTO EXISTING SLOPE.

REINFORCED FILL SHALL CONSIST WELL GRADED, CLEAN, ON-SITE OR IMPORTED SOILS, FREE FROM FOREIGN DEBRIS WHICH ARE READILY COMPACTABLE, AND WHOSE STRENGTH CHARACTERISTICS AND UNIT WEIGHT SATISFY THOSE PRESENTED ON THIS DRAWING.

THE DESIGN PRESENTED ON THIS DRAWING WAS BASED ON THE FOLLOWING SOIL PARAMETERS:

- FOUNDATION SOIL: SOIL UNIT WEIGHT = 128 PCF SOIL FRICTION ANGLE = 28°
- SOIL COHESION = 0 PSF
 RETAINED SOIL: SOIL UNIT WEIGHT = 129 PCF
- SOIL FRICTION ANGLE = 28°
- SOIL COHESION = 0 PSF
- REINFORCED BACKFILL: SOIL UNIT WEIGHT = 120 PCF SOIL FRICTION ANGLE = 34°
 - SOIL COHESION = 0 PSF

ALL SOIL PARAMETERS AND NET ALLOWABLE BEARING PRESSURE OF 3,000 PSF SHALL BE CONFIRMED BY THE OWNER'S GEOTECHNICAL ENGINEER PRIOR TO THE CONSTRUCTION OF THE RETAINING WALLS.

PERFORM GRADATION AND ATTERBERG LIMITS TESTING PRIOR TO CONSTRUCTION AND AT REGULAR INTERVALS DURING CONSTRUCTION PER ASTM D422 AND ASTM D4318 TO VERIFY BACKFILL TYPES MEET MINIMUM PROJECT REQUIREMENTS.

PERFORM SOIL SHEAR STRENGTH TESTS PER ASTM D3080 TO VERIFY SOIL ANGLE OF INTERNAL FRICTION (PHI ANGLE) FOR REINFORCED BACKFILL. FOR THE REINFORCED BACKFILL ZONE, THE PLASTICITY INDEX (P.I.), AS DETERMINED BY AASHTO T-90, SHALL NOT EXCEED 6 (PER REINFORCED EARTH ABBREVIATED TECHNICAL SPECIFICATIONS FOR MECHANICALLY STABILIZED EARTH (MSE) RETAINING WALLS) WITH A GRADATION SUCH THAT 100% PASSES 4-INCH SIEVE, 75%-100% PASSES 3-INCH SIEVE, AND LESS THAN 15% PASSES #200 SIEVE.

THE OWNER OR CONTRACTOR SHALL RETAIN A GEOTECHNICAL ENGINEER TO VERIFY EXISTING SOIL CONDITIONS AND TO ENSURE THAT THE WALL IS CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS. FAILURE TO PERFORM THE TESTING AND INSPECTIONS STATED HEREIN WILL RELEASE THE ENGINEER FROM THIS DESIGN. TESTING AND INSPECTION REPORTS SHALL BE PROVIDED TO THE ENGINEER. REPORTS SHOULD ADDRESS NOT ONLY TEST RESULTS BUT VERIFICATION OF MATERIAL TYPES AND CONSTRUCTION DETAILS INCLUDING GRID LENGTHS, LOCATIONS, AND INSTALLATION PROCEDURES. ANY DISCREPANCIES FROM THE CONTRACT DOCUMENTS SHOULD BE REPORTED TO THE ENGINEER.

PROVIDE WALL ENGINEER WITH MATERIAL REPORTS BEFORE CONSTRUCTION AND INSPECTION REPORTS FOR REVIEW OF DESIGN CONFORMANCE.

PART 3 EXECUTION

- 3.1 VERIFY
- A. CHECK THAT FOUNDATION AND BEARING AREA ARE READY FOR WALL INSTALLATION (PROPERLY CLEARED AND GRUBBED, ALL STUMPS, ORGANIC MATERIAL, DEBRIS, AND DELETERIOUS MATERIAL REMOVED. REPORT UNSUITABLE CONDITIONS TO ENGINEER IN WRITING.

3.2 PREPARATION

A. EXCAVATE FOUNDATION SOIL TO THE LINE AND GRADES AS SHOWN ON THE CONSTRUCTION DRAWINGS OR AS DIRECTED BY THE ENGINEER. OVER-EXCAVATED AREAS SHALL BE FILLED WITH COMPACTED BACKFILL MATERIAL AS PER PROJECT SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER. AS A MINIMUM, FOUNDATION SOIL SHALL BE PROOF ROLLED PRIOR TO BACKFILL AND GEOSYNTHETIC PLACEMENT.

3.3 INSTALLATION

- A. PLACE THE WELDED WIRE FACING PANELS ALONG WALL LAYOUT LINE, AS SHOWN ON THE CONSTRUCTION DRAWINGS. ALIGN EACH BASKET WITH NO OVERLAPS UNLESS SHOWN ON PLANS. CONNECT ADJACENT BASKETS AND INSTALL WIRE STRUTS FROM HORIZONTAL LEG UP TO VERTICAL LEG. USE A RUNNING BOND PATTERN ON UPPER WIRE FACING PANEL LIFTS TO AVOID A STACKED WALL JOINT CONDITION.
- B. GEOSYNTHETIC MATERIAL BREAKS DOWN WHEN EXPOSED TO UV LIGHT. LIMIT MAXIMUM EXPOSURE TO UV LIGHT TO 14 CALENDAR DAYS OR LESS.
- C. PLACE THE GEOGRID AT THE PROPER ELEVATION AND ORIENTATION AS SHOWN ON THE CONSTRUCTION DRAWINGS OR AS DIRECTED BY THE ENGINEER. ENGINEER (OR ENGINEER'S REPRESENTATIVE) SHALL VERIFY AND DOCUMENT CORRECT ORIENTATION OF THE GEOSYNTHETIC. CUT THE GEOSYNTHETIC TO LENGTH AS SHOWN ON THE CONSTRUCTION DRAWINGS.
- D. PLACE ONLY THE AMOUNT OF GEOGRID REQUIRED FOR IMMEDIATELY PENDING WORK TO PREVENT UNDUE DAMAGE AND UV EXPOSURE.
- A. GEOGRID MAY NOT BE OVERLAPPED OR CONNECTED MECHANICALLY TO FORM SPLICES. SINGLE PANEL LENGTHS ARE REQUIRED IN THE PRIMARY STRENGTH DIRECTION (ROLL DIRECTION) PERPENDICULAR TO WALL OR SLOPE FACE. POSITION ADJACENT ROLLS ALONG ROLL EDGES, NO OVERLAPPING IS REQUIRED BETWEEN ADJACENT ROLLS UNLESS SPECIFIED BY THE ENGINEER. A MINIMUM SOIL COVER OF 3 INCHES IS REQUIRED BETWEEN GEOGRID OVERLAP LAYERS.
- B. ENGINEER'S SUGGESTED INSTALLATION PROCEDURE FOR EACH LIFT OF WRAPPED RETAINING WALL.
- 1. AFTER PLACING AND SECURING THE FACING UNITS AND LAYING OUT THE GEOGRID, INSTALL A TEMPORARY RESERVE BETWEEN THE FACING UNIT AND THE GEOGRID TO ALLOW PLACING THE UV BARRIER. PROVIDE A MINIMUM RESERVE WIDTH OF 12 INCHES. THE UV BARRIER RESERVE MAY CONSIST OF UV BARRIER COBBLES AND BOULDERS OR REMOVABLE FORM.
- 2. PLACE GEOTEXTILE FILTER FABRIC PARALLEL TO THE FACING UNITS SO THAT THE HILL- SIDE EDGE IS ABOUT 4 FEET BEHIND FACING UNITS. DRAPE FILTER FABRIC OVER THE FACING UNITS AND UV BARRIER RESERVE.

- 3. DRAPE GEOGRID LEADING EDGE OVER THE FACING UNIT, RESERVE, AND FILTER FABRIC, EXTENDING THE GEOGRID FAR ENOUGH FOR ADEQUATE WRAP LENGTH AS SHOWN ON THE DRAWINGS. PLACE GEOGRID SMOOTHLY AND FREE OF WRINKLES AND LYING FLAT. TEMPORARILY SECURE GEOGRID IN-PLACE WITH STAPLES, PINS, SAND BAGS, OR BACKFILL.
- 4. PLACE AND COMPACT A LAYER OF REINFORCING FILL, SLOPE THE END OF THE FILL ADJACENT TO THE FACING UNIT AT ABOUT 1:1 TO ALLOW ROOM FOR UV BARRIER ATOP GEOGRID. UNDRAPE AND WRAP THE GEOGRID AND FILTER FABRIC OVER THE COMPACTED REINFORCING FILL AND REMOVE TEMPORARY RESERVE (IF USED).
- 5. PLACE THE UV BARRIER BETWEEN FACING UNITS AND FILTER FABRIC AND GEOGRID SO THAT IT COMPLETELY COVERS THE GEOGRID.
- 6. REPEAT FOR EACH FOLLOWING LIFT.

E. REINFORCING FILL PLACEMENT

- 1. PLACE REINFORCING FILL IN MAXIMUM 9 INCH COMPACTED LIFTS.
- 2. COMPACT EACH LIFT TO THE DENSITY AS ESTABLISHED BY THE ROLL PATTERN. COMPACT REINFORCING FILL WITHIN 3 FEET OF THE WALL FACE WITH HAND EQUIPMENT.
- 3. PLACE, SPREAD AND COMPACT REINFORCING FILL IN SUCH A MANNER AS TO MINIMIZE THE DEVELOPMENT OF WRINKLES IN AND/OR MOVEMENT OF THE GEOGRID.
- 4. PLACE REINFORCING FILL IN SUCH A MANNER AS TO MINIMIZE THE DISTURBANCE OR MISALIGNMENT OF THE WALL FACING.
- 5. PROVIDE A MINIMUM FILL THICKNESS OF 6 INCHES PRIOR TO THE OPERATION OF VEHICLES OVER THE GEOGRID.

H. RETAINING WALL DRAINAGE

- 1. INTERNAL DRAINAGE SHALL BE CONSTRUCTED IN ACCORDANCE WITH THESE CONSTRUCTION DRAWINGS AT THE LOCATIONS AND ELEVATIONS SHOWN ON CROSS SECTIONS AND DETAILS. THE INTERNAL DRAINAGE SYSTEM IS INTENDED TO CONTROL GROUNDWATER SEEPAGE IN THE RETAINING WALL REINFORCED ZONE. THE INTERNAL DRAINAGE SYSTEM IS NOT INTENDED TO ACCOMMODATE SURFACE WATER INFILTRATION THAT OCCURS DUE TO IMPROPER CONTROL OF SURFACE WATER DURING AND AFTER CONSTRUCTION.
- 2. EXTERNAL DRAINAGE CONTROL MEASURES MUST BE CONSTRUCTED AND MAINTAINED DURING THE CONSTRUCTION OF THE RETAINING WALL(S). AT THE END OF EACH WORK DAY, THE RETAINING WALL CONSTRUCTOR SHALL GRADE THE SURFACE OF THE LAST LIFT OF THE REINFORCED BACKFILL SUCH THAT THE SURFACE WATER IS DIRECTED AWAY FROM THE RETAINING WALL(S).
- 3. THE GENERAL CONTRACTOR SHALL PROTECT THE RETAINING WALL WORK AREA FROM SURFACE WATER AT ALL TIMES BY THE USE OF BERMS, DIVERSION DITCHES, TEMPORARY DRAINS, SILT FENCING, AND ALL OTHER MEANS THAT MAY BE REQUIRED.
- 4. THE PONDING OF WATER ABOVE OR WITHIN TWENTY (20) FEET OF THE REINFORCED ZONE DURING OR AFTER WALL CONSTRUCTION SHALL NOT BE PERMITTED.
- 5. THE GROUND SURFACE ABOVE AND BELOW THE RETAINING WALL SHALL BE PROTECTED AGAINST EROSION DURING AND AFTER CONSTRUCTION BY OTHERS (SEE ALSO POST-CONSTRUCTION CARE).
- 6. IT IS THE RESPONSIBILITY OF THE CIVIL ENGINEER TO PROPERLY DESIGN THE SITE DRAINAGE AND GRADING TO PREVENT EROSION OF THE RETAINING WALL BACKFILL AND FOUNDATION, AND INFILTRATION INTO THE RETAINING WALL BACKFILL. THE RETAINING WALL CONTRACTOR WILL BE RESPONSIBLE FOR DAILY DRAINAGE CONTROL MEASURES WITHIN THE RETAINING WALL REINFORCED ZONE. THE GENERAL AND EARTHWORK CONTRACTORS SHALL BE RESPONSIBLE FOR SITE DRAINAGE OUTSIDE THIS AREA AND ITS EFFECTS ON THE RETAINING WALL CONSTRUCTION AND PERFORMANCE DURING AND AFTER CONSTRUCTION.

I. UTILT

- ALL NEW UTILITIES LOCATED WITHIN THE RETAINING WALL REINFORCED ZONE OR LOCATED ADJACENT TO THE RETAINING WALL REINFORCED ZONE SHALL BE INSTALLED AS THE RETAINING WALL REINFORCED BACKFILL IS BEING PLACED.
- 2. UTILITIES TO BE INSTALLED IN THE VICINITY OF THE WALL, SUCH AS LIGHT POLES, HAND RAILS, GUARD RAILS, AND/OR DRAINAGE STRUCTURES, MUST BE DESIGNED AND CONSTRUCTED SO THAT THEY DO NOT ADD LATERAL FORCES TO THE WALL SYSTEM. ALSO, ANY EXCAVATION, SUCH AS INSTALLATION OF CONCRETE GUTTERS, SHRUB AND TREE PLANTING, ETC., CONDUCTED IN THE VICINITY OF THE WALL AFTER THE WALL HAS BEEN CONSTRUCTED MUST BE DONE WITHOUT DAMAGING THE WALL OR REINFORCEMENT MATERIALS.
- 3. UTILITIES THAT ARE CONSTRUCTED INSIDE THE RETAINING WALL REINFORCED ZONE SHALL BE PLACED IN STRICT ACCORDANCE WITH PROJECT SPECIFICATIONS. PROPER CARE MUST BE TAKEN TO INSURE THAT THE PIPE JOINTS ARE WATER TIGHT, AND THAT ALL PIPES ARE PLACED ON PROPERLY COMPACTED SOILS.
- J. QUALITY CONTROL OF PLACED FILL SHALL CONFORM TO RSS NOTES 1.3.D

EROSION AS SOON AS POSSIBLE FOLLOWING CONSTRUCTION.

- K. MINIMIZE TURNING OF TRACKED VEHICLES TO PREVENT TRACKS FROM DISPLACING THE FILL AND DAMAGING THE GEOGRID. RUBBER TIRED EQUIPMENT MAY PASS OVER THE GEOSYNTHETIC REINFORCEMENT AT LOW SPEEDS, LESS THAN 5 MPH. AVOID BRAKING AND TURNS. CONTRACTOR SHALL REPLACE ANY GEOGRID DAMAGED DURING INSTALLATION AT NO ADDITIONAL COST TO THE OWNER.
- L. SLOPE SURFACE OF REINFORCING FILL TO DRAIN AWAY FROM THE WALL FACE AND TO PREVENT WATER PONDING UPON THE SURFACE OF THE REINFORCING FILL. PROVIDE DITCHES AND FLOW PATHS, AS NEEDED, TO KEEP THE SITE DRAINED. MAINTAIN THE SITE AREA TO PREVENT STORMWATER OR SURFACE WATER FLOW FROM ADJACENT AREAS FROM ENTERING THE WALL AREA.

A POST CONTRUCTION CARE

- M. POST CONTRUCTION CARE.
 1. NO EXCAVATION THROUGH LAYERS OF SOIL REINFORCEMENT SHALL BE PERMITTED WITHOUT THE PRIOR WRITTEN APPROVAL OF THE RETAINING WALL DESIGN ENGINEER OF RECORD.
- INSTALLATION OF IRRIGATION LINES ABOVE THE REINFORCED ZONE OR WITHIN TEN (10) FEET OF THE WALL TOE
 IS NOT PERMITTED WITHOUT PRIOR WRITTEN APPROVAL OF THE RETAINING WALL ENGINEER OF RECORD.
 MATERIAL STOCKPILES MUST BE KEPT A MINIMUM OF TEN (10) FEET FROM THE FRONT FACE OF THE RETAINING
- 4. PROPER SURFACE WATER CONTROL AND DIVERSION OF WATER AWAY FROM THE RETAINING WALL MUST BE MAINTAINED AT ALL TIMES. ALL TOE AND CREST SLOPES SHALL BE VEGETATED AND PROTECTED AGAINST
- 5. THE RETAINING WALL DESIGN ENGINEER OF RECORD SHALL BE CONTACTED TO REVIEW ANY REQUIRED POST WALL CONSTRUCTION UTILITY PLACEMENT IN THE VICINITY OF THE WALL. EXCAVATION IN AND AROUND THE WALL MAY DAMAGE THE COMPONENTS OR COMPROMISE THE INTEGRITY OF THE STRUCTURE AND MUST BE EVALUATED BY THE RETAINING WALL DESIGN ENGINEER OF RECORD
- 6. ANY INCIDENTS THAT MAY CAUSE DAMAGE OR COULD AFFECT THE LONG-TERM PERFORMANCE OF THE RETAINING WALL MUST BE REPORTED TO THE RETAINING WALL DESIGN ENGINEER OF RECORD IMMEDIATELY.

JCTURE REVISIONS:

JE, SUITE 110 7202 711

WSP USA ENVIRONM 245 N. WACO AVENUE, S WICHITA, KANSAS 67202 PHONE: 316-448-2711 FAX: 316-448-2711


ORCED SOIL SLOPE WALL DETAIL STR-IMHOFF CREEK BANK STABILIZATION
CITY OF NORMAN, OKLAHOMA

DESIGNED BY: ---DRAWN BY: ACG
CHECKED BY: EJB
DATE: Mar 22, 2024




PROJECT NO. 8275000431

SHEET NO. 27 OF 30




1. RSS FACING TO CONSIST OF PREFABRICATED GALVANIZED STEEL WELDED WIRE FABRIC, 4x4-W4xW4 FORMS. 2. OVERALL LENGTH OF WIRE FORMS IS 10'-4"±. EFFECTIVE CONSTRUCTED WIDTH IS 10 FT WITH 2" OVERLAPPING ON EACH END OF FORM. 3. FORMS AS MANUFACTURED BY DIMENSION FABRICATORS, INC. OR APPROVED EQUAL.







1. SEE WELDED WIRE FORM (WWF) FACING UNIT DETAIL FOR FACING MATERIALS AND DIMENSIONS. INSTALL ADJACENT WWF FACING UNITS TO PROVIDE 2" OVERLAP OF HORIZONTAL WIRES.
 WHEN MSE LAYOUT INCLUDES A CORNER/TURN, FULL GEOGRID COVERAGE IS REQUIRED. REFER TO ELEVATION VIEW FOR LIMITS OF FULL GEOGRID COVERAGE.









PROJECT NO. 8275000431


REINFORCED SOIL SLOPE WALL DETAIL STR-002

DESIGNED BY: ----

DRAWN BY: ACG CHECKED BY: EJB DATE: Mar 22, 2024

IMHOFF CREEK BANK ST CITY OF NORMAN, OK

SHEET NO. 28 OF 30



PROCESSED BACKFILL MATERIAL PER PROJECT SPECIFICATIONS. CARE SHALL BE

THIS WIRE FORM PER PROJECT SPECIFICATIONS, LEAVING A TROUGH DIRECTLY

6. PLACE PLANTABLE FILL AND STEEP SLOPE SEED MIX INTO TROUGH. BASE OF

7. FOLD BACK MIRAMESH AND PULL TAUGHTLY OVER THE TOP OF BACKFILLED

8. SET THE NEXT WELDED WIRE FORM PER HORIZONTAL AND VERTICAL PLAN

WELDED WIRE FORM WITH A MINIMUM HORIZONTAL RETURN OF 30".

9. ORDINARY HIGH WATER (OHW) LEVEL VARIES AS FOLLOWS:

TROUGH SHALL BE NO LESS THAN 4" WIDE, TOP OF TROUGH SHALL BE 6" WIDE.

TROUGH SHALL BE 9" HIGH SO VEGETATION OCCURS IN TOP HALF VERTICALLY AND

ON THE 9" HORIZONTAL BENCH OF THE WELDED WIRE FORM. COMPACT PLANTABLE

DOWNSTREAM EL.

1097.23

1097.77

UPSTREAM EL.

1097.69

1100.64

EXISTING GROUND-

AT BASE OF WALL

BEHIND THE WELDED WIRE FORM TO ACCOMMODATE THE GROWTH MEDIUM

5. PLACE AND COMPACT THE FINAL LAYER OF PROCESSED BACKFILL MATERIAL FOR

TAKEN TO ENSURE ADEQUATE COMPACTION AT WALL FACE.

FILL IN ACCORDANCE WITH PROJECT SPECIFICATIONS.


GEOMETRY AND REPEAT STEPS 2-7 ABOVE.

STATION TO STATION

16+40 TO 17+50

22+00 TO 31+05

(PLANTABLE FILL).




WITH MIRAFI 180N OR APPROVED EQUAL

FOUNDATION ZONE,

ODOT STANDARDS

EXCAVATE AND BACKFILL WITH TYPE D AGGREGATE BASE IN ACCORDANCE WITH



TYPICAL DIMENSIONS AND SETBACK DETAIL

2. OVERALL LENGTH OF WIRE FORMS IS 10'-4"±.

WALL HEIGHT, H (FT)	(FT)	FROM BOTTOM OF WALL (FT)	GEOGRID*
UP TO 15'	9	1.5, 3, 4.5, 6, 9, 12	MIRAFI 5XT
>15' AND UP TO 18'	16	1.5, 4.5, 6	MIRAFI 20XT
>15' AND UP TO 18'	12	7.5, 10.5, 13.5, 16.5, 19.5	MIRAFI 5XT
>18' AND UP TO 22'	16	1.5, 3, 4.5, 6, 7.5	MIRAFI 20XT
>18' AND UP TO 22'	12	9, 12, 15, 18, 21	MIRAFI 7XT
*SPECIFIED GEOGRID S UPON APPROVAL OF T		EQUIVALENT GEOGRID MAY BE SUBS	TITUTED

GEOGRID EMBEDMENT LENGTH, L GEOGRID LOCATION, MEASURED

PROJECT NO. 8275000431

ALL DETAIL STR-003

SLOPE W

ORCED SOIL

DESIGNED BY: ----

DRAWN BY: ACG

CHECKED BY: EJB

DATE: Mar 22, 2024

SHEET NO. 29 OF 30

- 1. NOTIFY OKLAHOMA 811 ONE-CALL. CONFIRM THE LOCATIONS OF ALL SURFACE OR SUBSURFACE FEATURES, INCLUDING UTILITIES, WHICH HAVE A BEARING UPON THE PROPOSED CONSTRUCTION PRIOR TO BEGINNING CONSTRUCTION. VERIFY THE LOCATION OF ALL EXISTING UTILITIES AND REPORT ANY DISCREPANCIES IMMEDIATELY PRIOR TO CONTINUANCE OF WORK. COORDINATE WITH LOCAL UTILITY COMPANIES PRIOR TO UTILITY DISCONNECT.
- 2. PERFORM ALL WORK IN ACCORDANCE WITH DRAWINGS AND ALL APPLICABLE CODES AND REGULATIONS UNLESS OTHERWISE NOTED. COMPLY WITH THE REQUIREMENTS OF THE VARIOUS FEDERAL, STATE, AND LOCAL SAFETY CODES (E.G. OSHA).
- 3. UNLESS NOTED OTHERWISE (UNO), EXISTING FEATURES SHALL REMAIN. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE INTEGRITY OF EXISTING FEATURES, INCLUDING EXISTING UTILITIES.
- 4. OBTAIN ALL REQUIRED PERMITS PRIOR TO EXECUTION OF THE WORK.
- 5. NOTIFY THE ENGINEER OF ALL ITEMS OF CONSTRUCTION REMAINING AND NOT SPECIFICALLY MENTIONED THAT INTERFERE WITH THE NEW CONSTRUCTION.
- 6. MAINTAIN CONDITION OF EXCAVATION SLOPE(S) AND PROVIDING SAFE WORKING CONDITIONS FOR ALL PERSONS ON THE PROJECT SITE THROUGHOUT THE CONSTRUCTION PROCESS.

SUGGESTED SEQUENCE OF CONSTRUCTION

- 1. LAYOUT LIMITS OF SHEET PILE BASED UPON TOTAL STREAM WIDTH.
- 2. DRIVE SHEET PILE TO MINIMUM TOE EMBEDMENT AS INDICATED IN THE SECTIONS. PROVIDE DRIVING LOGS TO ENGINEER WITHIN 24 HOURS OF PILE DRIVING COMPLETION. LOGS AT A MINIMUM SHALL STATE BLOWS PER FOOT, HAMMER SIZE AND ENERGY.
- 3. PLACE RIPRAP AS SHOWN IN THE DRAWINGS

DESIGN CRITERIA

- 1. SHEET PILES SIZED BASED ON SHEAR AND BENDING MOMENTS ESTIMATED USING "NAVFAC DESIGN MANUAL 7.02 FOUNDATIONS AND EARTH STRUCTURES. MAXIMUM ANTICIPATED LATERAL MOVEMENT AT TOP-OF-SHEET PILE IS 1 INCH.
- 2. DESIGN GROUNDWATER LEVEL IS ASSUMED AT A STATIC LEVEL EQUAL TO THE STREAM INVERT.
- 3. SHEET PILE DESIGNED IN ACCORDANCE WITH ALLOWABLE STRESS DESIGN (ASD) PROVISIONS OF THE "AISC STEEL CONSTRUCTION MANUAL", 14TH EDITION.

MATERIAL SPECIFICATIONS:

- 1. STEEL SHEET PILES SHALL BE NZ14, OR APPROVED EQUIVALENT, CONFORMING TO ASTM A572, GRADE 50.
- 2. SHEET PILE CORNER ANGLES: USE MANUFACTURE'S CORNER PILE ANGLE ELEMENTS TO MEET THE ANGLES CALLED FOR ON THE DETAIL.
- 3. RIP-RAP AROUND SHEET PILE SHALL BE $D_{50} = 18$ " SIZE RIP RAP.

PILE WALL TOLERANCES


1. PLACE SHEET PILES AT THE LOCATIONS SHOWN ON THE PLAN VIEW. DO NOT DEVIATE BY MORE THAN 3 INCHES IN ANY DIRECTION FOR OF THE WALL.

FIELD TESTING INSPECTION

1. PROVIDE MINIMUM 24 HOUR NOTICE TO INSPECTION ENGINEER'S STAFF OF CONSTRUCTION ACTIVITY REQUIRING TESTS.


SUBMITTALS

1. PROVIDE PILE DRIVING LOGS TO ENGINEER WITHIN 24 HOURS OF PILE INSTALLATION COMPLETION.



SHEET PILE PROFILE VIEW


NOT TO SCALE



SHEET PILE CROSS SECTION VIEW

NOT TO SCALE

CROSS VANE INFORMATION								
LOCATION	CHANNEL EL.	SHEET PILE & EL.	SHEET PILE EDGE EL.	100-YR CRITICAL VEL. EL				
STA 28+40	1089.33	1092.33	1093.00	1100.88				
STA 24+60	1087.85	1090.85	1091.50	1098.53				



SHEET PILE LAYOUT DETAIL

NOT TO SCALE

ROCK TOE REVETMENT WITH LIVE SOIL

NOT TO SCALE

PROJECT NO. 8275000431

SHEET NO.

30 OF 30

STR-004

IMHOFF

DESIGNED BY: ---DRAWN BY: ACG

CHECKED BY: EJB
DATE: Mar 22, 2024

201/5/715861 DICHOL A: 118AC715861 DICHOL By: C.Hibrara Assolution Date /Time: 3 / 21 / 2

SHEET.

1/3