



CONTRACTOR PRICING WORKSHEET

JOB ORDER CONTRACTING NO:

730-24

PROJECT NAME: OK - Norman - FY 2027 - Lining

THE LOCAL GOVERNMENT PURCHASING COOPERATIVE

Item	Description of Item	Est. Quant.	Unit
BASE BID ITEMS			
I.5A.008	Clean & CCTV 24" Light Cleaning <3passes included in Install	170	LF
I.5A.012	Clean & CCTV 36" Light Cleaning <3passes included in Install	937	LF
I.5A.016	Clean & CCTV 60" Light Cleaning <3passes included in Install	410	LF
I.20A.041	Mobilization - Oklahoma - UV CIPP	1	EA
I.1A.008	24" X 5.6mm - CIPP UV Cure - Foxborough	170	LF
I.1A.012	36" X 5.6mm - CIPP UV Cure - Robinson	937	LF
I.20A.041	Mobilization - VLS Crew	1	LS
II.21A.005	VLS - Geokrete Supply & Install 1.5" GeoKrete Plus Corrugation Fill (1x3) On Existing 56" CMP Storm Pipe And 1" On Exiting 48" RCP	410	LF
II.21A.020	VLS Crew Invert Repair (Per CF) *Will Bill As Needed	1	CF
I.5A.031	21" - 36" Post TV Inspection After Rehabilitation	1107	LF
I.5A.035	55" - 60" Post TV Inspection After Rehabilitation	410	LF
II.21B.004	Grout Injection Under Sidewalk (min pay 1,037#)	1037	#
Proposal BASE Total			

SUPPLEMENTAL ITEMS

	Proposal SUPPLEMENTAL ITEMS Total		
--	--	--	--

TOTAL BASE + SUPPLEMENTAL (less Bonds)

LIST PRICING

Unit Price	Total
\$ 24.00	\$ 4,080.00
\$ 33.00	\$ 30,921.00
\$ 55.00	\$ 22,550.00
\$ 35,000.00	\$ 35,000.00
\$ 263.00	\$ 44,710.00
\$ 475.00	\$ 445,075.00
\$ 35,000.00	\$ 35,000.00
\$ 937.50	\$ 384,375.00
\$ 200.00	\$ 200.00
\$ 11.00	\$ 12,177.00
\$ 52.20	\$ 21,402.00
\$ 30.00	\$ 31,110.00
\$ 1,066,600.00	

\$ -
\$ 1,066,600.00

PROJECT SPECIFIC DISCOUNT

Unit Price	Total
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 25,000.00	\$ 25,000.00
\$ 263.00	\$ 44,710.00
\$ 345.00	\$ 323,265.00
\$ 15,000.00	\$ 15,000.00
\$ 690.00	\$ 282,900.00
\$ 175.00	\$ 175.00
\$ 11.00	\$ 12,177.00
\$ 30.00	\$ 12,300.00
\$ 22.65	\$ 23,488.05
\$ 739,015.05	

\$ -
\$ 739,015.05

Insurance, Bonds, CoOp Fee: **\$ -**

Pricing Date: **08.21.26**

TOTAL: \$ 739,015.05

Buying Agency:	City of Norman OK - Stormwater Division
Contact Person:	Luis Rangel
Phone:	(405) 219-8111
Email:	Luis.Rangel@NormanOK.gov

Contractor:	Vortex Services, LLC
Prepared By:	Patrick Holland
Phone:	207.530.0937
Email:	patrick.holland@vortexcompanies.com

NOTE:**The Customer shall be responsible for providing:**

- All pricing is contingent upon release of the entire scope. Partial scope release will require review and recalculation of costs.
- Access to jobsite and hydrants or free water source as necessary (including meters)
- Town will provide dump site and pay for any associated fees
- All Traffic Control
- All Permits and Permissions which may be necessary (Federal, State, Local, etc.)
- Any and all access will be provided by Town
- Bypass included up to 350gpm beyond that will be added cost
- Depth to invert assumed to be by <8' (design of thickness).
- Condition of Property: The parties acknowledge that the nature of the Work to be performed hereunder at the Property is such that the drain line and other characteristics and conditions of the site and Property cannot be fully assessed by Contractor until the Services identified in the proposal have commenced. As such, the parties acknowledge that the condition of the Property including the drain line may necessitate modifying the proposal and executing applicable Purchase Orders. Neither party, at this time, can satisfy itself as to coordination of such schedules and as to the existing condition of all parts of the Property and its location, including, without limitation, access to the Site, availability, location, and condition of the drain line, all necessary utilities, climatic conditions, surface and subsurface conditions, potential exposure to hazardous or toxic wastes and substances, gases and other hazardous conditions and the condition of all improvements in or on the Property. Once the actual condition of the Property or of any of the other items described above is determined and necessary modifications to the proposal and/or Purchase Orders are mutually agreed upon, the Contractor shall be solely responsible for completing the Work.
- Mechanical Cleaning / Tuberculation removal not included in bid proposal.
- If bond is needed please add 1.5%.
- Any Site Restoration will be performed by Others.
- Cleaning includes 3 passes per pipe segment. Additional passes shall be charged at \$685.00/Hr. Includes downtime for CCTV crew
- CIPP Samples can be provided at no additional cost. If 3rd party CIPP testing is required, it can be provided at \$450 per each test. There was no CIPP specification mentioning samples and testing for this bid.
- If a certified P.E. thickness design is required, please add \$2,000 per each diameter.
- Standard wages are included. Therefore, Prevailing wages / Union Wage Rates / Apprenticeships are not included in this bid proposal.
- Client / GC must notify Vortex if the project is Certified payroll prior to contract execution or additional fees may apply.
- Any delays besides weather that is outside of our control will be billed at a standby rate of \$1,250 / hour, for the CIPP Lining Crew & \$650/ hour for the Clean & CCTV Crew.

SIDEWALK GROUTING CLARIFICATIONS

- 1.)Owner shall be available throughout project to review completed work and indicate acceptance or exceptions prior to SGSde-mobilization from worksite.
- 2.)Provide clear access to work areas; advise SGSI of any underground utilities, hazards above or below ground surface
- 3.)Owner warrants that all underground utilities in the affected repair areas have been pressure tested and are structurally sound
- 4.)Owner shall be responsible for all aesthetic wall repairs and flooring materials affected by repair procedure, pre and post job
- 5.)Owner indemnifies and holds harmless Superior Grouting Services Inc, from any/all claims relating to current condition of existing concrete. Superior will re-align concrete applying the highest standard, quality and accuracy possible considering current condition of the existing concrete.