

KEN'S ELECTRIC INC.
 841 1st Ave SE
 Oelwein, IA 50662
 319-283-4221

Ken's Electric, Inc.

841 1st Ave SE
 Oelwein IA 50662
 319-283-4221

| | |
|-------------|----------------|
| Date | March 11, 2021 |
| Proposal # | 205969-01 |
| Customer ID | 103272 |

HVAC REPLACEMENT

Billing Information

Oelwein Police Department
 501 Rock Island Rd
 Oelwein IA 50662
 319-283-4311

Service at

Oelwein Police Department
 501 Rock Island Rd
 Oelwein IA 50662
 319-283-4311

305195

GEOTHERMAL HEAT PUMP INSTALL

| | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
| INSTALL GEO LOOP VERTICLE PER TON | ü |
| INSTALL GEO WATER TO WATER 3 TON | ü |
| GEOCOMFORT INDOOR UNITS | ü |
| GEO FLO PUMPING STATION | ü |
| GEO INTERIOR LOOP PIPING | ü |
| HOURLY COMMERCIAL | ü |
| INCLUDED IN THIS OPTION WILL BE A COMPLETE REPLACEMENT OF THE HEATING AND COOLING SYSTEM FOR THE OELWEIN POLICE DEPARTMENT. WE WILL INSTALL A 22 TON GEOTHERMAL SPLIT SYSTEM. WE WILL INSTALL A 22 TON VERTICAL LOOP FIELD ON THE SOUTH SIDE OF THE POLICE STATION. FROM THE MAIN LOOP WE WILL HORIZONTAL BORE UNDER THE BUILDING TO THE MECH ROOM. THE MAIN PUMPING SYSTEM WILL BE INSTALLED IN THIS ROOM. WE WILL PIPE FROM THE MAIN ROOM TO EACH OF THE 10 UNITS THROUGH OUT THE BUILDING. EACH OF THE UNITS WILL BE REPLACED WITH A PROPER SIZED GEOTHERMAL UNIT. WE WILL REPLACE THE BOILER SYSTEM WITH A WATER TO WATER GEOTHERMAL UNIT TO RUN THE INFLOOR HEAT IN THE GARAGES. THE WATER HEATER WILL ALSO BE REPLACED WITH AN ELECTRIC MODEL THAT WILL BE COUPLED TO THE GEOTHERMAL SYSTEM FOR ADDED EFFICIENCY. EACH OF THE 10 ZONES WILL HAVE WIFI THERMOSTATS WITH THE CAPABILITY TO CONTROL VIA THE INTERNET. ALL MATERIAL AND LABOR HAVE BEEN INCLUDED FOR A COMPLETE INSTALL. | ü |
| WARRANTY: 5 YEAR PARTS 5 YEAR LABOR | |
| Total | \$ 224,900.00 |

TERMS

50% UPON ACCEPTANCE OF THIS PROPOSAL, 50% UPON COMPLETION OF THE PROJECT. THIS PROPOSAL IS VALID FOR 30 DAYS.

Accepted Option: _____

 Acceptance (Customer)

 Date

 Approval (Company)

 Date