



Memo

To: Honorable Mayor & City Council,
From: Public Works Superintendent Victor Kane
CC: City Administrator Dylan Mulfinger

Reference: Fall Sealcoat Projects

Date: 09/17/21

Greetings,

There are two roads we would like have seal coated this fall. West Charles from the viaduct to 13th Ave NW. The second being 10th Ave NW from 1st St. to 3rd St. NW.

We received two quotes (attached) coming in at \$47,022 and \$42,834 to complete this work. I am respectfully requesting that we accept Blacktop Services quote for a total of \$42,834.

Thank you for your time,
Victor Kane

From the Desk of
Public Works Superintendent Victor Kane

PROJECT WORKSHEET
Prairie Road Builders, Inc



Date: 8/27/2021

Customer: City of Oelwein, Iowa
 Herb 319-283-8173

SS:		DS:		P:		Grind:		BR:		BP:	
-----	--	-----	--	----	--	--------	--	-----	--	-----	--

CODE: SS-Single Seal, DS-Double Seal, P-Patch, G-Grind, BR-Base Repair, BP-Base Prep

Identification	From	To	Measurement	Sq. Yd.	Rec. Imp.	Cost
1. W. Charles St.	RR Bridge	West side of 13 th Ave	3785 x 24	10,093	SS	25,737.15
2. W. Charles St.	West side of 13 th Ave	West side of bridge (city limits)	1250 x 24	3333	SS	8,499.15
3. 10 th Ave NW (gravel now) Base work and prep done by the City	3 rd St. NW	2 nd St. NW	Radius 390 x 16	47 693	DS DS	3,774.00
4. 10 th Ave SW	2 nd St. NW	1 st St. NW	50 x 17-19	1000	DS	5,100.00
5. 10 th Ave NW	1 st St. NW	W. Charles St.	300 x 23	767	DS	3,911.70
					Total:	47,022.00

2021 Street Maintenance



16 North Taft Street
 PO Box 632 • Humboldt, IA 50548
 (515) 332-4208 office • (515) 332-3653 fax

Oelwein, IA

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
	10TH Ave NW	Double	10TH Ave	NW - 3 Blocks				
	"	Seal						
	"	Coat with 3/8"	W. Charles	1st ST NW	295 x 23			
	"	Chips	1st ST NW	2nd ST NW	493 x 18			
	"	MC-3000 @	2nd ST NW	3rd ST NW	408 x 15			
		IA DOT Rates!						
			NOTE: City will complete Patching & grading prior to our Double Seal/Coat Project.					
			ABOVE Project Total Cost =					\$ 10,890.
			Note: This Project is TIED to Proposal on "W. Charles" street.					

Measured by: Mark J. Steffes #319-404-7770

Date: 8-24-21

Accepted by: _____

Date: _____

2031 Street Maintenance



De/Wein, IA

16 North Taft Street
PO Box 632 • Humboldt, IA 50548
(515)332-4208 office • (515)332-3653 fax

No.	Street	Type of Work	From	To	Size	Sq. Yards	Patch	Cost
	" W. Charles "	Single Seal	Viaduct & west to 137th Ave NW			3800 x 26	10,978 sq's	
		Asphalt						
		3/8" Chips						
		with MC-3000						
		Asphalt						
		@ Iowa DOT						
		Rotes, Rotes,						

NOTE: City will close Road and provide signs @ Intersections for this project. City will complete Patching & Cleaning prior to our Asphalt Resurfacing.

NOTE: Project will be measured upon completion for actual total sq's for final billing.

Mobilization - Above → # 9,000.00
Approximately 10,978 sq's @ # 2.09 / sq = # 22,944.02

Above Project total cost = 31,944.02

Measured by: Mark J. Stoffes #319-404-7720

Date: 8-24-21

Accepted by: _____ Date: _____