

11/15/2021

Vic Kane  
City of Oelwein  
20 2<sup>nd</sup> Ave. SW  
319-283-5440 Office  
319-238-1153 Mobile  
vkane@cityofelwein.org

Dear Vic,

Thank you for considering Yant Equipment for your Reliable Fueling Solutions. We appreciate the opportunity to provide you with this proposal.

Reliable Fueling Solutions at affordable pricing is what our customers desire. We recognize this and have a strong commitment to providing it. As a result, Yant Equipment has enjoyed continued growth and success for over 60 years.

I have prepared the following equipment below to meet your current needs. The new PetroVend system is EMV capable and complies with all Mastercard/Visa and proprietary cards for the Oelwein Airport. The additions of pulsers would be needed. All tanks and their respective ancillary equipment will be reused if possible.

Yant Equipment will provide trenching and boring services for underground pipe to install new needed electrical connections. It is the responsibility of the customer to provide and pull new wire as needed to power and allow for system communication. All electrical connections and communication must be in working condition before project will commence to its second phase. EMV encryption requires a manager network switch for communication and compliance. This switch is provided through the PetroVend Network. The first year's services regarding the network switch are included in its price. After 1 year the monthly charge will be approximately \$85.00 each month.

**PV300 System EMV READY**

- PV300 Pedestal with 7" Touchscreen
- EMV and Mag Strip Reader
- Secure pin pad
- 1-year OASE process/support
- OASE/NBS onboarding and process fees
- Dover Fueling Solutions EMV terminal Software
- Edge Gateway P.C.

- Router/Switch
- Pedestal, Mounting Bracket and 2 hose PCM
- Receipt printer
- Phoenix SQL Lite and Startup
- Pulsers for pump to pedestal for communication

Total Equipment Cost - \$25,066.39

(Total Does NOT include Surcharges, Freight, and/or any applicable taxes)

Yant Equipment will trench and bore as needed to the existing tanks and install underground pipe for electrical conduit. Wire new OPW PV300 system. Yant will turn-key the installation, troubleshoot, train on all system wiring and useability.

Items to be consider in addition would be:

- Repair of existing Emergency Stop
- New installation of any switches or controls related to any other pumps or equipment

Total Installation Labor Turn-key ready - \$19,115.48

**Projected Quote Estimate - \$44,181.87**

All network and/or communication functions are the responsibility of customer. If the project scope exceeds normal man hours related to excess trouble shooting or environmental causes regular hourly rate will apply (\$100.00 per hr.). Any additional mileage, trips or travel time may apply.

Sincerely,  
Nick Shanno



RELIABLE FUELING SOLUTIONS  
O M A H A ★ L I N C O L N

NICK SHANNO  
OPERATIONS MANAGER  
Nshanno@yantequipment.com

Office 402-345-6045  
Cell 402-681-1557

2209 N 15TH ST EAST | 7890 N 56TH ST  
OMAHA, NE 68110 | LINCOLN, NE 68514

YANTEQUIPMENT.COM