Date of Issuance	: September 11, 2019	Effective Date:	October 31, 2019
Owner:	City of Oelwein	Owner's Contract No.:	
Contractor:	Blacktop Service Company	Contractor's Project No.	:
Engineer:	FOX Engineering	Engineer's Project No.:	1022-19A.660

Contract Name:

**Change Order No.** 

The Contract is modified as follows upon execution of this Change Order:

Oelwein 2019 Seal Coat Improvements

1. Bid item No. 7.01 – Bituminous Seal Coat, Single Pass, 3/8" Cover Aggregate: This quantity is being changed from 33,498 SY to 33,579 SY which increased the bid item by \$231.66. City Staff eliminated seal coat from certain roadway sections. In addition, the City has added double seal coat on certain roadway sections. See attachments for quantities:

- NE Seal Coat Area bid tabulations
- NW Seal Coat bid tabulations

Project:

2. Bid Item No. 7.02 – Cold Patch Pavement: The city will allow the Contractor to utilize Hot Mix Asphalt (HMA) in lieu of Cold Mix Patch. The revised depth of the proposed patches shall be 3 inches vs 4 inches. Field measures patches at a 3 inch depth is estimated to 150 tons of HMA per the plan quantities. The quantity is being changed from 150 tons (estimated) to 163.36 tons which increased the bid item by \$4,118.75. The City Staff determined additional patching of pavement was necessary prior to sealcoating.

CHANGE IN CONTRACT PRICE	CHANGE IN CONTRACT TIMES
Original Contract Price:	Original Contract Times:
	Substantial Completion: N/A
\$ <u>169,047.78</u>	Ready for Final Payment: November 1, 2019
[Increase] [Decrease] from previously approved Change	[Increase] [Decrease] from previously approved Change
Orders No. 0 to No. 0:	Orders No. 0 to No. 0:
	Substantial Completion: N/A
\$ <u>0.00</u>	Ready for Final Payment: November 1, 2019
Contract Price prior to this Change Order:	Contract Times prior to this Change Order:
	Substantial Completion: N/A
\$ <u>169,047.78</u>	Ready for Final Payment: November 1, 2019
Increase of this Change Order:	[Increase] [Decrease] of this Change Order:
	Substantial Completion: N/A
\$4,350.41	Ready for Final Payment: November 1, 2019
Contract Price incorporating this Change Order:	Contract Times with all approved Change Orders:
	Substantial Completion: N/A
\$ <u>173,398.19</u>	Ready for Final Payment: November 1, 2019

	RECOMMENDED:	ACCEPTED:	ACCEPTED:
Ву:	Engineer (if required)	By:Owner (Authorized	By: Contractor (Authorized
Title:	PROS MANAGER	Title	Title:
Date:	10.31.2019	Date:	Date:

## **NE SEALCOAT AREA**

REF NO.	STREET LOCATION	SEAL COAT LIMITS	NOTE	PATCH SIZE	PATCH AREA (SY)	SEAL COAT SIZE (ft x ft)				DOUBLE SEAL COAT AREA (SY)	NOTE TO CITY
1	3rd Ave NE	9th St Intersection	Patch	3' x 3'	1.0						
2	4th Ave NE	6th St NE to 9th St NE	Patch & Sealcoat			22	ж	1,400	3,422.2	3,422.2	
3	8th St NE	3rd Ave NE to 4th Ave NE	Patch & Sealcoat			25	ж	280	777.8	777.8	
4	7th St NE	3rd Ave NE to 4th Ave NE	Patch & Sealcoat			20	ж	280	622.2	622.2	
5	6th St NE	6th Ave Intersection	Patch	15' x 25'	41.7						
6	6th Ave NE	North of 6th St NE	Patch & Sealcoat	20' x 45'	100.0		П				
7	7th Ave NE	House No. 625-707	Patch & Sealcoat			32	×	250	888.9		
8	3rd St NE	2nd Ave NE to 4th Ave NE	Patch & Sealcoat			30	×	600	2,000.0		
9	5th St NE	Fredrick (10 Block) to 1st Ave NE	Patch & Sealcoat			30	×	310	1,033.3		
10	5th St NE	2nd Ave NE to 4th Ave NE	Patch & Sealcoat	10' x 30'	33.3	30	x	270	900.0		
11	3rd Ave NE	4th St NE to Lincoln DR	Patch & Sealcoat			20	×	670	1,488.9		
12	4th Ave NE	5th St NE to Lincoln DR	Patch & Sealcoat			20	x	350	777.8		
13	6th Ave NE	1st St to 2nd St	Grade & Sealcoat			20	×	500	1,111.1	1,111.1	
14	2nd St NE	500 block - south side middle of block	Patch	5' x 30'	16.7		П				
15	6th St NE	8th Ave NE west to corporate limits	Patch & Sealcoat			22	×	370	904,4	904.4	Additional 70-ft x 22-ft Seal Coat

TOTALS: 31.2 13,926.7 6,837.8

## **NW SEALCOAT AREA**

REF NO.	STREET LOCATION	SEAL COAT LIMITS	NOTE	PATCH SIZE	PATCH AREA (SY)	SEAL COAT SIZE (ft x ft)			LIGHT TRAFFIC SEAL COAT AREA (SY)		NOTE TO CITY
1	2nd St NW	6th Ave NW to 8th Ave NW	Patch & Sealcoat			25	x	704	1,955.6	1,955.6	
2	10th Ave NW	West Charles to 2nd St NW	Patch & Scalcoat			25	×	925	2,569.4		Remove from Project
3	11th Ave NW	West Charles to 2nd St NW	Patch & Sealcoat			15	×	925	1,541.7		
4	12th Ave NW	West Charles to 2nd St NW	Patch & Sealcoat			25	91	925	2,569.4		Remove from Project
5	1st St NW	5th Ave NW to 8th Ave NW	Patch & Sealcoat			25	×	1,263	3,508.3		
6	4th St NW	Intersection of 4th Ave NW	Patch	3' x 20'	6.7						
7	4th St NW	Intersection of 4th Ave NW	Patch	4' x 4'	1.8						
8	4th St NW	Intersection of 4th Ave NW	Patch	4' x 4'	1.8						
9	4th-St-NW	Fredrick to 1st Ave NW	Patch & Scalcoat			26	M	560	1,617.8		
10	6th St NW	200 Block	Patch & Sealcoat	2 tons		32	x	320	1,137.8		
11	1st Ave NW	7th St NW Intersection	Patch	30' x 30'	100.0						

TOTALS: 17.9 **8,143.3 1,955.6**