

Grand Total

\$157,025.91

Scope of Work

1. Install temporary fencing around the work area - **Approximately 970 LF**
2. Demolish existing concrete sidewalk along Mill Street - **Approximately 5,040 SF (12' x 420')**
3. Remove and haul away debris from demolition - Approximately 5,040 SF
4. Remove and replace the curb and gutter at sidewalk location.
5. Remove and replace curb ramps.
6. Supply and install redwood header board along existing fence.
7. Construct curb behind sidewalk at the northwest corner of Yolo & 1st Street intersection.
8. Construct modifications to the storm drainage pipe and drop inlet near Yolo Street.
9. Adjust the existing water meter box to grade.
10. Prep and grade area for new concrete sidewalk installation - Approximately 5,040 SF
11. Form and pour new concrete sidewalk - Approximately 5,040 SF
12. Leave existing maintenance access ramp intact and integrate with new sidewalk where applicable.
13. Apply necessary AC paving batch back for sidewalk restoration.
14. Clean the work area and dispose of all construction waste materials.

Qualifications

1. Priced for scope to reflect city engineer supplied drawing.
2. Site conditions are to be prepared and ready by others to mobilize.
3. The area must have access to equipment, water, power, restrooms, and a dumpster.
4. Any deviations from the estimate will result in a change order.
5. Price valid for 30 days.
6. KYA pays prevailing wages.
7. Priced per CMAS.

Exclusions

1. Move-In Clause: This quote is based on one move-in. The price is based on all areas being available before mobilization. The additional cost for mobilization will be \$2,500 each.
2. Grading/backfill of landscape area, irrigation, planting, capping, or relocating sprinklers are excluded.
3. Testing, surveying, staking, erosion control, air monitoring, dust control, sanitary facilities, temporary controls, corrective grinding, access stabilization, and soil sterilant are excluded.
4. Weekend work and/or night work is excluded.
5. Must be given at least a three-week notice to schedule work.
6. No dumpster or acquiring permits.
7. No core drilling or saw cutting.
8. Traffic control.
9. Adjustment of underground utility covers and/or any work associated with them is excluded.
10. ADA upgrades are not included. The customer is responsible for drawings, inspections, testing, permits, and ensuring ADA compliance.

Preliminary Construction Schedule

<i>Task</i>	<i>Duration</i>	<i>Start</i>	<i>Finish</i>
<i>Submittal</i>	4 Weeks		
<i>Submittal Review</i>	2 Weeks		
<i>Material Lead Time</i>	8 Weeks		
<i>Installation / Construction</i>	2 Weeks		
<i>Substantial Completion</i>	1.5 Weeks		

Signature of Acceptance of Proposal:

Print:

Date:
