

Centennial Park Gazebo repair cost estimate and schedule

		Number	Per item cost	Cost			
Concrete step form	Use old steps	50' est.	0	0			
Concrete mesh	42" x 7'	2, cut in half	20	40			
Concrete bottom step, 4"-5"d x 2'w x 25'long	60lb bags, .45 cu ft	55	4	220			
Step stringers, pres. Treated pine	3 steps	8	23	190			
Steps, 2"x6"x 8', weather shield, ground contact	3 steps x 24'	18	12	216			
Hand rails, 2"x4"x4', kiln dried	2"x4"x8'	2, cut in half	8	16			
Hand rail posts, 4"x4"x4' prom. Doug fir	4"x4"x8'	2, cut in half	18	36			
Hang Rail post anchors	4"x4"	4	11-26-00	44.00-104.00			
Deck screws, #10 x 4", 5lb box		1	30	38			
<b>Estimated total not inc. tax</b>				\$800-900.00			
<b>Schedule</b>							
	<b>6/3/2022</b>	Remove old stairs					
		Build concrete deck frame, w/mesh					
		Cement, mixer to gazebo					
<b>6/4/2022 All hands on deck!</b>		Pour concrete	Need water and generator				
	<b>6/5/22-6/10/22</b>	Prep wood pieces for installation					
	<b>6/11/2022</b>	Build steps and hand rails					
	?	Stain and /or paint					

