



PO BOX 725 PIPESTONE MN 56164 507.825.5462

Dust Mitigation Plan in relation to new corn receiving pit

- Work being done at the Hord Feed & Grain Mill will not increase traffic at that facility. The work is allowing for better flow of traffic coming through the mill on a daily basis.
- HFG has implemented the use of a contracting service to apply a dust control product to the driveways of the facility and will continue this process on a schedule going forward.
- The new corn receiving pit will have a concrete exit to the street eliminating dust from a stone driveway in that area.
- The new pit will be equipped with dust control measures. Along with those measures, HFG will have the ability to close the exit door of the pit while unloading if necessary.

Hord Feed & Grain Dust control Upgrades

- Installed baffles below pit grates to increase dust control while dumping corn. (Completed January 2025)
- Installed a vacuum system which pulls the dust from the corn dump pit into the vacuum. This in conjunction with the baffles has greatly reduced any dust emissions at the new corn dump. (Completed August 2025)

Primary Contact

Greg Staatz

Feed Mill Manager

greg.staatz@hordfarms.com

507-215-0294

Secondary Contact

Cal Hulstein

Project Manager

cal.hulstein@hordfarms.com

507-215-1250