MAJESTIC ASPHALT

20932 Burr Oak Rd. Capron, IL 61012 * 815-543-5653

Proposal

NAME	PHONE
Lions Park	
STREET	WORK TO BE PERFORMED AT: Asphalt Walking Path
CITY/STATE: Poplar Grove, IL	DATE OF PLANS: 2021 Season

1. Will remove existing damaged asphalt walking path approx. 5' x 2,075'.
2. Will excavate existing soils approx. 3' x 2,075' to accommodate 8" new base stone.
3. Will install approx. 250 ton CA6 base stone to excavated area.
4. Will grade base stone for proper drainage.
5. Will compact base stone with vibratory roller.
6. Will pave walking path approx. 8' x 2,075' with N50 hot mix asphalt @ 2.5".
7. Will compact all new asphalt with vibratory roller.
8. Will haul away debris and leave work area broom clean.
    - Prevailing wages to be paid.
    - Laser grader box to be used to meet ADA requirements.

All materials and workmanship is guaranteed for one year. All work to be completed in a workmanlike manner. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders and will become an extra charge over and above the estimate. This proposal is subject to acceptance within 60 days and it is void thereafter.

Total labor and material: $47,300.00

Half down, paid in full upon completion

Respectfully Submitted Dave Stout

ACCEPTANCE OF PROPOSAL

Signature_____