PROPOSAL

No problem!
Pearson
Rockford Office: 815-398-8312
Fax: 815-229-8778
2415 20th St., Rockford, IL 61104
www.PearsonGuy.com

Plumbing • Heating – A/C
PEST CONTROL ... AND MORE!

CUSTOMER INFORMATION

Village of Poplar Grove
200 N Hill St
Poplar Grove, IL 61065

C/S	DATE
494855	9-21-2020

JOB NAME
Drinking fountain with bottle filler

JOB LOCATION
lobby

E-MAIL
mhilden@villageofpoplargrove.com

We hereby submit specifications and estimate for:

- Disconnect and remove the existing drinking fountain and tile around the fountain to allow removal.

- Install an Elkay EZH20 bottle filling station with single ADA drinking fountain with hands free activation and 8GPH chiller.

- Connect water line and drain to new unit.

- Mount unit on the wall and repair tile around drinking fountain as needed.

* Customer to supply tile.

* Add $140.00 to add Elkay filter to system.

We Propose hereby to furnish material and labor – complete in accordance with above specification, for the sum of:

($ 3,420.00)

Payment to be made as follows:
50% Down, Balance due upon completion.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Authorized Signature: Don Howe

Note: This proposal may be withdrawn by us if not accepted within 90 days.

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance: _____

E_mail: _____

Signature: _____