

# AREA MECHANICAL

COMPLETE MAINTENANCE CONTRACTS • SALES, SERVICE, & INSTALLATIONS  
PLUMBING • REFRIGERATION • STEAM & HOT WATER BOILERS  
HVAC • GEOTHERMAL • KITCHEN EQUIPMENT

September 11, 2024

Village of Poplar Grove Sewer Plant

Attn: Jason Hagberg

Re: AC in control room compressor, economizer control, damper actuator, enthalpy sensor, filter drier, and economizer sensor replacement quote

1. Shut down power to existing unit.
2. Recover any refrigerant if needed.
3. Remove and replace compressor on circuit 1.
4. Replace liquid line drier, pull vacuum, and charge with 9 lbs of R22.
5. Remove and replace contactor, economizer control, damper actuator, enthalpy sensor, and economizer sensor.
6. Perform startup and verify operation.
7. Leak check all connections and make any repairs if necessary for circuit 1.
8. Notify manager of completed work.

Total estimated cost for work listed above: \$8408.33 plus tax and shipping which isn't calculated until the order is placed.

## EXCLUSIONS

- Overtime
- Additional repairs beyond the quoted scope of work

Respectfully,

Cody Saunders

2707 HUFFMAN BLVD  
ROCKFORD, IL 61103

PHONE: (815) 964-2070  
SALES@AREAMECHANICAL.COM

24 HOUR SERVICE

