MAJESTIC ASPHALT

20932 Burr Oak Rd. Capron, IL 61012 * 815-543-5653

Change Order

NAME	PHONE
Lions Park	
STREET	WORK TO BE PERFORMED AT:
	Asphalt Walking Path
CITY/STATE	DATE OF PLANS
Poplar Grove, IL	2021 Season

1. Will excavate existing soils and ag lime approx. 5' x 2,075' to accommodate 8" new base stone, will properly dispose of soils & ag lime.
2. Will install approx. 525 ton CA6 base stone to excavated area.
3. Will grade base stone for proper drainage.
4. Will compact base stone with vibratory roller.
5. Will haul away debris and leave work area broom clean.
    - Prevailing wages to be paid.
    - Laser grader box to be used to meet ADA requirements.

All materials and workmanship is guaranteed for one year. All work to be completed in a workmanlike manner. Any alteration or deviation from above specifications involving extra cost will be executed only upon written orders and will become an extra charge over and above the estimate. This proposal is subject to acceptance within 60 days and it is void thereafter.

Total labor and material: $21,000.00

Half down, paid in full upon completion

Respectfully Submitted Lau Stott

ACCEPTANCE OF PROPOSAL

Signature_____