

Global Pump Solutions LLC

4541 J D Mouser Pkwy
Alvarado, TX 76009 US
(972) 449-5770
accounting@gpspumps.com
www.globalpumpsolutions.net



Estimate

ADDRESS
City of Prosper
601 W. Fifth Street
Prosper, TX 75078

ESTIMATE 4365
DATE 04/29/2024
EXPIRATION DATE 05/25/2024

CONTACT
James

PROJECT NAME
Prosper VT

DATE	DESCRIPTION	QTY
Labor	Teardown and inspect Fairbanks VT Provide GPS inspection report of findings upon customers request. Rebuild with new National Pump column / bowl assembly. Adapt new lower end to existing pump head. Sandblast pump head and recoat.	45
Field Labor	Load VT and motor from pump station. Reinstall rebuilt pump and motor. Test run with customer for proper operation.	16
National Vertical Turbine	K20LC-03;12-TPL;NONE;NONE DSVT: FAIRBANKS REPLACEMENT 4860gpm @ 250ft 4-6weeks	1
Machining Services	Adapter collar from column assembly to pump head.	1
Motors	Rewind and recondition Motor. High pot motor surge test when complete.	1
Misc --	oils, solvents, paint, misc.	1

Pricing does not include shipping unless explicitly stated. Terms are NET 15 unless otherwise negotiated.

SUBTOTAL	78,192.00
TAX	0.00
TOTAL	\$78,192.00

Note: Unforeseen problems not listed in scope of work will be addressed at the time of project. Additional charges may be added if project goes beyond time frame or scope of work.

Global Pump Solutions BUYBOARD#672-22

Accepted By

Accepted Date