SURVEYOR'S NOTES:


- 1. Bearings are based on the State Plane Coordinate System, Texas North Central Zone (4202) North American Datum of 1983 (NAD '83), distances are surface with a combined scale factor of 1.00015271.
- This property lies within Zone "X" of the Flood Insurance Rate Map for Collin County, Texas and Incorporated Areas, map no. 48085C0120J, with an effective date of June 2, 2009, via scaled map location and graphic plotting.
- Monuments are found unless specifically designated as set.
- 4. Elevations (if shown) are North American Vertical Datum of 1988 (NAVD '88).


NOTE REGARDING UTILITIES

Source information from plans and markings will be combined with observed evidence of utilities pursuant to Section 5.E.iv. to develop a view of the underground utilities. However, lacking excavation, the exact location of underground features cannot be accurately, completely, and reliably depicted. In addition, in some jurisdictions, 811 or other similar utility locate requests from surveyors may be ignored or result in an incomplete response, in which case the surveyor shall note on the plat or map how this affected the surveyor's assessment of the location of the utilities. Where additional or more detailed information is required, the client is advised that excavation and/or a private utility locate request may be necessary. Utility locations are per observed evidence.

LEGEND OF ABBREVIATIONS

- D.R.C.C.T. DEED RECORDS, COLLIN COUNTY, TEXAS
- P.R.C.C.T. PLAT RECORDS, COLLIN COUNTY, TEXAS O.P.R.C.C.T. OFFICIAL PUBLIC RECORDS, COLLIN COUNTY, TEXAS
- DOC.#
- DOCUMENT NUMBER • C.M. CONTROLLING MONUMENT
- SQ. FT. SQUARE FEET
- ROW RIGHT OF WAY
- CAPPED REBAR SET CRS





LEGEND OF SYMBOLS


LOT 3, BLOCK A,

VICTORY AT FRONTIER

VOL. 2018, PG. 699

P.R.C.C.T.

🛯 air conditioning unit



SIGN "CITY-LIMIT"

LOT 3, BLOCK A, VICTORY AT FRONTIER VOL. 2018, PG. 699 P.R.C.C.T.

This survey was prepared without the benefit of a commitment for title insurance. Therefore, easements, agreements, or other documents, either recorded, or unrecorded may exist that affect the subject property that are not shown on this survey. SURVEYOR'S CERTIFICATE This is to certify that I, John H. Barton III, a Registered Professional Land Surveyor of the State of Texas, have prepared this map from an actual survey on the ground, and that this map correctly represents that survey made by me or under my direction and supervision. This survey meets the minimum requirements for a Category 1A, Condition II Land Title Survey. Fieldwork was completed on September 14, 2020. Date of Plat/Map: September 15, 2020 PRELIMINARY THIS DOCUMENT SHALL NOT BE RECORDED FOR ANY PURPOSE AND SHALL NOT BE USED, VIEWED, OR RELIED UPON AS A FINAL **SURVEY DOCUMENT September 15, 2020** John H. Barton III, RPLS# 6737 TERMS OF ACCEPTANCE OF SURVEY This survey is issued pursuant to a real estate transaction and is appurtenant to the title commitment referenced in the "Title Commitment Notes" This survey is issued for use in such transaction. Notwithstanding any of the above statements, the surveyor has a contractual relationship with one client or entity. Review/requested revisions by other parties must be received by or through such entity. Client is responsible for reviewing survey (including, but not limited to: notations; existence or lack of spelling/grammatical/typographical errors; certified parties; dates; instruments) within thirty (30) days of the date of plat or map. After such time has passed, client accepts survey as issued, and further revisions are not embraced by the above certification. Additional or altered commitments for title insurance will require an new or re-issued survey. Please feel free to request pricing for this at info@bcsdfw.com, or call (817) 864-1957.

PROPERTY DESCRIPTION

BEING a portion of Lot 3 in Block A of Victory at Frontier, an addition in the Town of Prosper, Collin County, Texas, according to the plat recorded under Volume 2018, Page 699, Plat Records of Collin County, Texas, (P.R.C.C.T.), the subject tract being more particularly described by metes and bounds as follows (bearings are based on State Plane Coordinate System, Texas North Central Zone, North American Datum of 1983 (NAD '83)):

BEGINNING at a 1/2 inch rebar with pink cap stamped, "BARTON CHAPA" set (hereinafter called "capped rebar set") for the southeast corner of the herein described tract, said point being in the east line of said Lot 3;

- **THENCE** through the interior of said Lot 3 the following calls:
- 1. North 88 degrees 35 minutes 37 seconds West, a distance of 344.09 feet to an "X" cut in concrete set; 2. North 01 degrees 24 minutes 24 seconds East, a distance of 167.98 feet to an "X" cut in concrete set;
- 3. North 89 degrees 26 minutes 11 seconds East, a distance of 83.18 feet to an "X" cut in concrete set in the west line of Lot 2 in said Block A;

THENCE South 00 degrees 15 minutes 13 seconds West, with the west line of said Lot 2, a distance of 26.31 feet to a capped rebar set;

THENCE South 88 degrees 35 minutes 36 seconds East, with the south line of said Lot 2, a distance of 263.84 feet to a capped rebar set for the southeast corner thereof, same being a northeast corner of said Lot 3;

THENCE South 01 degrees 24 minutes 24 seconds West, with the east line of said Lot 3, a distance of 76.26 feet to a capped rebar set;

THENCE South 04 degrees 16 minutes 09 seconds West, with the east line of said Lot 3, a distance of 68.37 feet to the **POINT OF BEGINNING** and enclosing 1.198 acres (52,186 square feet) of land, more or less.

TITLE COMMITMENT NOTES



CATEGORY 1A, CONDITION II LAND TITLE SURVEY

PORTION OF LOT 3, BLOCK A VICTORY AT FRONTIER TOWN OF PROSPER COLLIN COUNTY, TEXAS



5200 State Highway 121 Colleyville, TX 76034 Phone: 817-488-4960

JOB NO. 2020.001.148

TABLE OF REVISIONS

VICTORY AT

FRONTIER

PROSPER,

TEXAS

SUMMARY


DRAWN: BCS

CHECKED: JHB

DATE



CATEGORY 1A **CONDITION II** LAND TITLE SURVEY



NORTH ELEVATION



SOUTH ELEVATION



20023-01 tws 10/29/21 updated 20023-01 tws 10/27/21 updated 20023-01 tws 10/22/21

0 - Rooftop HVAC (exact location may vary) **Architectural Panel** -Metal Coping 21'-6"aff 8 A ANA ANA ∠ Alum. Storefront Brick -Brick \square Downspout Stucco

WEST ELEVATION

EAST ELEVATION





FACADE NOTES

This Façade Plan is for conceptual purposes only. All building plans require review and approval from the Building Inspections Division.

All mechanical equipment shall be screened from public view. Rooftop mounted equipment shall be screed by a parapet wall or screening wall. Screening walls shall be the specifications of the Zoning Ordinance.

When permitted, exposed utility boxes and conduits shall be painted to match the building.

All signage areas and locations are subject to approval by the Building Inspections Division.

Windows shall have a maximum exterior visible reflectivity of ten (10) percent.

Any deviation from the approved Façade Plan will require re-approval by the Town of Prosper.

NET FACADE TOTAL MASONRY: TOTAL ARCHITECTU TOTAL AWNINGS: TOTAL STUCCO:	5,166 SF 100% 3,325 SF 64% IRAL PANEL: 1,228 SF 24% 399 SF 7% 214 SF 5% EXHIBIT B
TOTAL FACADE: TOTAL DOORS/GLA	
TOTAL MASONRY: 60% PANELS : 255 S METAL AWNING: 66 S	F TOTAL FACADE: 1,671 SF F 100% DOORS/GLAZING: 624 SF F 60% NET FACADE: 1,047 SF 100% MASONRY (STONE): 479 SF 46% F 19% TOTAL MASONRY: 46%
MASONRY (BRICK): 620 S TOTAL MASONRY: 69% PANELS : 320 S	F DOORS/GLAZING: 76 SF