

June 22, 2023

## PROPOSAL

Town of Prosper  
250 W. First Street  
Prosper, Texas 75078

Attn: James Rodriguez – Water & Sewer Superintendent

Re: Furnish & Install One (1) 3/4 HP KASCO Tank Mixing System at 2.5 MG Composite EST

### KASCO EQUIPMENT DETAILS


Axis Construction, LP in conjunction with Kasco Marine is pleased to present a Proposal for one (1) **Submersible mixer** on above mentioned project. Below you will find a brief description of your application, our recommended equipment and product sheets.

Tank Description: Existing 2.5 MG Fish Trap Composite EST

#### Recommendation

Kasco recommends **one (1) 3400C61 CertiSafe NSF 61/372 mixer** for this application. The Certisafe mixer has three (3) power cable options (50ft, 75ft and 200ft). Pricing includes the cable length of **75ft**. Kasco recommends the **Suspended Mount SM-100** in the Elevated Storage Tank.

#### Scope of Material furnished by Axis Construction, LP & KASCO

Qty	Description	
1	<p>Kasco Municipal mixer complete package <b>#34C61075SM-CS15</b></p> <ul style="list-style-type: none"><li>Kasco 3400C61 CertiSafe Tank Mixer (120V) with 75ft UL power cord. Order part <b>#3400C61</b></li><li>1- Kasco Suspended Mount <b>#SM100</b></li><li>Kasco SCADA CS-150 is a 120Vac, 60hz, single phase UL listed control panel engineered to operate Kasco C61 CertiSafe™ tank mixers. Designed for easy installation and operation, H-O-A control switch, indicator LEDs, Low water inhibit, and SCADA I/O for remote operation and monitoring. Order part <b>#176371</b></li><li><b>Standard 3-year Manufacturer's warranty included.</b></li><li>Axis has included freight to site as noted above</li><li>Axis labor warranty is 1 year</li></ul> <p>Total price includes equipment as stated &amp; Freight to Jobsite.</p>	<p><b>EST 1 @ \$12,180.00</b> <b>Freight @ \$300.00</b></p>  <p><b>\$12,480.00</b></p>

## Installation

We are pleased to provide a Proposal to furnish labor, equipment and materials required to install and start-up mixer. Please note the following details:

1. We will install all conduit & wire from the top of the tank mixer connection junction box, down to mixer panel mounted at the base of the tank.
2. Conduit will be rigid aluminum and will be secured with galvanized right-angle clamps on the ladder.
3. We have not included final wiring of mixer or any SCADA wiring. We will start-up the mixer once the power is connected by your electrician.

**Total Cost for Install & Start-up of Kasco Mixer = \$15,540.00**

**Total Cost for Equipment and Installation = \$28,020.00**

### Notes:

1. **BUY BOARD- We are approved/listed on Contract 662-22 for Tank Mixers.** If you use BuyBoard for the purchase, you will get 8% off of the price of labor and equipment as shown above.
2. Installation as detailed above is included in this Proposal. Install can be done by others if you prefer.
3. Proposal is firm for 30 days and subject to change unless a PO is received.
4. Terms are Net 30 upon invoice.
5. Mixer will take approx. 5 days for delivery from KASCO. Lead time for our install is approximately 7 days after receipt of PO for mixer.
6. We recommend installation of a lightning arrestor/surge protector be added to the electric panels to protect the mixer and other components.

If you have any questions on the above information, please contact me at (817) 439-0709 or via e-mail address joeswinnea@hotmail.com. I look forward to an opportunity to work for you on this project.

Respectfully Submitted,

*Joe Swinnea*