



May 25, 2022

Proposal for Prosper FD

August Industries is pleased to provide you with the following quote on your system.

AVAILABLE THROUGH BUY BOARD CONTRACT #603-20

BAUER UNICUS 4 STANDARD 13H-E1 or E3 COMPLETE INTEGRATED STATIONARY SYSTEM supplied with the following quality features:

- 6,000 PSI, 13 CFM CHARGING RATE
- 10 H.P. SINGLE OR THREE PHASE ELECTRIC MOTOR, (SPECIFY UPON ORDER)
- PLC CONTROLLER WITH MULTICOLOR HMI TOUCHPAD PANEL MOUNTED DISPLAY AND CARRIES FULL UL LISTING
- AUTO CASCADE CONTROL SYSTEM
- EMERGENCY STOP SWITCH
- INTEGRAL THREE POSITION, NFPA 1901 APPROVED FULL CONTAINMENT FILL STATION ACCOMMODATES SCBA OR SCUBA CYLINDERS
- AUTOMATIC CONDENSATE DRAIN SYSTEM WITH COLLECTION RESERVOIR AND LEVEL INDICATOR
- P-2 SECURUS ELECTRONIC FILTER MONITORING SYSTEM
- COMPRESSOR HIGH TEMP AND LOW OIL PROTECTION SYSTEM
- SOUND ATTENUATING ENCLOSURE WITH HINGED DOOR ACCESS
- INSTALLED WITH THE OPTIONAL GAS TEK CO MONITOR WIRED FOR ALARM AND SHUTDOWN
- FOUR (4) ASME CODE CYLINDERS INSTALLED IN AN INTEGRAL DESIGNED RACK IN REAR OF UNIT
- FIRE EDITION PAINT SCHEME

Complete package as described, LIST PRICE:

\$82,670.00

OUR QUOTE:

\$72,813.50

TERMS:

Net 30 with approved purchase order

This quoted price is valid for 60 days

Price does include shipping, installation, and training (\$2,550.00)

August Industries will hold the unit until the station is ready for the installation but will bill the department for just the equipment cost upon receipt of the compressor at our facility. The installation portion will be billed when the installation is completed.

Please allow 6-8 weeks for completion