



P.O. Box 104960
 117 Commerce Drive
 Jefferson City, MO 65110

Phone: (573) 635-6229
 Fax: (573) 636-7538

To:	City Of Republic	Contact:	
Address:	213 N. Main Republic, MO 65738	Phone:	
Project Name:	City Of Republic JAC St. / Fire Station #1	Bid Number:	S2021057
Project Location:	JAC Rd & Fire Station #1, Republic, MO	Bid Date:	6/7/2021

Line #	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
0001	JAC Street Roadway - Fine Grading, Agg Base And Asphalt Paving (4" Agg, 5.5" Bit Base, 1.5" BP-2)	1,056.00	SY	\$52.75	\$55,704.00
0002	JAC Street - 2' Concrete Curb & Gutter	846.00	LF	\$29.25	\$24,745.50
0003	Fire Station #1 - 8 Asphalt Milling And Asphalt Paving (6" Bit Base, 2" BP-1 Surface)	3,040.00	SY	\$52.40	\$159,296.00
0003	Fire Station #1 - 2" Asphalt Transition Milling And Asphalt Paving (2" BP-1 Surface)	3,040.00	SY	\$17.35	\$52,744.00
Total Bid Price:					<u>\$292,489.50</u>

Notes:

- Item 0001 - JAC Street Roadway - Fine Grading, Agg Base And Asphalt Paving (4" Agg, 5.5" Bit Base, 1.5" BP-2) - On 1056 SY of prepared subgrade (By Others) lay 4" type 1 baserock, 5.5" Bit Base Asphalt, Tack Coat and 1.5" Surface Asphalt.
- Item 0002 - JAC Street - 2' Concrete Curb & Gutter - Lay 846 LF of 2' curb and gutter down length of roadway and at small repair section at Hamilton Street. Tie ins for 3 curb inlets.
- Item 0003 - Fire Station #1 - 8 Asphalt Milling And Asphalt Paving (6" Bit Base, 2" BP-1 Surface) - On 3040 SY of existing asphalt parking area mill asphalt to a depth of 8", lay 6" Bit Base asphalt followed by tack coat and 2" BP-1 Asphalt Surface Course.
- JAC Street Bid Day Notes:
 Work is not likely to be completed prior to the June 24th deadline listed in the bid request. Work will be completed in the 2021 paving season with no defined deadline.
 Subgrade to be placed by City to +- 1/2".
 City to backfill curbs prior to asphalt placement. All backfill, topsoil and turf is excluded.
 All storm boxes to be installed prior to arrival of curb and gutter crew. City to provide layout.
 All striping signage and anything other than aggregate base, concrete curb and asphalt paving is excluded.
- Fire Station #1 Bid Day Notes:
 Work to be completed in the 2021 paving season with no defined deadline.
 Bid request states removal and replacement of 8" asphalt pavement. Bid anticipates there to be 8" of asphalt currently on the parking lot that can be milled. If there is not 8" of asphalt material that can be removed with a mill changes to the scope would be at a revised cost.
 In the case that any subgrade issues are encountered any remediation would be at an additional cost.
 Asphalt material will be a MoDOT approved Bit Base for the 6" base layer followed by MoDOT approved BP-2 for the surface.
 Bid request doesn't differentiate any depth change from 8" asphalt paving so that has been included throughout, this would be considered a heavy duty paving profile.
 Based on onsite observations it appears that areas of this parking lot could benefit from a much less invasive mill and fill that could potentially save costs if areas of failure were patched and the remainder received a 2" mill and overlay. This could be discussed at later date with the city.
- Bid Includes Greene County Prevailing Wage Order 28 and is tax exempt.
- Bid is based on the quantities above. Final Billing to be based on actual quantity of work performed.
- Fire Station #1 Revised Pricing 2" Overlay**
Work includes transition milling as needed to ensure smooth transitions to adjoining surfaces, tack coat and 2" asphalt paving on 3040 SY of existing asphalt.
In the case that subgrade issues appear during milling operations any patching would be at an added cost.
Striping is not included.
- Timeline of Construction**
As discussed with the recent weather we have had many projects delayed and our schedule has become tight. That being said it is understood that JAC street construction needs to take place in the July 12th -16th timeframe. With a grand opening at the site on August 1st. If awarded the contract we will do everything in our power to ensure that the timeline is met and the work is completed within the timeframe of July 12th to the 16th. As we proceed with the curb and gutter work city crews will need to backfill those curbs as soon as possible once concrete has had a reasonable amount of cure time so that paving can proceed backfilling.


Fire Station Paving to be completed in the 2021 paving season with no defined deadline.



P.O. Box 104960
 117 Commerce Drive
 Jefferson City, MO 65110

Phone: (573) 635-6229
 Fax: (573) 636-7538

To: City Of Republic	Contact:
Address: 213 N. Main Republic, MO 65738	Phone:
	Fax:
Project Name: City Of Republic JAC St. / Fire Station #1	Bid Number: S2021057
Project Location: JAC Rd & Fire Station #1, Republic, MO	Bid Date: 6/7/2021

<p>ACCEPTED: The above prices, specifications and conditions are satisfactory and hereby accepted.</p> <p>Buyer: _____</p> <p>Signature: _____</p> <p>Date of Acceptance: _____</p>	<p>CONFIRMED: Capital Paving And Construction LLC</p> <p style="text-align: right;"></p> <p>Authorized Signature:</p> <p>Estimator: Jeff Creamer (573) 691-2837 jcreamer@capitalpavingmo.com</p>
--	---