Opinion of Probable Cost 12/21/2022 Stori Field Concept 2 City of Richland Center

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity		Unit Price		Item Total	
Street &	Site work							
1	Mobilization	LS	1	\$	18,000.00	\$	18,000.00	
2	Site Clearing & Grubbing	LS	1	\$	2,000.00	\$	2,000.00	
3	Temporary Traffic Control	LS	1	\$	1,500.00	\$	1,500.00	
4	Remove Existing Asphalt	SY	290.0	\$	5.00	\$	1,450.00	
5	Common Excavation (Estimated 2500 CY +/-)	LS	1	\$	27,600.00	\$	27,600.00	
6	Strip, Salvage, & Re-Spread Topsoil (Estimated 1000 CY +/-)	LS	1	\$	8,000.00	\$	8,000.00	
7	Excavation Below Subgrade (EBS) (Excavation Only)	CY	30	\$	15.00	\$	450.00	
8	Base Aggregate Dense - 1 1/4"	TON	770	\$	15.00	\$	11,550.00	
9	Base Aggregate Dense - 3" (Includes Base for EBS)	TON	1590	\$	15.00	\$	23,850.00	
10	Finish Grading In Prep. Of Stone Base	LF	535	\$	5.00	\$	2,675.00	
11	Sawcut Asphalt	LF	200	\$	5.00	\$	1,000.00	
12	HMA Pavement - Upper Layer 1.75"	TON	230	\$	110.00	\$	25,300.00	
13	HMA Pavement - Lower Layer 1.75"	TON	230	\$	110.00	\$	25,300.00	
14	Remove Existing Building	LS	1	\$	4,000.00	\$	4,000.00	
15	Asphaltic Tack Coat	SY	2150	\$	0.40	\$	860.00	
16	Street Sign - Stop Sign (R1-1) and Street Name Assembly	EA	1	\$	750.00	\$	750.00	
17	Restoration W/ Seed, Mulch, & Fertilizer	SY	7000	\$	4.00	\$	28,000.00	
18	New Tree	EA	4	\$	600.00	\$	2,400.00	
19	Inlet Protection - Type D	EA	2	\$	200.00	\$	400.00	
20	Clear Stone Tracking Pad	TON	50	\$	20.00	\$	1,000.00	
21	Silt Fence	LF	400	\$	3.50	\$	1,400.00	
22	Remove Existing Curb & Gutter	LF	60	\$	6.00	\$	360.00	
23	Concrete Curb & Gutter - 30"	LF	555	\$	22.00	\$	12,210.00	
		Subtotal - Street & Site work Contingency (10%)				\$	200,055.00	
						\$	20,005.50	
		Professional Services (12%)					26,407.26	
		Total - 3					246,467.76	

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity	Unit Price		Item Total	
Sanitary	Sewer						
24	Sanitary Sewer - 8" PVC	LF	600	\$	55.00	\$	33,000.00
25	Sanitary Sewer - Connect to Existing	EA	2	\$	1,500.00	\$	3,000.00
26	Sanitary Sewer Televising	LF	600	\$	3.00	\$	1,800.00
27	Sanitary Sewer - 48" Dia. Manhole	EA	4	\$	5,500.00	\$	22,000.00
28	Sanitary Sewer Service Lateral - 4" PVC	LF	440	\$	40.00	\$	17,600.00
29	Sanitary Sewer- 4" Wye Only	EA	8	\$	400.00	\$	3,200.00
30	Abandon Existing Sanitary Sewer	LS	1	\$	3,000.00	\$	3,000.00
31	Select Granular Backfill (Trucked-In)	CY	150	\$	15.00	\$	2,250.00
		Subtotal - Sanitary Sewer			\$	85,850.00	
		Contingency (10%)			\$	8,585.00	
		Professional Services (12%)			\$	11,332.20	
					Total -	\$	105,767.20

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity	Unit Price		Item Total	
Park and	d Sledding Hill						
32	HMA Pavement - Parking Stalls - 3"	TON	90.00	\$	130.00	\$	11,700.00
33	Pavement Marking - 4"	LF	460.00	\$	10.00	\$	4,600.00
33	Poured Concrete Steps	VSF	250	\$	70.00	\$	17,500.00
34	Concrete Sidewalk (5")	SF	3240	\$	7.00	\$	22,680.00
35	Handrail	LF	50	\$	80.00	\$	4,000.00
•		Subtotal - Park and Sledding Hil			\$	60,480.00	
		Confingency (10%)			\$	6,048.00	
		Professional Services (12%)			\$	7,983.36	
		Total -				\$	74,511.36

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity		Unit Price	Item Total
Water D	istribution					
32	Water main - 6" C-900	LF	50	\$	65.00	\$ 3,250.00
33	Water main - 8" C-900	LF	685	\$	70.00	\$ 47,950.00
34	Water Main - Connect to Existing	EA	2	\$	2,000.00	\$ 4,000.00
35	Gate Valves - 6"	EA	2	\$	2,350.00	\$ 4,700.00
36	Gate Valves - 8"	EA	2	\$	3,000.00	\$ 6,000.00
37	Styrofoam Insulation	EA	4	\$	125.00	\$ 500.00
38	Water Service Lateral - 1" HDPE	LF	830	\$	32.00	\$ 26,560.00
39	Water Service - Corporation, Curb Stop, Union, and Box	EA	16	\$	550.00	\$ 8,800.00
40	Hydrant - New w/ Marker Flag	EA	2	\$	6,450.00	\$ 12,900.00
41	Select Granular Backfill (Trucked-In)	CY	200	\$	15.00	\$ 3,000.00
			Subtotal - Water Distribution			\$ 117,660.00
		Contingency (10%)			\$ 11,766.00	
		Professional Services (12%)				\$ 15,531.12
		Total -				\$ 144,957.12

Bid Item Ref. No.	Description	Unit of Measure	Estimated Quantity	Unit Price		Item Total	
Storm Se	ewer & Storm Water Management						
42	Storm Sewer - 15" RCP	LF	350	\$	75.00	\$	26,250.00
43	Storm Sewer - 18" RCP	LF	150	\$	80.00	\$	12,000.00
44	15" RCP Apron Endwall W/out Pipe Gate	EA	1	\$	1,200.00	\$	1,200.00
45	Storm Sewer Manhole - 48"	EA	3	\$	4,250.00	\$	12,750.00
46	Storm Sewer Curb Inlet - 2' x 3' Precast Box W/ Frame & Grate	EA	2	\$	2,600.00	\$	5,200.00
47	Remove Existing Storm Sewer	LS	1	\$	2,000.00	\$	2,000.00
48	Stormwater Pond Outlet Structure	LS	1	\$	10,000.00	\$	10,000.00
49	Stormwater Management Pond	LS	1	\$	40,000.00	\$	40,000.00
		Subtotal - Storm Sewer & Storm Water Mgmt			\$	109,400.00	
		Contingency (10%)					10,940.00
			Professional Services (12%)				14,440.80
		Total -					134,780.80
Total - Stori Field Development						\$	573,445.00
		Contingency (10%)				57,344.50	
		Professional Services (12%)			_	75,694.74	
		Total -Stori Field Development					706,484.24
		Cost Per Unit				÷	44,155.27
	Cost Per Unit w/o Park Improvements						39,498.31

This Engineer's Opinion of Probable Cost is made on the basis of our experience and qualifications. It represents our best judgment as experienced and qualified design professionals based on our information available at the time the cost opinion is made. It should be recognized that Vierbicher Associates, Inc. does not have control over the cost of materials or services furnished by others, over market conditions, or contractors methods of determining their prices. Accordingly, Vierbicher Associates, Inc. cannot and does not guarantee that bids or actual costs will not vary from this opinion.

