

Request For Bids- Concrete Pad & walkway near the Woodman Aquatic Center Splash Pad for a future shelter.

Richland Center Park & Recreation Department

REQUEST FOR BIDS – CONCRETE SLAB AND WALKWAY FOR FUTURE SHELTER SITE

The Richland Center Park & Recreation Department is requesting bids for a 17 ft wide x 20 ft long concrete slab & 8 ft wide x average 7 ft long walkway connector at the Woodman Aquatic Center Splash Pad area for a future shelter.

REQUEST FOR BIDS – SITE PREP GRADING, GRAVEL BASE

The Richland Center Park & Recreation Department is requesting bids for site prep to include sod stripping & topsoil to subgrade, 6" compacted aggregate for a 17 ft wide x 20 ft long concrete slab & 8 ft wide x average 7 ft long walkway connector at the Woodman Aquatic Center Splash Pad area for a future shelter.

Site address: 1055 N. Orange (7th Street side) with a Site showing available Monday, July 22nd at 5:00pm.

If you have any questions, please contact Jodi Mieden at (608)604-6608 or (608)647-8108 ext. 7

Bid packets are available at the City Clerk's office.

Bids must be submitted no later than 1:00 pm on Thursday July 25th ,2024.

The Park & Recreation Department will review bids on Friday, July 26th. The Park Board will recommend to the Common Council who is expected to award the bid at the August 6th meeting. Desired completion date by May 10th, 2025.

Submit bids (clearly marked as Splash Pad Concrete slab & walkway) to:

ATTN: Jodi Mieden, Park & Recreation Department, 450 S Main St., Richland Center, WI 53581

OR email to: jodi.mieden@richlandcenterwi.gov

The City of Richland Center reserves the right to reject any and all bids. All bids are subject to City Council approval. The City of Richland Center is an equal opportunity employer.



Bid Specifications for site prep, concrete slab and walkway

Please include this initialed checklist with bid.

The following are the minimum specifications.

Yes No Initials

 X NA Site prep & grading, sod stripping & top soil to subgrade, elevation to mimic pool surface under chain link fence. Runoff free flow to 7th Street sidewalk.

 X NA 6" layer of compacted aggregate base.

X NA 5" thick concrete slab for shelter area with 12" wide thickened edges and post surrounds with 4ft control expansion joints. All thickened edges and post surrounds concrete to be 8" thick for concrete slab. Reinforced with 3/8" rebar 16" O.C. supported with concrete brick or rebar chairs.

X NA 5" thick concrete slab for walkway with 4ft control expansion joints. Reinforced with 3/8" rebar 16" O.C. supported with concrete brick or rebar chairs. Connecting to existing splash pad concrete.

X NA Concrete mix: 3/4" max aggregate and 6 bag mix. Air entrained.

X NA Curing compound per manufacturer's specifications.

 X NA Center point of slab to be positioned on center point of building end wall per drawing.



27589 US Hwy 14
Richland Center, WI 53581
(608) 647-3551
office@augelliconcrete.com

PRICE QUOTE FOR: Richland Center - Woodman Aquatic Center Splash Pad for future shelter

BID DATE: July 25, 2024 1:00 PM

Line #	Description	Quantity	Unit	Unit \$	Total
	17' Wide X 20' Long Concrete Slab 5" thick with 8" thickened edge with rebar	340.00	SF		
	8' Wide X 7" Long Pathway 5" thick with rebar	56.00	SF		
	Lump Sum	1.00	LS	\$10,000.00	\$10,000.00
	TOTAL AMOUNT OF BID				\$10,000.00

NOTE:

- All subgrade to be +1" under curb, -2" under sidewalk and within -1" for paving.
- Extra fill or base material to be supplied by others.
- No traffic control included.
- Each additional mobilization is \$1,500.00
- No excavation, removals, backfill or saw cuts are included in pricing unless they are listed as a pay item
- No cold weather protection is included in the pricing unless it is listed as a pay item
- No layout or staking included in the pricing unless it is listed as a pay item
- No Bond Money has been included in the above bid.
- A concrete washout spot is required. Augelli Concrete will not be responsible for concrete pick up.
- All invoices will be billed by actual quantities placed.

Please take notice: There will be only 1 return visit for any warranty work (punch list), whether you choose to do it right away or in 12 months from the date concrete work is completed. But only 1 trip back.

Additionally please note: Once you are on the schedule, you will need to give a 48 hour notice of cancellation if you will not be able to meet that schedule to allow us time to make other arrangements.

This quote is valid if accepted within 30 days or as otherwise stated on proposal. Please sign and return this proposal if accepting the quoted price.

ALSO PLEASE NOTE: All projects will need a MINIMUM of a 2 weeks notice of when we are to be on site due to the concrete shortage and scheduling issues the industry is currently experiencing.

Augelli Concrete & Excavating, LLC is an Equal Opportunity Employer and Union Contractor

Customer Acceptance:

Company

Authorized Signature and Date