



April 13, 2026

Ms. Darcy Perkins
Municipal Services Specialist
City of Richland Center, WI

Re: Leachate Collection System Jetting

Jet Leachate Collection System

It is estimated that there is approximately 3,000 feet of 4-inch leachate collection pipes at the Richland Center Landfill. It is assumed that water can be obtained on-site or from a nearby source. Superior Jetting will provide a two-person jetting crew, high pressure jetting equipment that operates at approximately 7,000 PSI with hoses up to 1,100 feet long, and two trucks with 1,000- or 2,000-gallon water tanks at a rate of \$440.00 per hour. It is estimated that it will take 4 hours to jet the pipes in the landfill. If major blockages are encountered, site personnel will be notified. If additional time is needed to remove the blockages it will be billed at the hourly rate. After the job is completed, the customer will receive a detailed report describing the pipes and distance jetted, and conditions encountered.

Attached is a summary of the cost for work described in this proposal. Please call me at 763-498-4064 if you have any questions regarding this estimate.

Sincerely,

Brent Weaver
Superior Jetting
President

Cost Estimate Richland Center Landfill 2026

Jet Leachate Collection System

The cost estimate for jetting approximately 3,000 feet of leachate collection pipe is based on a two-person jetting crew, high pressure jetting equipment, and water shuttle truck at a rate of \$440.00 per hour for an estimated 4 hours.

Estimated Cost	\$ 1,760.00
----------------	-------------

Mobilization & Lodging

Approximately 12 hours of mobilization is required from our shop near Princeton, MN to and from Richland Center, WI. Mobilization is charged at a rate of \$235.00 per hour. This mobilization of equipment, crew, and lodging if required.

Cost	\$ 2,820.00
------	-------------

Total Cost	\$ 4,580.00
-------------------	--------------------