Corrosiveness of H2S requires more frequent service including the cleaning of points and contacts to keep the station operational.





The compromised structural integrity of the electrical panel is causing it to lean under the weight of electrical components. Public Works is out of viable locations from which to brace the existing panel.





Further evidence of the corrosiveness H2S can be seen on the main disconnect and meter can that compromises a weather-tight seal crucial for safe operations.

