

CERTIFIED SURVEY MAP

Being Outlot 1 of Jarvis Addn. as recorded in Plat Cabinet A on page 423, Iowa County Certified Survey Map 1182 recorded as Document 306260, and part of the SW 1/4 and SE 1/4 of the SW 1/4, all in Section 11, T6N, R4E, Village of Ridgeway, Iowa County, Wisconsin

SURVEYOR'S CERTIFICATE:

I, Laurence E. Schmit, Professional Land Surveyor hereby certify that under the direction of Jon Husom, I have made a survey, division, and map. Subject map is a correct representation of all the exterior boundaries of the land surveyed and the division thereof, and that I have fully complied with the provisions of Chapter 236.34 of the Wisconsin Statutes in the dividing, mapping of the land which is described as being Outlot 1 of Jarvis Addn. as recorded in Plat Cabinet A on page 423, Iowa County Certified Survey Map 1182 recorded as Document 306260, and part of the SW 1/4 and SE 1/4 of the SW 1/4, all in Section 11, T6N, R4E, Village of Ridgeway, Iowa County, Wisconsin


Commencing at the SW corner of Section 11, T6N, R4E, thence S 89°02'04" E, 295.05' along the south line of the SW 1/4 of the SW 1/4 to the POINT OF BEGINNING; thence N 44°10'41" W, 324.91' ; thence N 00°23'43" E, 618.09'; thence N 67°00'20"E, 295.07' to the NW corner of C.S.M. 1182; thence N 66°51'11" E, 701.83' to the northerly corner of C.S.M. 1182; thence S 59°11'23" E, 382.31' to the NW corner of lot 2 of said C.S.M. 1182; thence S 35°00'14" W, 261.25' to the most westerly corner of said C.S.M.; thence S 62°17'50" E, 248.42' to the most southerly corner of said lot 2 at the most westerly corner of lot 3 of C.S.M. 495; thence S 34°51'01" W, 60.68' to the most westerly corner of lot 4 of said C.S.M. 495; thence S 53°26'49" E, 107.71' along the westerly line of lot 4 of said C.S.M. 495 to a point 100' NW"ly of the northerly line of Wells Street; thence S 34°52'24" W, 481.72' to the north corner of lot 4 of Block J of Arthurs Map of the Village of Castleton as recorded in PLat Cabinet A on page 423; thence S 34°51'26" W, 267.94' to the Westerly corner of lot 1 thereof; thence N 88°32'11" W, 158.06' to a found #10 Rebar near the south line of the SW 1/4 of the SW 1/4; thence N 89°10'31" W, 558.58' to the POINT OF BEGINNING. Containing 1,248,913 square feet, or 28.671 acres, more or less.

VILLAGE OF RIDGEWAY
 Approved for recording by the Village of Ridgeway

sheet 2 of 2

_____ date:

Michele Casper - Pres.



NUMBER	BEARING	DISTANCE
L-51	N 44°10'41" W	324.91'
L-52	N 00°23'43" E	618.09'
L-53	N 67°00'20" E	295.07'
L-54	S 62°17'50" E	248.42'
L-55	S 34°51'01" W	60.68'
L-56	S 34°51'26" W	267.94'
L-57	N 88°32'11" W	158.06'
L-58	N 89°10'31" W	558.58'
L-59	S 53°26'49" E	107.71'