

CORPORATION STOP-

INSTALLATIONS SHALL CONFORM WITH MUNICIPAL WATER WORKS SPECIFICATIONS AND STANDARDS.

Corporation/Curb Stop with Box

1. PIPE AND FITTING MATERIALS TO BE PVC SDR35, MEETING ASTM 3034 FOR USE WITH SANITARY SEWER SYSTEMS.


Typical Wye and Chimney Detail (Residential)

ADAPTOR TO BE PREMANUFACTURED UNIT FOR CONNECTION OF PIPE TYPES.

CATCH BASIN GRATE-Notes: 1" REBAR FOR . ALL SECTIONS SHALL BE DESIGNED BAG REMOVAL SILTSACK — FOR HS-20 LOADING. DIAMETER OF STRUCTURES SHALL BE COORDINATED WITH PIPE CONFIGURATIONS. 2. COPOLYMER MANHOLE STEPS SHALL BE INSTALLED AT 12" O.C. FOR THE FULL DEPTH OF THE STRUCTURE. **Alternate Top Slab** 3. PROVIDE OPENINGS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS. JOINT SEALANT BETWEEN PRECAST SECTIONS SHALL BE PREFORMED BUTYL RUBBER. Plan View SEE NOTE 5. CATCH BASIN GRATE-5. DRAIN MANHOLE FRAME AND COVER SHALL BE SET IN FULL MORTAR BED. SPECIFICATIONS. ADJUST TO GRADE WITH CLAY BRICK AND MORTAR (2 BRICK COURSES SILTSACK-TYPICALLY, 5 BRICK COURSES MAXIMUM) 3. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER. -SHELF TO BE CONCRETE FORMED AT A SLOPE OF 1" PER FOOT. LEXPANSION RESTRAINT Section View **Notes:** INSTALL SILTSACK IN ALL CATCH BASINS WHERE INDICATED ON THE PLAN BEFORE COMMENCING WORK OR IN PAVED AREAS AFTER BINDER COURSE IS PLACED AND HAY BALES HAVE BEEN REMOVED. 2. GRATE TO BE PLACED OVER SILTSACK. 3. SILTSACK SHALL BE INSPECTED PERIODICALLY AND AFTER ALL --- CEMENT CONCRETE INVERT STORM EVENTS AND CLEANING OR REPLACEMENT SHALL BE PERFORMED PROMPTLY AS NEEDED. MAINTAIN UNTIL UPSTREAM ——COMPACTED GRAVEL AREAS HAVE BEEN PERMANENTLY STABILIZED Siltsack Sediment Trap Drain Manhole (DMH)

N.T.S.

Source: VHB



1. USE METALLIC TRACING/WARNING TAPE OVER ALL PIPES.

PIPE BEDDING MATERIAL SHALL EXTEND FROM A HORIZONTAL PLANE THROUGH

THE PIPE AXIS TO 6 INCHES BELOW THE BOTTOM OF THE PIPE'S OUTSIDE B. PIPE BLANKET MATERIAL SHALL COVER THE PIPE A MINIMUM OF 12 INCHES

ABOVE THE CROWN OF THE PIPE'S OUTSIDE SURFACE. . COMPACTION SHALL BE IN 6 INCH (MAX) LAYERS FOR BEDDING MATERIALS

MATERIALS AND 12 IN (MAX) LAYERS FOR BLANKET MATERIALS.


3. MAXIMUM ALLOWABLE TRENCH WIDTH AT A PLANE 12 INCHES ABOVE THE PIPE SHALL BE 36 INCHES (PIPE DIAMETERS UP TO 15 INCHES).

WATER LINES SHALL BE LOCATED AT LEAST 10—FT HORIZONTALLY FROM SEWER LINES. A MINIMUM VERTICAL SEPARATION OF 18—IN SHALL BE PROVIDED WHERE SEWER AND WATER LINES CROSS AND THE WATER LINE SHALL BE LOCATED ABOVE THE SEWER LINE.


INSTALL INSULATION ABOVE SEWER LINES WHEN THEY CROSS UNDER DRAIN LINES WITHIN 10-FT OF A DRAINAGE STRUCTURE. INSULATION SHALL BE 2-IN (MIN.) RIGID INSULATION PLACED 30-IN (MIN.) ACROSS THE TRENCH AND SHALL EXTEND 5-FT ON EITHER SIDE OF THE CROSSING.

Sewer Trench 7/06 N.T.S. LD_300S-NH Source: VHB


NO.:



LD_115



5.CONNECTIONS DIRECTLY INTO THE EXISTING PIPE WITHOUT A SADDLE OR A FULL WYE FITTING ARE NOT ALLOWED. 6.TO BE USED IF AN EXISTING WYE IS NOT FOUND.



1. ALL MATERIAL TO MEET FILTREX 2. FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.


-2" X 2" X 36" WOODEN STAKES PLACED 10' O.C. FILTREX SOCK (12" TYPICAL) WORK AREA SECTION NTS


2" X 2" X 36" WOODEN STAKES PLACED 10' O.C. AREA TO BE PROTECTED (12" TYPICAL) WORK AREA PLAN NTS

FILTREX EROSION CONTROL

EROSION CONTROL NOTES:

- 1) PRIOR TO STARTING ANY OTHER WORK ON THE SITE, THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES AND SHALL INSTALL EROSION CONTROL MEASURES AS SHOWN ON THE PLANS AND AS IDENTIFIED IN FEDERAL, STATE, AND LOCAL APPROVAL DOCUMENTS PERTAINING TO THIS PROJECT.
- 2) CONTRACTOR SHALL INSPECT AND MAINTAIN EROSION CONTROL MEASURES, AND REMOVE SEDIMENT THEREFROM ON A DAILY BASIS AND WITHIN TWELVE HOURS AFTER EACH STORM EVENT AND DISPOSE OF SEDIMENTS IN AN UPLAND AREA SUCH THAT THEY DO NOT ENCUMBER OTHER DRAINAGE STRUCTURES AND PROTECTED AREAS.
- 3) CONTRACTOR SHALL PERFORM CONSTRUCTION SEQUENCING SUCH THAT EARTH MATERIALS ARE EXPOSED FOR A MINIMUM OF TIME BEFORE THEY ARE COVERED, SEEDED, OR OTHERWISE STABILIZED TO PREVENT EROSION.
- 4) UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF PERMANENT GROUND COVER, CONTRACTOR SHALL REMOVE AND DISPOSE OF EROSION CONTROL MEASURES AND CLEAN SEDIMENT AND DEBRIS FROM ENTIRE DRAINAGE AND SEWER SYSTEMS. 5) ALL MATERIALS AND STOCKPILES SHALL BE STORED ON UPLAND AREAS. STOCKPILES SHALL
- BE SURROUNDED BY FILTER SOCK, SHALL HAVE HAVE SIDE SLOPES NO GREATER THAN 30%, AND SHALL BE SEEDED OR STABILIZED IF LEFT UNDISTURBED FOR TWO WEEKS OR MORE.
- 6) ALL DISTURBED SLOPE SURFACE SHALL BE SEEDED W/ NEW ENGLAND WILD FLOWER MIX ON EROSION CONTROL MAT. APPLICATION RATE: 1 LB / 2500 SF OR OTHERWISE NOTED.
- 7) FILTER SOCK FILTER MATERIAL SHALL BE COMPOSITE MULCH.
- 8) SEDIMENT CONTROL MEASURES SHALL BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF AND DURING ALL PHASES OF CONSTRUCTION AND BE CONSTRUCTED PRIOR TO AND IMMEDIATELY AFTER ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON THE
- 9) PERIODIC INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL STRUCTURES SHALL BE PROVIDED TO ENSURE THAT THE INTENDED PURPOSE IS ACCOMPLISHED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SEDIMENT LEAVING THE LIMIT OF WORK. SEDIMENT CONTROL MEASURES SHALL BE IN WORKING CONDITION AT THE END OF EACH WORKING DAY.
- 10) ANY SEDIMENT TRACKED ONTO PAVED AREAS SHALL BE SWEPT AT THE END OF EACH WORKING
- 11) ALL SEDIMENT RETAINED BY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE LEGALLY
- 12) DUST SHALL BE CONTROLLED BY WATERING OR OTHER APPROVED METHODS AS DIRECTED BY
- 13) THE CONTRACTOR SHALL USE TEMPORARY SEEDING, MULCHING, OR OTHER APPROVED STABILIZATION MEASURES TO PROTECT EXPOSED AREAS DURING PROLONGED CONSTRUCTION OR OTHER LAND DISTURBANCE. STOCKPILES THAT WILL BE EXPOSED FOR LONGER THAN 14 DAYS






TYPICAL 1-1/2" WATER SERVICE CONNECTION

Sewer Saddle Connection

N.T.S.



2. USE METALLIC TRACING/WARNING TAPE OVER ALL PIPES.

3. PAVEMENT SECTION TO CONFORM TO TOWN OF BRAINTREE DEPARTMENT OF PUBLIC WORKS (DPW) SPECIFICATION.

		REVISIONS:
	DATE:	COMMENTS:
∥ R		

EROSION CONTROL & DETAILS 913 NORTH STREET RANDOLPH, MASSACHUSETTS

DATE: 8-7-2025 DRAWN BY: DTM DESIGNED BY: CYM CHECKED BY: CYM



1285 WASHINGTON STREET WEYMOUTH, MA (781) 335-1464

ROADWAY BOX SEE DETAIL (F2-9)

PREPARED FOR: PERMITTING

SHEET C-2