



## ROOFING & GUTTER ESTIMATE

HOME OWNER:	DATE: 04/23/2023	CONTRACTOR:
NAME/NAMES: Jim Withers		NAME: Andrew Kellogg
HOME ADDR: 531 S. 7th St		ADDRESS: P.O. BOX 966
CITY, STATE, & ZIP CODE: Rochelle IL, 61068		CITY & STATE: DeKalb IL, 60115
CELL OR HOME: 847-331-6798		CELL: # (815) 501-3282
EMAIL:		EMAIL: Dekalbroofing@gmail.com

SALESPERSON	JOB SHORT DESCRIPTION	PAYMENT TERMS	DUE DATE
Andrew Kellogg	Tear-Off Shingles/Re-Shingle Roof/Clear Grave Of Flat Roof For New EPDM Flat-Roof Material/New Gutters For Building	50% Due Upon Signing/50% Due On Job Completion	UPON SIGNING
QUANTITY	DESCRIPTION / MATERIAL	LINE TOTAL	
88 Square Total	CertainTeed Limited Lifetime Architectural Shingles (50 YEAR) (LANDMARK)		
22 Rolls	CertainTeed Ice & Water Shield along all Gutter Lines & Valleys, 6 Feet up		
8 Rolls	CertainTeed RooferSelect Asphalt Saturated Felt, Or Choice of Synthetic Felt		
7 Bundles	CertainTeed ShadowRidge Ridge Cap to all Hip and Peak Ridges		
5 Bundles	CertainTeed SwiftStart Starter Strips to all Rake & Eave Edges		
27, 12' Pieces	Color-Matching Aluminum O.D.E (Outside Drip Edge) to all Rake Edges		
35, 12' Pieces	Color-Matching Aluminum Gutter Apron to all Eave Edges		
6 Boots	Plumbing Boot will be Installed on Each Vent Pipe(s) <input checked="" type="checkbox"/> Rubber <input type="checkbox"/> Lead <input type="checkbox"/> Galvanized		
135' Feet	Choice of Veticalation <input type="checkbox"/> Box Vents <input checked="" type="checkbox"/> Ridge Vent		
N/A	Replacement of Specialty Vents <input type="checkbox"/> Broan Vent <input type="checkbox"/> Turbine Vent <input type="checkbox"/> Power Vent		
15 Sheets	If it Exceeds 15 Boards there will be a charge per-sheet		
160' Feet	Seamless 5" Aluminum Hanging Gutters, 3x4" Aluminum Downspouts, With all Assessories		
N/A	Flat-Roof Material For Go Over's Or Full Replacement <input checked="" type="checkbox"/> E.P.D.M <input type="checkbox"/> GACO <input type="checkbox"/> Flintlastic		
35 Square Total	Solid & Vented Soffit, Fascia Can Be Custom Bent If Needed		
As Needed	Flashing For Brick Chminey, Roof To Wall, Or Baby Tins Will be used As Needed		
N/A	Replacement of Skylight, Or Flashing Kit With Ice&Water to be used on Existing Skylight		
130 Square Total	Materials from Roof to be Removed and Disposed Of		
Entire Site	Clean-Up, Roof & Grounds Around the Property using Magnets, Brooms, and Rakes		

X:		<b>SUBTOTAL</b>	<b>\$ 66,550.00</b>
		<b>50% DEPOSIT</b>	<b>\$ 33,275.00</b>
		<b>50% REMAINING</b>	<b>\$ 33,275.00</b>
		<b>TOTAL</b>	<b>\$ 66,550.00</b>
Signature Of Home Owner			
DATE:		<b>ACCEPTANCE NOTICE</b> You are hereby authorized to furnish all materials and labor required to complete the work mentioned in the above proposal. Any alteration or deviation from the above specifications involving extra cost of material or labor will become an extra charge over the sum mentioned in this contract. Homeowner recognizes this form as a legally binding contract.	
X:			
Signature Of Contractor			